



Finnish Network Statement 2008



FINNISH RAIL
ADMINISTRATION



Finnish Rail Administration

Finnish Network Statement 2008

ISBN 952-445-169-7 (stapled)

ISBN 952-445-170-0 (PDF)

ISSN 1459-3831

Cover layout: Proinno Design Oy, Sodankylä

Cover photo: Olavi Huotari

Print: Kopijyvä Oy, Kuopio

Helsinki 2006

Foreword

The Finnish Rail Administration (RHK) publishes this Network Statement for the timetable period 2008. This is the fifth Network Statement prepared in Finland, in accordance with the Finnish Railway Act. The Network Statement describes the access conditions, the state-owned rail network, the allocation capacity, the services supplied to railway undertakings and the principles of determining the infrastructure charge. The Network Statement is published for applicants for capacity for each timetable period separately. The present Network Statement is intended for the timetable period 9 December 2007 – 13 December 2008.

The Network Statement 2008 has been prepared based on the previous Network Statement taking into account the feedback received from users and the Network Statements of other European Infrastructure Managers.

The structure of the Network Statement follows the common European structure and comprises the following chapters:

- General
- Access conditions
- Rail network
- Capacity allocation
- Services supplied to railway undertakings
- Infrastructure charge

Within the Finnish Rail Administration, the Network Statement is the responsibility of the Traffic Management Unit. All the departments of the Finnish Rail Administration and several outside specialists have been involved in the preparation of the Network Statement.

Helsinki, 27 November 2006

Finnish Rail Administration

Table of Contents

FOREWORD 3

1 GENERAL INFORMATION 7

1.1 Introduction..... 7

1.2 Objective..... 7

1.3 Legal Framework..... 7

1.4 Legal Status 8

1.4.1 General Remarks..... 8

1.4.2 Liability..... 8

1.4.3 Appeals Procedure..... 8

1.5 Structure of the Network Statement 8

1.6 Validity and Updating 8

1.6.1 Validity Period 8

1.6.2 Updating..... 8

1.7 Publishing..... 8

1.8 Contacts 9

1.9 Co-operation between Infrastructure Managers 10

1.10 Glossary..... 12

2 ACCESS CONDITIONS 13

2.1 Introduction..... 13

2.2 General Access Requirements 13

2.2.1 General Requirements for Operating Railway Traffic 13

2.2.2 General Requirements for Access to the Rail Network 14

2.2.3 Operating Licence 14

2.2.4 Safety Certificate 14

2.2.5 Insurance..... 15

2.3 How to Apply for a Train Path 15

2.4 General Business Conditions 15

2.4.1 Framework Agreement 15

2.4.2 Access Contracts..... 16

2.5 Operational Rules..... 16

2.6 Exceptional Transport 16

2.7 Dangerous Goods..... 16

2.8 Rolling Stock Acceptance Guidelines 16

2.9 Safety Acceptance 16

3 INFRASTRUCTURE..... 17

3.1 Introduction..... 17

3.2 Extent of Network..... 17

3.2.1 Limits 17

3.2.2 Connected Railway Networks 17

3.3 Network Description 17

3.3.1 Geographic Identification..... 17

3.3.2 Capabilities 17

3.3.3 Traffic Control and Communications Systems 21

3.4 Traffic Restrictions 22

3.4.1 Specialised Infrastructure 22

| | | |
|-------|--|----|
| 3.4.2 | Environmental Restrictions | 22 |
| 3.4.3 | Dangerous Goods | 22 |
| 3.4.4 | Tunnel Restrictions | 23 |
| 3.4.5 | Bridge Restrictions | 23 |
| 3.5 | Availability of the Infrastructure | 23 |
| 3.6 | Passenger Stations | 23 |
| 3.7 | Freight Terminals | 23 |
| 3.8 | Service Facilities..... | 23 |
| 3.8.1 | Train Formation Yards..... | 23 |
| 3.8.2 | Storage Sidings | 23 |
| 3.8.3 | Maintenance and Service Facilities..... | 23 |
| 3.8.4 | Refuelling Facilities | 23 |
| 3.8.5 | Technical Equipment | 23 |
| 3.9 | Infrastructure Development | 23 |
| 4 | CAPACITY ALLOCATION | 24 |
| 4.1 | Introduction..... | 24 |
| 4.2 | Description | 24 |
| 4.3 | Schedule for Train Path Requests and Allocation Capacity Requests | 25 |
| 4.3.1 | Schedule for Working Timetable | 25 |
| 4.3.2 | Requesting Infrastructure Capacity for Temporary Traffic..... | 25 |
| 4.4 | Allocation | 26 |
| 4.4.1 | Coordination | 26 |
| 4.4.2 | Dispute Resolution..... | 26 |
| 4.4.3 | Congested Infrastructure | 26 |
| 4.5 | Allocation of Capacity for Maintenance, Renewal and Enhancements | 27 |
| 4.6 | Non-usage Rules | 28 |
| 4.7 | Exceptional Transport and Dangerous Goods | 28 |
| 4.8 | Special Measures to be Taken in the Event of Disturbance | 28 |
| 4.8.1 | Principles | 28 |
| 4.8.2 | Operational Regulation | 28 |
| 4.8.3 | Foreseen Problems | 28 |
| 4.8.4 | Unforeseen Problems..... | 28 |
| 5 | SERVICES | 29 |
| 5.1 | Introduction..... | 29 |
| 5.2 | Services Offered by RHK | 29 |
| 5.3 | Services Offered by Others..... | 29 |
| 6 | CHARGES | 30 |
| 6.1 | Charging Principles and Services Included in the Infrastructure Charge..... | 30 |
| 6.2 | Infrastructure Charge System | 30 |
| 6.3 | Tariffs | 30 |
| 6.4 | Incentive System for the Charges..... | 30 |
| 6.5 | Changes to Charges..... | 30 |
| 6.6 | Billing Arrangements | 30 |

Index..... 31

Appendices

Appendix 1: Infrastructure Register.....32

Appendix 2: Railway Traffic Operating Point Register39

Appendix 3: Transport Operating Regulations
for the Tornio–Haaparanta Section of Line..... 89

Appendix 4: Loading Gauge 97

Appendix 5: Structure Gauge 98

Appendix 6: Line Categories and Permitted Speeds
for Different Axle Loads99

Appendix 7: Signalling Systems107

Appendix 8: Vibration-related Speed Restrictions 112

Appendix 9: Maximum Permitted Train Speeds in Tunnels 113

Appendix 10: Bridge-related Restrictions..... 114

Appendix 11: Significant and Other Track Works
Affecting Traffic in 2008 115

Appendix 12: Passenger Information at the Stations of
the State-owned Rail Network 118

Appendix 13: Network Statements of Other Countries 119

1 General Information

1.1 Introduction

The Network Statement is published in accordance with the Railway Act (555/2006) and Directive 2001/14/EC of the European Parliament and of the Council on the allocation of railway infrastructure capacity and the levying of charges for the use of railway infrastructure and safety certification (hereinafter referred to as the "Capacity and Infrastructure Charge Directive"). The Network Statement for the timetable period 2008 is the fifth Network Statement published in Finland.

1.2 Objective

The Network Statement is published for the use of applicants for capacity. Railway undertakings can request capacity for international traffic within the European Economic Area, as well as for domestic freight traffic. Domestic passenger traffic may be operated only by VR Ltd.

The Network Statement describes the access conditions, state-owned rail network, capacity allocation, services supplied to railway undertakings and the basis on which the infrastructure charge is determined. The Network Statement specifies in detail the general rules, deadlines, procedures and grounds applicable to capacity allocation and the charging systems.

1.3 Legal Framework

Current Legislation

In accordance with the Railway Act, RHK publishes information on the provisions of the Railway Act, as well as on the provisions issued under this Act and other provisions, concerning

- 1) the right of access to the rail network;
- 2) the principles of determining the infrastructure charges;
- 3) applying for infrastructure capacity and the related deadlines;
- 4) the requirements for and approval of railway rolling stock; as well as
- 5) other conditions concerning operating and starting the operation of rail traffic.

RHK publishes information on the nature and extent of the rail network in the Network Statement for each timetable period. This information is contained in Chapter 3 of this Network Statement. The provisions issued by RHK on:

- 1) specialised infrastructure under the Railway Act (point 3.4.1);
- 2) the priority order to be applied to congested infrastructure under the Railway Act (point 4.4.3);
- 3) the threshold quota for the minimum use of railway infrastructure on each train path under the Railway Act (point 4.6) are also published in the Network Statement.

1.4 Legal Status

1.4.1 General Remarks

The Network Statement is not a regulation issued by RHK but a document providing information.

1.4.2 Liability

Information published in the Network Statement does not affect regulations issued by RHK or Finnish Rail Agency.

1.4.3 Appeals Procedure

A decision taken by RHK may be appealed against under the Railway Act by filing a claim for rectification with the Regulatory Body, which in Finland is the Finnish Rail Agency. A claim for rectification may be filed if the decision taken by the Finnish Rail Agency concerns:

- 1) priority order for allocating capacity in individual cases;
- 2) levying of the infrastructure charge;
- 3) capacity allocation;
- 4) allocation of urgently needed capacity;
- 5) issuing the certificate of conformity or inspection certificate of the notified body

The claim for rectification shall be filed with the the Finnish Rail Agency within 30 days of the date of receipt of notice of the decision. The Finnish Rail Agency shall decide on the claim for rectification within two months of the date on which all relevant information for taking a decision has been delivered to it. The decision shall, however, be taken within ten days of the date on which all relevant information has been delivered if the claim concerns the priority order in individual cases, capacity allocation or a request for urgently needed capacity.

1.5 Structure of the Network Statement

This Network Statement follows the common structure set for network statements by RailNetEurope.

The Network Statement consists of five more chapters in addition to this one. The second chapter deals with the requirements for accessing the Rail Network, the third handles the rail network infrastructure, the fourth covers issues related to capacity allocation, the fifth chapter is about services offered to railway undertakings, and the sixth chapter deals with the infrastructure charge and charging principles. The Network Statement includes appendices that provide a more detailed description of the rail network features and other issues related to rail traffic operations.

1.6 Validity and Updating

1.6.1 Validity Period

The Network Statement is valid for one timetable period. It is published four months ahead of the expiry of the deadline for submission of capacity requests, that is 12 months ahead of the timetable period. The Network Statement 2008 is intended for the timetable period 2008, that is, for the period 9.12.2007–13.12.2008. The Network Statement for the timetable period 2009 will be published by 7.12.2007 at the latest.

1.6.2 Updating


If information contained in item 1.3 changes, RHK will publish the changes in its publications.

The Appendix 11 of the Network Statement presents an estimate of the railway work that is to be done during the timetable period 2008 and which may affect traffic. The working programme, timing of tasks and the required railway work will change as the funding and plans become more focused. The Finnish Rail Administration will publish the list of railway work and maintain an updated version of the document on their Internet pages at <http://www.rhk.fi>.

1.7 Publishing

The Network Statement is published in three languages: Finnish, Swedish and English. If any discrepancies are found between the different language versions, the Finnish language version will prevail. The Finnish version of the Network Statement can be obtained in printed form from the Finnish Rail Administration and all language versions are available in PDF format on the Finnish Rail Administration's Internet pages at <http://www.rhk.fi>.

Development plans for the rail network for 2008–2011 are presented in RHK's Action and Financial plan (TTS) of RHK. Statistics concerning the rail network and railway traffic are presented in the annually published Finnish Railway Statistics.



Picture 1. Finnish Rail Administration's organisational chart.

1.8 Contacts

Finnish Rail Administration

The Finnish Rail Administration is a department subject to the Ministry of Transport and Communications. It is responsible for the maintenance and development of Finland's rail network, railway capacity allocation and traffic control.

Finnish Rail Administration
PO Box 185 (Keskuskatu 8)
FI-00101 Helsinki

Telephone: +358 20 751 5111
Fax. +358 20 751 5100
E-mail: info@rhk.fi, kirjaamo@rhk.fi
Internet: <http://www.rhk.fi>

On traffic related issues, please send your messages to the following e-mail address: oss@rhk.fi.

Other contact information can be found on RHK's Internet pages.

Ministry of Transport and Communications

PO Box 31 (Eteläesplanadi 16–18)
FI-00023 Government

Telephone: +358 9 160 02
Fax. +358 9 160 28596
E-mail: kirjaamo@mintc.fi
Internet: <http://www.mintc.fi>

Finnish Rail Agency

The Finnish Rail Agency is subject to the Ministry of Transport and Communications. It monitors general railway safety, the safety of railway systems and the safety of railway undertakings' and Finnish Rail Administrations' operations.

PO Box 84 (Jaakonkatu 3)
FI-00101 Helsinki

Telephone: +358 20 776 7611
Fax: +358 20 776 7630
E-mail: kirjaamo@rvi.fi
Internet: <http://www.rautatievirasto.fi>

Finnish Competition Authority

The Finnish Competition Authority operates under the Ministry of Trade and Industry. Its objective is to protect sound and effective economic competition and increase economic efficiency by promoting competition and abolishing competition restraints.

PO Box 332 (street address: Pitkänsillanranta 3 A)
FI-00531 Helsinki

Telephone: +358 9 731 41
Fax: +358 9 7314 3328
E-mail: kirjaamo@kilpailuvirasto.fi
Internet: <http://www.kilpailuvirasto.fi>

1.9 Co-operation between Infrastructure Managers

In January 2004, the European railway infrastructure managers established a common organisation to shape the business of European rail infrastructure. RailNetEurope or RNE is an organisation whose goal is to promote international traffic in the European railway infrastructure and sell and market the railway capacity managed by its members.

Instead of engaging in bilateral or multilateral co-operation, the European railway infrastructure managers established a single organisation, RNE, to represent all of its members from the European perspective. The goal is to harmonise regulations and promote European rail traffic, and in so doing benefit every member.

RNE consists of 29 members, either full or associated members or candidates. All in all RailNetEurope partners serve a network of around 230,000 km railway infrastructure. Also a ferry line has joined the association and contributes to lowering the barriers in international rail traffic. RNE's main target group consists of customers engaging in international business. The Infrastructure Managers involved in RailNetEurope today take care of 120 customers dealing with international business and over 300 companies involved in national rail traffic.

The RNE members have set up One Stop Shops (OSS) working as a network of customer contact points. For international path requests, the customer needs to contact only one of these OSS, which will coordinate the whole international path allocation process.

One Stop Shop

- Offers the customer support and information on the full product and service range of the Infrastructure Managers.
- Supplies all the information required to gain access to the infrastructure of any Infrastructure Manager participating in RNE.
- Handles requests for any international train path within RNE.
- Ensures that requests for the next timetable period are duly taken into account in the annual timetabling process.
- Provides train path offers for the whole international journey.

Each OSS contact is part of the international network aiming at making network access for customers as simple as possible. The OSS also provides information on infrastructure charges and train movements including quality monitoring. The OSS provides competent and efficient assistance across all borders, based on transparent, confidential and non-discriminatory procedures. The contact information of railway infrastructure managers' OSS contacts can be found on the RailNet-Europe's Internet pages at <http://www.railneteurope.com>.

RailNetEurope members include:

- Administrador de Infraestructuras Ferroviarias (ADIF) (Spain)
- Banedanmark (Denmark)
- Banverket, Swedish National Rail Administration (BV) (Sweden)
- BLS Lötschbergbahn AG (BLS) (Switzerland)
- České Dráhy (CD) / SZCD (Czech)
- Chemins de fer Hélieniques / Hellenic Railways (CH-OSE) (Greece)
- Compania Nationala De Cai Ferate S.A. (CFR) (Romania)
- DB Netz AG (Germany)
- Eurotunnel (France / England)
- Győr-Sopron-Ebenfurti Vasút Rt. / Raab-Oedenburg-Ebenfurter Eisenbahn AG (Austria / Hungary)
- Infrabel (Belgium)
- Jernbaneverket (JBV) (Norway)
- National Railway Infrastructure Company (NRIC) (Bulgaria)
- Network Rail (Great Britain)
- PKP Polskie Linie Kolejowe S.A. (PKP-PLK) (Poland)
- ProRail B.V. (the Netherlands)
- Public Agency for Rail Transport of RS (ŽPZP) (Slovenia)
- Finnish Rail Administration (RHK) (Finland)
- Rede Ferroviária Nacional E.P. (REFER) (Portugal)
- Réseau Ferré de France ja Société Nationale des Chemins de fer Français (France)
- Rete Ferroviaria Italiana SpA (RFI) (Italy)
- Scandlines Deutschland GmbH (Germany / Sweden)
- Société Nationale des Chemins de Fer Luxembourgeois (CFL) (Luxemburg)
- Swiss Federal Railways SBB-Infrastruktur (SBB CFF FFS) (Switzerland)
- SZ Holding Slovenske železnice d.o.o. Infrastructure (SZ) (Slovenia)
- Trasse Schweiz AG/Swiss Train Paths Ltd. (Switzerland)
- Vasúti Pályakapacitás-elosztó Kft. (VPE) (Hungary)
- Železnice Slovenskej republiky (ZSR) (Slovakia)
- ÖBB Infrastruktur Betrieb AG (Austria).

Network Statements of Other Countries

Internet addresses and names of Network Statements published by other rail network administrators are listed in Appendix 13.

1.10 Glossary

- **Coordination** refers to a procedure by which RHK and the applicants attempt to solve situations where there are competing requests for infrastructure capacity.
- **Infrastructure capacity** refers to the capacity of a train path to carry train traffic over a particular period and depending on the characteristics of the rail network.
- **Infrastructure maintenance** refers to construction, maintenance and development of tracks, of structures, equipment and systems connected with them, as well as of real property needed for infrastructure maintenance.
- **Museum train traffic** refers to traffic operated on a small scale on the rail network by a non-profit association with museum trains or comparable rolling stock.
- **Private siding** refers to a track which is connected to the state-owned rail network according to the private siding connection permit. The connection permit is provided by the Finnish Rail Administration.
- **Railway undertaking** refers to a company or other association under private law whose main activity is to operate rail traffic. The company must have an appropriate operating licence issued in the European Economic Area and possess the rolling stock needed for operating traffic. Undertakings providing only traction services are also regarded as railway undertakings.
- **Traffic control** is the management of traffic on individual train paths. In addition traffic control duties include issuing train safety notices and permits required for train traffic. Traffic control personnel also receive information and issue permits for work done on or near the tracks and receive information on the termination of such work. The remote control operator or train dispatcher is responsible for the traffic control. If so required due to the volume of traffic and safety apparatus a signals or turnout worker, shunting foreman, engine driver or a worker responsible for the safety of work done near the tracks or other person appointed in due order for the task may participate in traffic control to the extent required by their task.

2 Access Conditions

2.1 Introduction

Access requirements to the rail network are listed in this chapter. The prerequisites for operating railway traffic are an operating licence, safety certificate or museum traffic operator's licence, allocated capacity and an access contract. In addition, for example, the rolling stock acceptance process and traffic safety staff qualifications are described in this chapter.

2.2 General Access Requirements

The legal framework of access to infrastructure is described in the Railway Act (555/2006). The provisions issued by the Finnish Rail Agency and RHK shall be observed on the state-owned rail network. Information on the provisions issued by the Finnish Rail Agency and RHK currently in force is available from the Finlex Data Bank, <http://www.finlex.fi>.

The Government Decree on safety and interoperability of the rail system (750/2006) lays down, for example, the essential requirements for the rail system. The essential requirements can be supplemented with separate provisions.

2.2.1 General Requirements for Operating Railway Traffic

Operation of rail traffic on the state-owned rail network requires that the railway undertaking and international grouping of railway undertakings meet the following conditions:

- 1) The railway undertaking or international grouping of railway undertakings shall have an operating licence issued by the Ministry of Transport and Communications in accordance with the Railway Act or a corresponding operating licence issued in the European Economic Area, unless the question is of museum train traffic referred to in the Railway Act.
- 2) The licence holder shall have a safety certificate in accordance with the Railway Act, issued or approved by the Finnish Rail Agency, which covers all the train paths on which traffic will be operated.
- 3) Capacity has been allocated to the railway undertaking for its traffic.
- 4) The licence holder shall make an access contract with RHK
- 5) Other conditions for operating rail traffic, laid down in or under the Railway Act are in all respects fulfilled.

Access conditions and phases for entering the market are presented in Figure 2.




Figure 2. Phases for entering the market

Museum Traffic

The same requirements described in this Network Statement are applied to museum train traffic as to other rail traffic, except with regard to the operating licence. The law provides that a museum traffic operator must have an operating licence granted by the Finnish Rail Agency, and that the licence corresponds with the railway undertaking's safety certificate. The operating licence will be granted upon application for a maximum of five years at a time. The prerequisite for granting the operating licence is that the museum traffic operator has sufficient liability insurance and risk management system, their rolling stock has been approved by the Finnish Rail Agency, and the persons attending to the traffic operation possess the required competence.

Capacity may be requested only as urgently needed capacity. RHK has drawn up instructions for museum train traffic operators for attending to certain matters regarding access to the network.

2.2.2 General Requirements for Access to the Rail Network

The following railway undertakings or international grouping of railway undertaking may access the state rail network to operate train traffic.

- 1) the railway undertakings and international groupings of railway undertakings referred to in the Railway Act providing domestic freight services or passenger services in international rail traffic between states belonging to the European Economic Area;
- 2) the rail transport operating subsidiary of the limited company referred to in the Act on the Incorporation of the Finnish State Railways (20/1995) for providing services in domestic passenger traffic, as well as in traffic between Finland and Russia.

These railway undertakings and international groupings of railway undertakings may use the rail network in accordance with the Railway Act and the traffic operating points on the state-owned rail network for their traffic operating on separately agreed conditions (access contract). Other undertakings or associations may also use individual traffic operating points on the rail network for their rail services, provided that this traffic serves a private siding connected to a traffic operating point and that an agreement on traffic operating has been made with RHK.

2.2.3 Operating Licence

The Ministry of Transport and Communications issues an operating licence for the operation of rail traffic to applicants established in Finland. The granted operating licence is valid for the time being and the Ministry reviews the operating licence and its conditions every five years. An operating licence issued in one state belonging to the European Economic Area is valid throughout the territory of the European Economic Area. An operating licence granted elsewhere must be delivered to the Ministry of Transport and Communications for information.

The prerequisite for granting the operating licence is that the main activity of the undertaking is to operate rail traffic. The undertaking must also have a safety certificate issued or approved by the Finnish Rail Agency, a solid financial standing, a competent management team and a sufficient liability insurance. The application for an operating licence is delivered to the Ministry of Transport and Communications.

2.2.4 Safety Certificate

The safety certificate is issued by the national safety authority. In Finland, it is issued by the Finnish Rail Agency. If the railway undertaking possesses a security certificate granted in another country in the European Economic Area, it need not apply for a new security certificate. The security certificate granted in another country must be approved by the Finnish Rail Agency. The security certificate will be granted or approved for a maximum of five years at a time. The undertaking must apply for a new security certificate as soon as its old certificate is no longer valid.

The purpose of the safety certificate is to ensure that the applicant fulfills the safety requirements for its operations and that the undertaking has the necessary qualifications to operate safely on the rail network. These requirements are presented in the Railway Act. It is also possible to include other requirements in the safety certificate regarding railway safety. The purpose of these requirements is ensure railway safety while taking into consideration the nature and scope of the railway traffic of the applicant. The aforementioned requirements are presented in more detail and explained in the instructions on how to apply for a safety certificate drawn up by the Finnish Rail Agency.

The Finnish Rail Agency requires information on:

- applicant's safety management system and other arrangements by the undertaking and its management ensuring that regulations concerning rail traffic safety are observed
- applicant's management and personnel in charge of traffic safety is competent and professionally trained
- applicant's rolling stock meets the set requirements and its service and maintenance has been properly arranged, and
- applicant has sufficient insurance or some other arrangement.

The Finnish Rail Agency has drawn up instructions on how to apply for a security certificate. The form used to apply for the security certificate can be obtained from the Finnish Rail Agency. The written application shall be submitted to the Finnish Rail Agency, which shall consider the application and if necessary request further information. The Finnish Rail Agency shall decide on the issuance or approval of the operating licence within four months after the request has been filed. The Finnish Rail Agency may grant a safety certificate for the entire state rail network or individual train paths. If the nature or scope of the undertaking or international grouping of railway undertakings changes fundamentally, it shall apply for a new safety certificate or request that the Finnish Rail Agency reapproves the safety certificate.

2.2.5 Insurance

A rail transport operator and a maintenance railway/work undertaking shall have sufficient liability insurance or other corresponding arrangement in case of such damage incurred by a party due to rail transport operations for which the operator a maintenance railway/work undertaking is by law or contract responsible. The nature and scope of operations and risks related to the operations must be taken into account in evaluating the sufficiency of the insurance or a similar arrangement. The insurance or other corresponding arrangement shall be in force for the duration of the entire period during which rail transport is operated.

2.3 How to Apply for a Train Path

A railway undertaking has to meet the following criteria to apply for rail capacity:

- The undertaking shall have an operating licence in conformity with the Railway Act or a corresponding licence issued in the European Economic Area unless it is a question of museum traffic referred to in the Railway Act.
- The undertaking shall, in compliance with the Railway Act, have a safety certificate for all the train paths on which the undertaking is planning to operate.

Applying for rail capacity and capacity allocation are described in Chapter 4 of the Network Statement.

2.4 General Business Conditions

2.4.1 Framework Agreement

RHK may make a framework agreement on the use of capacity with applicants for capacity. The purpose of such an agreement is to specify the characteristics of the capacity requested by the applicant. The framework agreement does not, however, entitle the applicant to obtain such capacity as is specified in the agreement.

Railway undertakings shall request the capacity specified in the framework agreement for each timetable period separately. RHK also allocates the capacity specified in the framework agreement following the procedure laid down in the Railway Act. Correspondingly, the access contract shall be concluded for each timetable period separately regardless of the framework agreement. The framework agreement does not, however, impede the application of the provisions of the Railway Act to other applicants for capacity.

The framework agreement is made for a maximum of five years. For special reasons, RHK may, however, also conclude framework agreements for a longer period. Conclusion of an agreement for more than five years can, however, be justified only by contracts, special investments or special business risks connected with the transport business of the party with which the agreement is concluded, as well as by the large-scale and long-term investments of the party with which the agreement is concluded or the contractual obligations connected with such activities.

2.4.2 Access Contract

Railway operators and museum traffic operator shall make an access contract with RHK on the use of necessary services with regard to the state rail network and operating railway traffic. These services include, for example, the use of marshalling yards, storage sidings and other tracks, as well as use of traffic control services. It is also possible to agree on other practical arrangements concerning railway traffic operations.

The railway traffic operator shall contact RHK to prepare the access contract and contractual negotiations as early as possible, preferably before applying for capacity. RHK makes this contract with each licence holder while taking into account the nature and scale of capacity allocated. The access contract is made for each timetable period and can be changed if decisions made during the timetable period concerning the allocation of capacity or other facts, for example, concerning the condition of the rail network so require. The access contract can only be concluded after all conditions stipulated in the Railway Act for operating railway traffic have been fulfilled. After the contract has been concluded, traffic may begin.

2.5 Operational Rules

Operational rules drafted by RHK can be viewed on the Finlex web site and other information on the RHK's and Finnish Rail Agency's web sites.

2.6 Exceptional Transport

Traffic restrictions are dealt with in item 3.4. Regulations concerning railway traffic and rolling stock can be viewed on the Finlex web site and other instructions on the Finnish Rail Agency and RHK web sites.

2.7 Dangerous Goods

Transport of dangerous goods is dealt with in item 3.4.3. Regulations concerning railway traffic and rolling stock can be viewed on the Finlex web site and other instructions on the Finnish Rail Agency and RHK web sites.

2.8 Rolling Stock Acceptance Guidelines

An authorisation issued by the Finnish Rail Agency is required for placing rolling stock in service. This authorisation can be issued for rolling stock that meets the requirements valid in Finland, which are laid down in legislation.

The requirements are based on the interoperability requirements for the rail system in accordance with Community law and the Finnish Rail Agency has issued complementary and more detailed instructions. Conformity can be proved by the EC Declaration of Conformity or a corresponding declaration issued within the European Economic Area.

In other cases, the Finnish Rail Agency is responsible for technical approval for the authorisation to place rolling stock in service.

The Finnish Rail Agency maintains a register used to monitor the validity and traffic safety of rolling stock. The purpose is to promote railway system safety and identify rolling stock. The rolling stock is recorded in a register maintained by the Finnish Rail Agency, if the rolling stock has been granted a commissioning licence in Finland. Rolling stock that will be used on the state's rail network and has been granted a commissioning licence elsewhere within the European Economic Area or in a country outside the EEA must also be recorded in the register. Any rolling stock used on private sidings will also be recorded in the register.

The Finnish Rail Agency can also register rolling stock for a limited time upon request. A fixed-period registration is also possible for any rolling stock that has been granted a commissioning licence in another country, if it has been granted a commissioning licence in Finland and is used on the state's railway network only temporarily.

The rolling stock register must include information on the owner, holder and renter of the rolling stock. The more detailed regulations on related information on other rolling stock to be recorded in the register will be set forth in a Council of State decree.

With regards to any rolling stock used for rail traffic between Finland and Russia, the register must include information on the vehicle owner or renter, any possible limitations on the vehicle use and information on the vehicle's maintenance plan in so far as is essential to the vehicle safety.

2.9 Safety Acceptance

Traffic safety staff shall meet the health, training and other qualification requirements laid down in Finnish legislation. Specific provisions on qualifications are laid down in the Traffic Safety Tasks Act which came into force on 1.1.2005. The Act lays down qualification requirements for personnel working with traffic safety tasks which have a direct impact on rail traffic safety. Those working in these tasks shall also meet the Finnish Rail Agency requirements concerning health, training and other qualifications. The qualification requirements vary depending on the job.

Before the Finnish Rail Agency issues or approves a safety certificate, the railway operator shall provide it with information on the qualifications of its traffic safety staff. An operator engaged in museum traffic must provide the Finnish Rail Agency with the corresponding information for issuing the operating licence. If necessary, the Finnish Rail Agency may upon issuing the safety certificate or operating licence examine in other ways and in more detail whether a person or persons employed by the railway traffic operator or otherwise connected to his or her operation meets the set qualifications.

3 Infrastructure

3.1 Introduction

The infrastructure refers to the state-owned rail network managed by RHK. RHK is responsible for infrastructure maintenance, that is, for the construction and maintenance of tracks, of structures and equipment connected with them, as well as of real property needed for infrastructure maintenance.

3.2 Extent of Network

3.2.1 Limits

The available network is presented graphically in Figure 3 (state-owned rail network in the beginning of timetable period 2008) and in Appendix 1 (Infrastructure Register).

The following line sections are closed to traffic:

- Kankaanpää–Niinisalo
- Kihniö–Aitoneva
- Raudanlahti–Säynätsalo
- Pesiökylä–Taivalkoski
- Kolari–Äkäsjoki
- Niesa–Rautuvaara.

The closure of the following line sections is planned for the timetable period 2008.

- Parkano–Niinisalo
- Parkano–Kihniö
- Kiukainen–Säkylä.

The following line sections are open to traffic in summer only (no snow ploughing, no maintenance of switches, no snow and ice clearance at level-crossings):

- Kiukainen–Säkylä.
- Isokylä–Kellosekä

3.2.2 Connected Railway Networks

There is a rail connection from Finland to Sweden via Tornio. The main outlines of traffic operating on the Tornio–Haaparanta line section are presented in Appendix 3. The Swedish infrastructure manager is Banverket.

A rail connection exists from Finland to Russia via Vainikkala, Imatrankoski, Niirala and Vartius. Rail traffic between Finland and Russia is based on the Rail Traffic Agreement between Finland and Russia. Traffic between Finland and Russia is not internal international traffic within the European Economic Area. Only VR Limited has access to the Finnish rail network in traffic between Finland and Russia.

3.3 Network Description

3.3.1 Geographic Identification

3.3.1.1 Track Typologies

The network is presented in Figure 3 (rail network map) and in the infrastructure register (Appendix 1).

3.3.1.2 Track Gauges

The nominal track gauge on the rail network 1,524 mm. The tolerance range is -10...+30 mm. The speed-dependent limit values for the track gauge are indicated in the RAMO publication, part 13 "Radan tarkastus" (Track inspection).

3.3.1.3 Stations and Nodes

The available traffic operating points (stations) are presented in Figure 4 (rail traffic operating points) and in Appendix 2 (Rail Traffic Operating Point Register).

The following traffic operating points are open for traffic in summer only (no snow ploughing, no maintenance of switches, no snow and ice clearance at level-crossings):

- Kauttua
- Säkylä.

3.3.2 Capabilities

3.3.2.1 Loading Gauge

The loading gauge (KU), Appendix 4, and the structure gauge (ATU) FIN1, Appendix 5, are used throughout the state-owned rail network. On private industrial sidings, there may be both loading and structure gauge limitations, which railway undertakings shall clarify separately for carrying out transportation.

The vehicle gauge (LKU) is specified in the LIMO publication, point 1 "Yleiset määräykset" (General rules).

3.3.2.2 Weight Limits

Axle loads

22.5 ton axle loads are permitted on most of the rail network. The maximum permitted axle loads per line section are indicated in Appendix 6 (Line Categories and Permitted Speeds for Different Axle Loads).

Metre Loads

The permitted metre load of rolling stock throughout the state-owned rail network is 8.0 tons/m.




Figure 3. State-owned rail network at the beginning of timetable period 2008.




Figure 4. Traffic operating points on the state-owned rail network at the beginning of timetable period 2008.

Euroopanlaajuinen rautatieverkko Suomessa
Europeiska bannätet i Finland
Trans-European Rail Network in Finland



Figure 5. The Finnish TEN network.

3.3.2.3 Line Gradients

The maximum gradient is 12.5 mm/m on the main lines and 22.5 mm on the secondary lines. The characteristic gradients of the line sections are indicated in Appendix 1 (Infrastructure Register).

3.3.2.4 Line Speeds

The maximum speed is 220 km/h for passenger trains and 120 km/h for freight trains. The speeds permitted for passenger and freight trains on the rail network are indicated in Appendix 6 (Line Categories and Permitted Speeds for Different Axle Loads).

3.3.2.5 Maximum Permitted Train Lengths

The maximum train length permitted on a line section shall be such that trains can also use secondary tracks at the traffic operating points. An agreement concerning the exceptional transport and other special transport must be made separately. Trains need not, however, be capable of using all secondary tracks at all traffic operating points. The train lengths used for dimensioning line sections are 550, 625, 725, 825 and 925 metres. The longest secondary tracks at each traffic operating points are indicated in Appendix 2 (Rail Traffic Operating Point Register).

3.3.2.6 Power Supply

On all electrified lines, power is taken from the catenary above the track in such a way that one or both of the running rails form a return circuit. Rated voltage is 25 kV/ 50 Hz AC. The electrified line sections are indicated in Appendix 1 (Infrastructure Register).

For fixed installations, electrification is described in part 5 "Sähköistetty rata" (Electrified railway) of the RAMO publication, and for the electric equipment of rolling stock in the LISO publication.

3.3.3 Traffic Control and Communications Systems

3.3.3.1 Signalling Systems

The signalling systems in use are indicated in Appendix 1 (Infrastructure Register) and graphically in Appendix 7 (Signalling Systems).

A line with section block is a line divided into block sections. Only one train may be in a block section at a time.

Hot box detectors have been placed on the rail network at 50 km intervals on line sections on which the greatest speed is or can be over 160 km/h. In addition hot box detectors have been placed near the busiest junction stations. A map of the location of the hot box detectors is presented in Appendix 7.

3.3.3.2 Traffic Control Systems

The line sections equipped with an automated traffic control system are indicated in Appendix 1 (Infrastructure Register) and in Appendix 7 (Signalling Systems). The following automated traffic control systems are used: centralised traffic control; train detection and train integrity monitoring; and radio control. On the CTC- and radio-controlled lines, all routes are equipped with the remote control of points and routes. On the secondary, loading and storage sidings of these line sections, however, local route setting may also be necessary. On radio-controlled lines, routes shall be set locally if it is necessary to operate on secondary, loading or storage sidings.

3.3.3.3 Communications Systems

The Train Safety Regulations (JT) prescribe the documents the engine driver must have at his disposal before departure. The contents of these documents are described in more detail in the Train Safety Regulations.

Information on exceptional situations is transmitted through the Advance Notification System (ETJ), maintained by RHK. The railway undertakings shall join this system, which transmits information both on circumstances affecting traffic operating temporarily and on permanent changes on the selected route practically in real time.

Communication between traffic controllers and drivers takes place in the Finnish language orally, by phone, through signals or by radio. A line radio system with a channel reserved for each line section is used on the rail network. The same radio system can also be used for directing shunting operations provided that the parties agree on the channels to be used. Speech is heard by all shunting units operating on the same channel within the range of audibility.

Speech transmitted via voice communication devices is recorded. Recordings are used for controlling traffic communication, as well as for investigating accidents and hazardous situations.

3.3.3.4 ATP Systems

Automatic train protection (ATP) means equipment with which it is ensured that trains keep to the speed limits and obey other signals.

The Train Safety Regulations (JT) make it possible to operate without ATP equipment at 80 km/h on a line with ATP. Museum trains and track machinery which do not yet have ATP equipment may operate on the network under current terms.

3.4 Traffic Restrictions

3.4.1 Specialised Infrastructure

RHK may designate a train path or a part of it as specialised infrastructure, if there are sufficiently alternative routes for other traffic. Specialised infrastructure refers to a train path or a part of it on which priority is given to the type of traffic for which the infrastructure is specialised. So far RHK has not designated any line section in Finland as specialised infrastructure.

3.4.2 Environmental Restrictions

The requirements laid down in RHK's LIMO publication are applied when registering rolling stock. LIMO sets out general and special requirements for rolling stock concerning noise, vibration, electromagnetic interferences, emissions, environmentally dangerous substances and the use of recycled construction materials.

Vibration-related speed restrictions are imposed on parts of the railway line on twelve line sections throughout Finland. The restrictions mainly apply to over 3,000 ton gross weight heavy trains (Appendix 8).

3.4.3 Dangerous Goods

Finland has signed the intergovernmental COTIF Convention, which regulates international rail traffic. Russia and other CIS countries have not acceded to the COTIF Convention. One of the annexes to COTIF are the Regulations concerning the International Carriage of Dangerous Goods by Rail (RID). The RID Regulations apply as such to the international rail transport of dangerous goods. The domestic rail transport of dangerous goods is regulated by the provisions transposed into Finnish legislation in accordance with the RID framework directive (96/49/EC).

The most important differences compared to the RID regulations are as follows: cold resistance requirement for certain packagings and tanks in domestic traffic is -40°C (RID -18 and -20°C); as well as the regulations concerning protection wagons and the bringing of wagons loaded with explosives to traffic operating points and the temporary storage of explosives. The decree of the Ministry of Transport and Communications also takes into account the requirements of the VOC directive (94/63/EC) concerning the recovery of vapours from petrol in connection with rail transport.

No absolute restrictions have been imposed on the transport of dangerous goods if carried out according to the regulations. It is recommended that wagons loaded with dangerous goods should not be parked in densely populated or ground-water areas. The transport of dangerous goods on tracks with spike fastening or laid with 43 kg rails shall be avoided.

It is prescribed by the Government Decree that railway undertakings shall carry out a safety analysis for railway yards through which considerable quantities of dangerous goods are carried. The safety analysis shall be submitted to the local rescue and environmental authorities for an opinion. The safety plan is approved by the Finnish Rail Agency.

3.4.4 Tunnel Restrictions

There are tunnel restrictions on the Helsinki–Turku line section. The restrictions are indicated in Appendix 9.

3.4.5 Bridge Restrictions

Bridge restrictions are described in Appendix 10.

3.5 Availability of the Infrastructure

Other restrictions than those listed in item 3.4 are described in the Train Safety Regulations (JT) and in the Advance Notification System (ETJ). Track work causing traffic restrictions is presented in Appendix 11.

3.6 Passenger Stations

The lengths of passenger platforms (shortest/longest) are indicated in Appendix 2 (Rail Traffic Operating Point Register). The platforms not maintained by RHK are indicated in brackets.

3.7 Freight Terminals

Loading possibilities are indicated in Appendix 2 (Rail Traffic Operating Point Register). K means “yes” and Y “private”. For loading platforms, the register lists their available length.

Private siding connections at traffic operating points are indicated by the marking “Private sidings” in Appendix 2 (Rail Traffic Operating Point Register).

3.8 Service Facilities

3.8.1 Train Formation Yards

Train formation yards are railway yards in which the layout and size of the track system make it possible to form trains. The train formation yards are indicated by the marking “Shunting” in Appendix 2 (Rail Traffic Operating Point Register).

3.8.2 Storage Sidings

Storage sidings are yard tracks primarily intended for the parking of wagons and coaches waiting for a transport task. Storage sidings can also be used for other purposes required by traffic operating. The local traffic control centre determines which tracks are used as storage sidings.

3.8.3 Maintenance and Service Facilities

The 400 and 1,500 V power supply facilities for rolling stock are indicated in Appendix 2 (Rail Traffic Operating Point Register). For the 400 V power supply, also the maximum current available is indicated in amperes. The use of maintenance and service facilities requires an agreement with their owner.

3.8.4 Refuelling Facilities

The Finnish Rail Administration does not own refuelling equipment or provide refuelling services. The Appendix 2 (Rail Traffic Operating Point Register) shows the refuelling facilities on traffic operating points. The use of refuelling facilities requires an agreement with their owner.

3.8.5 Technical Equipment

The use of other technical equipment (e.g. scales, cranes, etc.) must be agreed with their respective owners. The Finnish Rail Administration does not provide this equipment for railway companies to use. The Appendix 2 (Rail Traffic Operating Point Register) shows the cranes located on traffic operating points.

3.9 Infrastructure Development

Rail network development plans are presented in RHK's Action and Financial plan for the years 2008–2011. At the end of 2006, approximately 1/5 of the rail network had a superstructure more than 30 years old and in need of renovation. The most critical challenge for the track maintenance during this planning period is the completion of the renovation, which to date has progressed well, and its extension to railway yards. At the same time increased costs brought on by the increase in the prices of technology and materials must be kept under control.

Discussions over the future of the part of the rail network with low traffic volumes will be held during this planning period. Decisions concerning the length of the railway network must be made before the renovation of track sections with low traffic volumes becomes inevitable.

The development plans for the years beyond the period covered by the Action and Financial Plan are presented in the “Rail Network 2030” report.

4 Capacity Allocation

4.1 Introduction

The legal framework of capacity allocation is described in the Railway Act (555/2006) and in the Government Decree on the Timetable Period in Rail Traffic and Applying for Infrastructure Capacity (751/2006).

4.2 Description

Capacity for operating regular train services on the state-owned rail network shall be requested from RHK for each timetable period within the time defined. Capacity for regular train services can also be requested during the timetable period. The schedule for train path requests and for allocation is shown in a diagrammatic form in Figure 6. It is also possible to make ad hoc requests for capacity for other than regular traffic.

Requesting Track Capacity

The principles of capacity requests are described in the Railway Act (555/2006) and in the Government Decree on the Timetable Period in Rail Traffic and Applying for Infrastructure Capacity (751/2006). The Finnish Rail Administration has drawn up instructions for capacity requests in order to specify the Act and the Decree. These instructions are currently being updated and once completed the new instructions will be available from the Traffic Control Unit of the Finnish Rail Administration's Traffic System Department. This chapter describes the contents of the existing instructions. These instructions can be used for requesting capacity for the purpose of operating regular services; and also, as appropriate, for ad hoc capacity requests.

Requests for capacity shall be made in writing. The request may, however, also be sent electronically, as provided in the Act on Electronic Service in the Administration (13/2003).

Written requests shall be addressed to RHK's Traffic System Department at the following address:

**Finnish Rail Administration
Traffic System Department/
Traffic Management Unit
PO Box 185**

FI-00101 Helsinki

E-mailed requests for capacity shall be sent to:

kirjaamo@rhk.fi

In accordance with the capacity request instructions, railway undertakings shall in their requests for capacity give the following information on each train:

- train diagram (train graph);
- departure and arrival time;
- train type (passenger / freight train);
- maximum permitted speed;
- times / days / periods of operation.

In addition to the above-mentioned information, railway undertakings may also give the following train information:

- train number;
- priority order class;
- stops of passenger trains/ handling points of freight trains;
- other information relating to operation.

Railway undertakings may also request part of the capacity without indicating exact requirements concerning the days of operation or the train graph. Such a train could be placed in operation on the conditions to be specified in the capacity allocation decision under the direction of RHK's Traffic Control. In that case, the information on "times / days / periods of operation" need not be given in the request. RHK will request further information from the applicant if the coordination process so requires.




Figure 6. Diagrammatic presentation of the schedule for train path requests and for allocation process.

4.3 Schedule for Train Path Requests and Allocation Capacity Requests

4.3.1 Schedule for Working Timetable

The timetable period in rail traffic starts annually at the second weekend of December, at 00.00 hrs on the night between Saturday and Sunday, and ends at the corresponding time the following year. The timetable period 2008 will start on 9.12.2007 and end on 13.12.2008. Correspondingly, the timetable period 2009 will start on 14.12.2008 and end on 12.12.2009. Applicants for capacity shall request capacity no earlier than 12 and no later than 8 months ahead of the timetable period. One request may include all the changes in traffic to be made during the timetable period.

Decisions on the allocation of capacity for regular services may be changed for the rest of the timetable period during the timetable period concerned at specified dates, provided that these changes do not affect the capacity allocated to other railway undertakings or to international traffic within the European Economic Area. The changes may take effect at 00.00 hrs on the night between Saturday and Sunday in the beginning of the timetable period and at the weekend following the end of the school year. In addition to the above dates, the Finnish Rail Administration may for special reasons decide on other dates on which changes can take place. The Finnish Rail Administration shall inform all railway undertakings of possible new dates on which the capacity for regular services may be changed.

Requests for changing capacity allocated for regular services must be submitted not later than four weeks before the date on which the change shall take effect.

4.3.2 Requesting Infrastructure Capacity for Temporary Traffic

Applicants for capacity may request capacity from RHK regardless of the prescribed period if they urgently need capacity for one or more provisional train paths. Ad hoc capacity requests for the time period between the change dates can be made after the capacity application period has ended. Infrastructure capacity for museum traffic can be applied no earlier than four months before the scheduled departure. The Finnish Rail Administration will announce its decision concerning the capacity request within five working days of receiving the application.

Ad hoc capacity requests must be made in writing. The request may, however, also be sent electronically, as provided in the Act on Electronic Service in the Administration. Contrary to the provisions of this Act, the decision on a request submitted electronically may be sent to the applicant for information by telefax or electronic mail as well. In such cases, the applicant is considered to have been informed of the decision after the telefax message or electronic mail has been sent to the applicant.




Figure 7. Dates on which the capacity for regular services may be changed during the timetable period 2008.

4.4 Allocation

4.4.1 Coordination

Based on the applications, RHK draws up the capacity allocation proposal (called “draft working timetable” in the Railway Act) for the next timetable period no later than four months after the deadline for the submission of requests for capacity. It has, however, been agreed by European railway infrastructure managers that no more than 2.5 months shall be used for the coordination of requests. The capacity allocation proposal contains information on the capacity that RHK proposes to allocate to an applicant only to such an extent and with such restrictions as is necessary for implementing traffic control for the use of this capacity.

The capacity allocation proposal is primarily based on the assumption that the requested capacity will be allocated, provided that the different train paths enable railway traffic to be operated in accordance with the technical and safety requirements. In order to improve the use of infrastructure capacity, RHK may, however, offer applicants capacity that does not essentially differ from the capacity they have requested. RHK may also decide not to allocate capacity, provided that reserve capacity is needed for the timetable period as a result of the priority order applied to rail traffic.

RHK sends the capacity allocation proposal to applicants for information within the prescribed period of time and gives them the opportunity to comment. Comments shall be presented within 30 days after receipt of the capacity allocation proposal. Customers purchasing freight transport services and associations representing purchasers of rail transport services also have the right to present comments on the capacity allocation proposal within 30 days, counted from the date on which RHK publishes an announcement in its collection of regulations that the capacity allocation proposal has been prepared.

Coordination for the Timetable Period

If there are several applicants for the same capacity or the requested capacity affects the capacity requested by another applicant, RHK will attempt to coordinate the requests between the applicants. In such cases, RHK may offer the applicants capacity that does not essentially differ from the capacity they have requested.

If the coordination of the requests between the applicants does not lead to a satisfactory result, RHK decides on the priority order in each individual case on the grounds laid down in the Railway Act. RHK shall decide on an individual priority order no later than ten days after coordination has ended.

Confirmation of the Capacity Allocation Proposal

Based on the capacity allocation proposal and the comments presented by the parties involved, RHK shall decide on the allocation of infrastructure capacity on a fair and non-discriminatory basis. In deciding, RHK shall pay particular attention to the needs of passenger and freight traffic and infrastructure maintenance, as well as to efficient use of the rail network. The priority order determined for specialised and congested infrastructure shall also be taken into account, unless otherwise provided in this chapter.

Allocating Ad Hoc Track Capacity

RHK allocates the requested ad hoc capacity if there is sufficient capacity for the use specified in the request. Unless otherwise provided in the Railway Act, the ad hoc capacity is allocated on a first-come first-served basis.

4.4.2 Dispute Resolution

Railway undertakings may appeal against a capacity allocation decision by RHK by filing a claim for rectification with the Regulatory Body. For further information, see 1.4.3.

4.4.3 Congested Infrastructure

RHK declares an element of infrastructure or a part of it to be congested infrastructure if the coordination of several requests for the same infrastructure has not led to a satisfactory result. RHK may also designate an element of infrastructure as congested if it is evident that it will become congested during the timetable period.

If there are several applications for the same infrastructure, the priority order is as presented in Table 1. Application of this priority order is based on the assumption that each train can be defined during its whole journey by one of the terms listed in the table. The term by which the train is defined may change during the journey of the train.

Table 1. Priority order on congested infrastructure.

| Priority | Traffic |
|----------|--|
| 1. | Synergic passenger traffic entity ¹ |
| 2.a | Express train traffic ² |
| 2.b | Transport for the processing industry ³ |
| 3.a | Local and other passenger traffic |
| 3.b | Other regular freight traffic |
| 4. | Freight traffic not requiring strict transport times |
| 5. | Other traffic ⁴ |

¹ The term “synergic passenger traffic entity” refers in passenger traffic to the whole of trains which form a transport system producing clear added value for customers. A system of this kind is, for example, traffic operated according to the basic interval timetable

² The term “express train traffic” refers to traffic which in some respect does not belong within the scope of the synergy-producing traffic system. International passenger traffic may belong in this category.

³ The term “transport for the processing industry” mainly refers to transport whose immediate place of destination or origin is a port or a private siding. This transport is essentially connected with total logistics management. This group includes, in particular, combined transport, transport for the wood-processing industry and transport to ports.

⁴ For example, traffic connected with track work or museum train traffic.

Derogation from the Priority Order Laid Down in the Network Statement

RHK may by a separate decision make a derogation from the general priority order laid down in the Railway Act and the Network Statement in favour of an applicant operating international traffic or such traffic as otherwise maintains or improves the functioning of the rail transport system or public transport. The same applies to cases where the rejection of the application would cause unreasonable damage to applicants, railway undertakings, international grouping of railway undertakings or to the business activities of their customers.

4.5 Allocation of Capacity for Maintenance, Renewal and Enhancements

The rail network may also be used for transferring track machines from bases to worksites, between worksites, and for maintenance purposes. Certain tracks are mainly used for maintenance purposes. A list of these tracks can be requested from RHK’s Rail Data Unit of the Rail Network Department. In accordance with the Railway Act, an operating licence is required for traffic outside the area reserved for infrastructure maintenance if track machines are transferred as a train, and also if the traffic is connected to track work. The operating licence issued by the Finnish Rail Agency will be granted upon application for a maximum of five years at a time. The prerequisite for granting the operating licence is that the maintenance / railway work undertaking has sufficient liability insurance and risk management system, their rolling stock has been approved by the Finnish Rail Agency and those handling the traffic operation have the required competence. Moreover, track machine movements shall be agreed upon separately with RHK. The track machines running on the rail network and their crews shall meet the requirements laid down under 2.8 and 2.9.

Track works which will probably be carried out during the timetable period 2008 and which are likely to have an impact on train traffic are indicated in Appendix 11. The working programme, timing of tasks, and the breaks required for the work will change as the funding and plans become more focused. Once the Network Statement is published, RHK will maintain up-to-date information on the working programme for the upcoming timetable period, and regularly inform the track capacity applicants about the programme. RHK will decide separately on all railway work and breaks required for their completion. The decision will be made prior to the upcoming timetable period, that is in December 2007 for the timetable period 2008.

Any required maintenance breaks or changes to an earlier decision, arising after the decision has been made, can be discussed separately, if necessary. The basic rule is that breaks requiring traffic arrangements are no longer arranged at this stage, but instead the work requested after the decision will be carried out according to (or in between) the traffic.

In addition to the aforementioned, the person or group applying for the working break must contact the regional traffic planner separately for each request and agree on the working break and its details in accordance with the RHK’s working break decision no later than two months before the work is scheduled to start.

4.6 Non-usage Rules

RHK has the right to cancel the capacity allocated to an applicant, or a part of it, if the applicant has used this capacity over a period of not less than 30 days less than required by the threshold quota specified below. In Finland, the threshold quota for the minimum use of capacity is 80 %, except on the line sections Helsinki–Kerava, Helsinki–Vantaankoski and Helsinki–Leppävaara, where the threshold quota for the minimum use is 95 %.

RHK may not, however, cancel the capacity if the failure to use it is due to non-economic reasons beyond the applicant or the railway operator's control. RHK always cancels the capacity for such a period during which the railway undertaking does not have a safety certificate for operating rail services.

4.7 Exceptional Transport and Dangerous Goods

For information on the transport of dangerous goods, see point 3.4.3, Dangerous Goods. Regulations concerning railway traffic and rolling stock are available on the Internet pages of the Finlex Data Bank and other instructions on the Finnish Rail Agency and RHK Internet pages.

4.8 Special Measures to Be Taken in the Event of Disturbance

4.8.1 Principles

RHK has the right to cancel the capacity completely or partially on a train path provisionally out of service due to a technical failure in the railway network, an accident or other incident.

In such case, RHK offers the operator alternative train paths, as far as possible. RHK is, however, not obliged to compensate for damage that may be caused to the operator, unless otherwise agreed upon with the operator in conformity with the Railway Act.

4.8.2 Operational Regulation

RHK is preparing instructions on how to clear disturbances in rail traffic. RHK intends to complete the instructions by the end of 2007. RHK defines the rules for managing disturbances between railway undertakings. Railway undertakings have the right to present their own proposals for instructions how to handle disturbances connected with their own trains. The liability for harm and damages caused by disturbances shall be agreed upon by negotiation in accordance with RHK's instructions, as far as possible.

4.8.3 Foreseen Problems

Disturbances are to be dealt with in accordance with RHK's instructions.

4.8.4 Unforeseen Problems

RHK, railway undertakings and railway maintenance undertakings shall be prepared for railway accidents in their fields of activity. The principle is that railway undertakings and railway track contractors shall be prepared to clear their own vehicles and the transported freight off the track, as well as remedy the damage caused to the environment within a reasonable time after the accident. Each undertaking shall draw up an emergency preparedness plan, which RHK shall approve. The preparedness measures included in the plan shall be taken before traffic operating is started. The undertakings themselves bear the costs caused by the creation and maintenance of the emergency preparedness system. The costs caused by an accident are borne by the party having caused the accident in accordance with the Act on Liability in Track-Guided Traffic and the Tort Liability Act.

RHK shall be prepared to restore the track quickly to operable condition and within a reasonable time to the condition it had before the accident. RHK agrees thereupon when making the rail network maintenance agreements.

The Ministry of Transport and Communications decides on the emergency preparedness obligations of each undertaking, depending on the nature and extent of its activities.

5 Services

5.1 Introduction

The legal framework of capacity allocation is described in the Railway Act (555/2006).

The Government is currently drafting its decree on the services offered to the rail traffic operators. Services concerning the usability of the rail network are described in Chapter 5 and Appendix 2 (Rail Traffic Operating Point Register) of the Network Statement. These services may be supplied by RHK or other parties.

5.2 Services Offered by RHK

RHK offers rail traffic operators on the state-owned rail network the right against payment to utilise the train paths in accordance with the capacity granted to it by RHK, marshalling yards, storage sidings, loading tracks and other tracks and passenger platforms. RHK also offers train traffic control passenger information and public address systems at the railway stations specified in the Network Statement (Appendix 12).

Use of capacity includes the right of the traffic operator to use of RHK's electricity supply network for traffic on the electrified line sections specified in the Network Statement. RHK does not, however, provide the electricity but the traffic operator shall conclude an agreement with a service provider. RHK also does not provide refuelling facilities.

RHK can offer services on a commercial basis for the use of railway operators. The additional services could comprise, for example, the use of buildings and land areas owned by RHK.

The use of services provided by RHK is agreed upon between the parties in the access contract or in a separate lease agreement.

5.3 Services Offered by Others

Railway undertakings are obliged to supply certain services and track access to services facilities for the use of railway operators if only one undertaking provides these services and it is not possible to otherwise arrange them. The availability of services shall be negotiated and an agreement shall be concluded with the service provider. The service provider has the right to charge a payment for its services. The payment shall be equitable for all railway undertakings and reasonable with respect to the costs incurred from providing the service.

Services supplied by others may include, for example:

- use of electrical supply equipment
- use of refuelling equipment
- use of passenger stations
- use of freight terminals
- use of train formation yards
- use of train formation equipment
- use of depot sidings
- premises and equipment needed for the servicing and maintenance of rolling stock
- use of other technical devices (e.g. sand distributors, water and electrical connections for rolling stock, radiation measurement devices, tank wagon filling gauges, wagon scales, and brake testing equipment), and
- training services for those involved in traffic safety tasks

6 Charges

6.1 Charging Principles and Services Included in the Infrastructure Charge

The legal framework of the basic infrastructure charge is described in the Railway Act (555/2006), Railway Infrastructure Tax (605/2003) and the Ministry of Transport and Communications Decree on the basic infrastructure charge (756/2006).

The basic infrastructure charge covers the minimum access package (the minimum access package is described under 5.2.), including track access to service facilities on the state-owned rail network.

6.2 Infrastructure Charge System

The infrastructure charge system will be changed. The basic principle remains that RHK shall collect a basic infrastructure charge from railway operators on a fair and non-discriminatory basis for the minimum access package and track access to service facilities, calculated on the actual level of use. The basic infrastructure charge shall always be based on the costs directly caused by the operation of railway traffic. The infrastructure tax consists of a charge for external costs and a supplementary charge in accordance with the Capacity and Infrastructure Charge Directive. In the charge for external costs, the environmental effects caused by the operation of rail traffic can be taken into account. The supplementary charge can be collected for covering the full amount of the costs caused by the use of the infrastructure. Furthermore, investment tax will be collected for the Kerava-Lahti line section until 31 August 2021 in order to cover the long-term expenses of the investment.

Table 2. Infrastructure charge.

| | |
|--|---|
| Basic charge | Freight traffic 0.1227 cent/ gross tonne-kilometre Passenger traffic 0.1189 cent/ gross tonne-kilometre |
| Infrastructure tax | Freight traffic <ul style="list-style-type: none">■ electric 0.05 cent/ gross tonne-kilometre■ diesel 0.1 cent/ gross tonne-kilometre Passenger traffic 0.01 cent/ gross tonne-kilometre |
| Investment tax (for line section Kerava-Lahti) | Freight traffic 0.5 cent/ gross tonne-kilometre Passenger traffic 0.5 cent/ gross tonne-kilometre |

6.3 Tariffs

The infrastructure charge consists of the charges mentioned in Table 2.

6.4 Incentive System for the Charges

Finland is not using an extensive incentive system for the charges. All compensation for the rail network availability and possible breaks will be agreed in the rail network access contract.

6.5 Changes to Charges

The infrastructure charge system will be changed. The principles of infrastructure charge system and amount of charges in force are available on RHK's web pages, <http://www.rhk.fi>.

6.6 Billing Arrangements

RHK invoices the infrastructure charge each calendar month based on the realised performances of the previous month. For invoicing, railway operators shall provide the RHK contact person with information each month on the rail services operated by them to:

**Finnish Rail Administration
Administration Department /
Financial Administration Unit
PO Box 185
FI-00101 Helsinki**

RHK does not require any guarantee for the payment of infrastructure charges. The infrastructure charge and other charges connected with it are, however, subject to distraint without sentence or decision.

Index

| | |
|--|------------|
| Access requirements | 13–16 |
| Access contract | 13, 16 |
| Accidents | 15, 21, 28 |
| Ad hoc request | 25, 26 |
| Allocation process | 24–27 |
| Axle loads | 17 |
| Border stations | 17 |
| Capacity allocation proposal | 26 |
| Congested capacity | 26 |
| Dangerous goods | 22 |
| Draft working timetable | 26 |
| Environmental restrictions | 22 |
| Electrification | 21, 23, 29 |
| Event of disturbance | 26 |
| Framework agreement | 15 |
| Gradient | 21 |
| Infrastructure | 17–23 |
| Infrastructure capabilities | 17 |
| Infrastructure charge | 30 |
| Infrastructure development | 23 |
| Infrastructure tax | 30 |
| Metre loads | 17 |
| Ministry of Transport and Communications | 9, 14 |
| Museum train traffic | 14 |
| Operating licence | 14 |
| OSS activities | 10–11 |
| Priority order for infrastructure capacity | 27 |
| RailNetEurope | 10–11 |
| Regulatory body | 8 |
| Requesting infrastructure capacity | 25 |
| Safety certificate | 13–15 |
| Services | 29 |
| Signalling systems | 21 |
| Specialised infrastructure | 22 |
| Speed | 21 |
| TEN (Trans-European) Network | 20 |
| Timetable period | 8, 24–25 |
| Track gauge | 17 |
| Track works | 27 |
| Traffic control | 21 |
| Traffic operating points | 17 |
| Traffic restrictions | 22 |
| Traffic safety communication | 21 |
| Train paths | 15 |
| Urgently needed capacity | 25–26 |

Liite 1: Infrastruktuuri- rekisteri

Bilaga 1: Infrastruktur- register

Appendix 1: Infra- structure Register

Merkintöjen selitykset:

| | |
|------------|-------------------------------------|
| On | "kyllä" |
| — | "ei" |
| AC2 | sähköistysjärjestelmä 25 kV / 50 Hz |
| ATP-VR/RHK | Junan kulunvalvonta |

Anteckningar:

| | |
|------------|------------------------------------|
| On | "ja" |
| — | "nej" |
| AC2 | elektrifieringsystem 25 kV / 50 Hz |
| ATP-VR/RHK | Automatisk tågkontroll |

Markings:

| | |
|------------|--------------------------------------|
| On | "yes" |
| — | "no" |
| AC2 | eletrification voltage 25 kV / 50 Hz |
| ATP-VR/RHK | Automatic train protection |

Chart columns:

- Traffic operating points (Node of the network) indicates all traffic operating points where the route of the train can be changed.
- Length of line is the distance between traffic operating points (nodes of the network).
- Max gradient is the maximum gradient measured in a distance of 1,200m.
- Electrification system indicates that the section of line is electrified.
- Section blocking or radio-controlled section indicates that an automatic safety device system is in use in order to protect the railway traffic.
- ATP indicates that the section of line is equipped with automatic train protection.
- ERTMS indicates that the section of line is equipped with pan-European safety device system and GSM-R radio network.
- ATP coding for tilting trains indicates the sections on which ATP allows higher speeds for tilting trains.
- Radio system indicates whether the type of communication equipment in use between the driver and traffic control is analogue (linjaradio) or digital (GSM-R).

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköistys- järjestelmä | Suojastettu tai radio-ohjattu osuus | Junan kulun- valvontajärjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio- järjestelmä |
|--|--|------------------------|----------------------|-----------------------------|---|-------------------------------------|-------|--|-----------------------|
| Trafikplats (knutpunkt i bannätet) | Trafikplats (knutpunkt i bannätet) | Banans längd | Största lutning | Elektrifie- rings-system | Linjeblockerad eller fjärrstyrd sträcka | Automatisk tågkontroll | | ATC-kodning av lutande tåg | Radiosystem |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line [km] | Max. gradient ‰ | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | Radio system |
| Helsinki | Kerava | 29 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Helsinki asema | Länsisatama | 4 | 10 | — | — | — | — | — | Linjaradio |
| Kerava | Hyvinkää | 29 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Hyvinkää | Riihimäki | 12 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Kerava | Olli | 16 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Olli Sköldvik | | 11 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Olli Porvoo | | 17 | 10 | — | — | — | — | — | Linjaradio |
| Kerava | Hakosilta | 65 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Hyvinkää | Lohja | 64 | 10 | — | — | — | — | — | Linjaradio |
| Lohja | Karjaa | 34 | 10 | — | — | — | — | — | Linjaradio |
| Lohja | Lohjanjärvi | 4 | 16.5 | — | — | — | — | — | Linjaradio |
| Pasila alapiha | Sörnäinen | 3 | 10 | — | — | — | — | — | Linjaradio |
| Helsinki | Huopalahti | 6 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Huopalahti | Vantaankoski | 9 | 20 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Huopalahti | Kirkkonummi | 31 | 12.5 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Kirkkonummi | Karjaa | 50 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Karjaa | Hanko | 50 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Karjaa | Turku | 107 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Turku asema | Turku satama | 3 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Turku tavara | Turku Vihariäinen | 9 | 10 | — | On | — | — | — | Linjaradio |
| Riihimäki | Toijala | 76 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Toijala | Turku | 128 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Toijala | Tampere | 40 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Toijala | Valkeakoski | 18 | 10 | — | — | — | — | — | Linjaradio |
| Turku | Raisio | 8 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköistys- järjestelmä | Suojustettu tai radio-ohjattu osuus | Junan kulun- valvontajärjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio- järjestelmä |
|--|--|------------------------|----------------------|-----------------------------|---|-------------------------------------|-------|--|-----------------------|
| Trafikplats (knutpunkt i bannätet) | Trafikplats (knutpunkt i bannätet) | Banans längd | Största lutning | Elektrifie- rings-system | Linjeblockerad eller fjärrstyrd sträcka | Automatisk tågkontrol | | ATC-kodning av lutande tåg | Radiosystem |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line [km] | Max. gradient ‰ | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | Radio system |
| Raisio | Naantali | 6 | 10 | — | — | — | — | — | Linjaradio |
| Raisio | Uusikaupunki | 57 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Uusikaupunki | Hangonsaari | 3 | 11.5 | — | — | — | — | — | Linjaradio |
| Tampere | Lielähti | 6 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Lielähti | Kokemäki | 91 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Kokemäki | Kiukainen | 13 | 12.5 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Kiukainen | Rauma | 34 | 12.5 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Kiukainen | Säkylä | 19 | 12.5 | — | — | — | — | — | Linjaradio |
| Kokemäki | Pori | 38 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Pori | Mäntyluoto | 21 | 10 | — | — | — | — | — | Linjaradio |
| Pori | Ruosniemi | 8 | 10 | — | — | — | — | — | Linjaradio |
| Mäntyluoto | Tahkoluoto | 11 | 10 | — | — | — | — | — | Linjaradio |
| Lielähti | Parkano | 69 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Niinisalo | Parkano | 42 | 10 | — | — | — | — | — | — |
| Parkano | Kihniö | 16 | 10 | — | — | — | — | — | — |
| Parkano | Seinäjoki | 84 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Riihimäki | Hakosilta | 48 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Hakosilta | Lahti | 11 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Lahti | Loviisan satama | 77 | 12.7 | — | — | — | — | — | Linjaradio |
| Lahti | Salpausselkä | 2 | 16.5 | — | — | — | — | — | Linjaradio |
| Lahti | Joutjärvi | 3 | 10 | — | — | — | — | — | Linjaradio |
| Joutjärvi | Heinola | 35 | 12.5 | — | — | — | — | — | Linjaradio |
| Joutjärvi | Mukkula | 7 | 15 | — | — | — | — | — | Linjaradio |
| Lahti | Kouvola | 61 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Kouvola | Luumäki | 59 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköistys- järjestelmä | Suojastettu tai radio-ohjattu osuus | Junan kulun- valvontajärjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio- järjestelmä |
|--|--|------------------------|----------------------|-----------------------------|---|-------------------------------------|-------|--|-----------------------|
| Trafikplats (knutpunkt i bannätet) | Trafikplats (knutpunkt i bannätet) | Banans längd | Största lutning | Elektrifie- rings-system | Linjeblockerad eller fjärrstyrd sträcka | Automatisk tågkontroll | | ATC-kodning av lutande tåg | Radiosystem |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line [km] | Max. gradient ‰ | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | Radio system |
| Kouvola | Juurikorpi | 33 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Juurikorpi | Kotka | 18 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Kotka asema | Kotkan satama | 1 | — | AC2 | — | — | — | — | Linjaradio |
| Paimenportti | Kotka Mussalo | 5 | 10 | AC2 | — | — | — | — | Linjaradio |
| Juurikorpi | Hamina | 19 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Kouvola asema | Kuusankoski | 10 | 10 | AC2 | — | — | — | — | Linjaradio |
| Kouvola | Mynttilä | 86 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Mynttilä | Ristina | 21 | 12.5 | — | — | — | — | — | Linjaradio |
| Mynttilä | Otava | 20 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Otava | Otavan satama | 2 | 22.5 | — | — | — | — | — | Linjaradio |
| Otava | Pieksämäki | 86 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Luumäki | Vainikkala | 33 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Luumäki | Lappeenranta | 27 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Lappeenranta | Mustolan satama | 18 | 10 | — | — | — | — | — | Linjaradio |
| Lappeenranta | Imatra | 39 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Imatra | Imatrankoski-raja | 10 | 12.5 | — | — | — | — | — | Linjaradio |
| Imatra | Parikkala | 60 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Pieksämäki | Huutokoski | 31 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Huutokoski | Savonlinna | 75 | 12.5 | — | — | — | — | — | Linjaradio |
| Savonlinna | Parikkala | 59 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Parikkala | Säkäniemi | 93 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Niirala-raja | Säkäniemi | 33 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Säkäniemi | Joensuu | 37 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Joensuu | Ilomantsi | 72 | 12.5 | — | — | — | — | — | Linjaradio |
| Joensuu | Viinijärvi | 32 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköistys- järjestelmä | Suojastettu tai radio-ohjattu osuus | Junan kulun- valvontajärjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio- järjestelmä |
|--|--|------------------------|----------------------|-----------------------------|---|-------------------------------------|-------|--|-----------------------|
| Trafikplats (knutpunkt i bannätet) | Trafikplats (knutpunkt i bannätet) | Banans längd | Största lutning | Elektrifie- rings-system | Linjeblocked eller fjärrstyrd sträcka | Automatisk tågkontrol | | ATC-kodning av lutande tåg | Radiosystem |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line [km] | Max. gradient ‰ | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | Radio system |
| Huutokoski | Varkaus | 18 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Varkaus | Kommila | 2 | 10 | — | — | — | — | — | Linjaradio |
| Varkaus | Viinijärvi | 101 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Joensuu | Uimaharju | 50 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Uimaharju | Liekka | 54 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Liekka | Pankakoski | 6 | 10 | — | — | — | — | — | Linjaradio |
| Liekka | Nurmes | 56 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Nurmes | Vuokatti | 85 | 12.5 | — | — | — | — | — | Linjaradio |
| Vuokatti | Lahnaslampi | 12 | 12.5 | — | — | — | — | — | Linjaradio |
| Vuokatti | Kontiomäki | 24 | 10 | — | — | — | — | — | Linjaradio |
| Pieksämäki | Suonenjoki | 38 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Suonenjoki | Isivesi | 6 | 10 | — | — | — | — | — | Linjaradio |
| Suonenjoki | Siiinjärvi | 76 | 12.5 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Viinijärvi | Siiinjärvi | 112 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Siiinjärvi | Isalmi | 60 | 12.5 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Isalmi | Murtomäki | 62 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Murtomäki | Otanmäki | 25 | 10 | — | — | — | — | — | Linjaradio |
| Murtomäki | Kontiomäki | 46 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Kontiomäki | Vartius | 94 | 12.5 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Vartius | Vartius-raja | 1 | 12.5 | — | — | — | — | — | Linjaradio |
| Kontiomäki | Pesökylä | 74 | 12.5 | — | — | — | — | — | Linjaradio |
| Pesökylä | Ämmänsaari | 18 | 12.5 | — | — | — | — | — | Linjaradio |
| Tampere | Orivesi | 40 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Orivesi | Vilppula | 47 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Vilppula | Mänttä | 8 | 12 | — | — | — | — | — | Linjaradio |

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköistys- järjestelmä | Suojastettu tai radio-ohjattu osuus | Junan kulun- valvontajärjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio- järjestelmä |
|--|--|------------------------|----------------------|-----------------------------|---|-------------------------------------|-------|--|-----------------------|
| Trafikplats (knotpunkt i bannätet) | Trafikplats (knotpunkt i bannätet) | Banans längd | Största lutning | Elektrifie- rings-system | Linjeblockerad eller fjärrstyrd sträcka | Automatisk tågkontrol | | ATC-kodning av lutande tåg | Radiosystem |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line [km] | Max. gradient ‰ | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | Radio system |
| Vilppula | Haapamäki | 26 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Haapamäki | Seinäjoki | 118 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Haapamäki | Jyväskylä | 77 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Orivesi | Jämsä | 56 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Jämsä | Kaipola | 7 | 12.5 | — | — | — | — | — | Linjaradio |
| Jämsä | Jämsänkoski | 4 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Jämsänkoski | Jyväskylä | 52 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Jyväskylä | Äänekoski | 47 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Äänekoski | Haapajärvi | 164 | 10 | — | — | — | — | — | Linjaradio |
| Jyväskylä | Pieksämäki | 80 | 12.5 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Seinäjoki | Kaskinen | 112 | 10 | — | — | — | — | — | Linjaradio |
| Seinäjoki | Vaasa | 75 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Vaasa | Vaskiluoto | 5 | 10 | — | — | — | — | — | Linjaradio |
| Ilisalmi | Pyhäkumpu erk.vh | 63 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Pyhäkumpu erk.vh | Pyhäkumpu | 3 | 7.5 | — | — | — | — | — | Linjaradio |
| Pyhäkumpu erk.vh | Haapajärvi | 36 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Haapajärvi | Ylivieska | 55 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Seinäjoki | Pännäinen | 101 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Pännäinen | Alholma | 10 | 10 | — | — | — | — | — | Linjaradio |
| Pännäinen | Kokkola | 33 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Kokkola | Yksphlaja | 5 | 10 | — | — | — | — | — | Linjaradio |
| Kokkola | Ylivieska | 79 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Ylivieska | Tuomioja | 68 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Tuomioja | Raahe | 28 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Raahe | Rautaruukki | 9 | 10 | AC2 | — | — | — | — | Linjaradio |

| Liikennepaikka (verkon solmupiste) | Liikennepaikka (verkon solmupiste) | Radan pituus | Määrävä kaltevuus | Sähköstys- järjestelmä | Suojastettu tai radio-ohjattu osuus | Junan kulun- valvontajärjestelmä | ERTMS | Kallistuvakoristen junien JKV-koodaus | Radio- järjestelmä |
|--|--|------------------------|----------------------|-----------------------------|---|-------------------------------------|-------|--|-----------------------|
| Trafikplats (knutpunkt i bannätet) | Trafikplats (knutpunkt i bannätet) | Banans längd | Största lutning | Elektrifie- rings-system | Linjeblockerad eller fjärrstyrd sträcka | Automatisk tågkontrol | | ATC-kodning av lutande tåg | Radiosystem |
| Traffic operating point (Node of the network) | Traffic operating point (Node of the network) | Length of line [km] | Max. gradient ‰ | Electrification system | Section blocking or radio controlled section | ATP | | ATP-coding for tilting trains | Radio system |
| Tuomioja | Oulu | 54 | 10 | AC2 | On | ATP-VR/RHK | — | On | Linjaradio |
| Oulu | Kontiomäki | 166 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Oulu | Kemi | 105 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Kemi | Ajos | 9 | 10 | — | — | — | — | — | Linjaradio |
| Kemi | Laurila | 7 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Laurila | Tornio | 19 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Laurila | Rovaniemi | 106 | 10 | AC2 | On | ATP-VR/RHK | — | — | Linjaradio |
| Rovaniemi | Kemijärvi | 85 | 12.5 | — | On | ATP-VR/RHK | — | — | Linjaradio |
| Kemijärvi | Isokylä | 7 | 12.5 | — | — | — | — | — | Linjaradio |
| Isokylä | Kelloseleä | 72 | 12.5 | — | — | — | — | — | Linjaradio |
| Tornio | Tornio-raja | 3 | 4 | — | — | — | — | — | Linjaradio |
| Tornio | Röyttä | 8 | 10 | — | — | — | — | — | Linjaradio |
| Tornio | Kolari | 183 | 10 | — | On | ATP-VR/RHK | — | — | Linjaradio |

Appendix 2

Rail Traffic Operating Point Register

Legend

| | |
|---|-----------------------------------|
| () in columns regarding platforms | platform not maintained by RHK |
| K | yes |
| Y | yes, private |
| K in columns regarding traffic control | remote control |
| M in columns regarding traffic control | manual |

Chart Columns:

- **'Name'** refers to the official name of the station and is used in traffic safety work.
- **'Another name'** is the name of a traffic operating point in Finland's second official language. Another name is usually a Swedish name, and only in Sköldvik is the Finnish name Kilpilahti used as another name, contrary to what the present language situation in the municipality would imply.
- **'Km Hki'** indicates the distance of a traffic operating point to the old station hall (already torn down), measured by a track kilometre system. According to the system, the location of all elements on tracks is fixed to landmarks.
- **'Municipality'** refers to the municipality, in which the traffic operating point is located.
- **'Traffic control'** describes, whether the traffic operating point has the technical equipment to control the train traffic manually or remote. It does not mean that traffic control services are regularly provided .
- **'Private sidings'** indicates that the traffic operating point has at least one connection to a siding, owned and managed by a private owner (includes everyone except RHK).
- **'Shunting'** indicates that the form of the tracks at a traffic operating point is such that it is possible to move at least a locomotive to the other end of a line of rolling stock without having to go through the main line of the traffic operating point.
- **'Minimum and maximum platform length'** indicates the minimum and maximum length of platforms used by passenger trains at the traffic operating point. A passenger train should not be longer than the platform at which it stops. If the platform length is in brackets (), the platform is not maintained by RHK, and services are operated at the responsibility of the railway undertaking.

- **'Platform height'** indicates the nominal height of platforms used by passenger trains, calculated from the surface of the rail.
- **'Design train length'** indicates the longest track of a traffic operating point, other than the main line going through it. The length is measured so that it is usable in both directions.
- **'Power supply'** indicates at which traffic operating point it is possible to get 400V or 1500V electric current mainly for rolling stock or track machinery power supply purposes.
- **'Side loading platform'** indicates, at which traffic operating points it is possible to load freight cars from the side, and shows the maximum platform length at the traffic operating point.
- **'End loading platform'** indicates at which traffic operating points it is possible to load freight rolling stock from the end of the platform (combined transports).
- **'Loading site'** indicates at which traffic operating points it is possible to load freight rolling stock at rail level. A typical example is loading raw timber from a vehicle or an intermediate depot at a rail yard onto flatcars.
- **'Crane'** indicates at which traffic operating point it is possible to use a crane to load wagons, and states the maximum capacity of the crane. This service is not provided by the Finnish Rail Administration (RHK).
- **'Fuel'** indicates at which traffic operating points there is a fuel distribution point. This service is not provided by the Finnish Rail Administration (RHK).
- **'Passenger traffic'** indicates those traffic operating points which have regular scheduled passenger traffic.
- **'Freight traffic'** indicates those traffic operating points which have regular freight traffic.

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-----------------------|-----------------|-------------|---------|-----------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Anvenus | | Ahv | 270+960 | Lielanti – Kokemäki | Kokemäki | K | | |
| Airaksela | | Arl | 436+985 | Pieksämäki – Siilinjärvi | Kuopio | K | K | K |
| Aittaluoto | | Atl | 328+220 | Pori – Ruosniemi | Pori | | K | |
| Ajos | Ajo | | 867+100 | Kemi – Ajos | Kemi | | K | K |
| Alapitkä | | Apt | 505+840 | Siilinjärvi – Iisalmi | Lapinlahti | K | | |
| Alavus | | Alv | 373+445 | Haapamäki – Seinäjoki | Alavus | | | K |
| Alholma | Alholmen | Alh | 532+570 | Pietarsaari – Alholma | Pietarsaari | | K | K |
| Alvajärvi | | Avi | 551+031 | Jyväskylä – Haapajärvi | Pihlupudas | | | |
| Arola | | Aro | 707+668 | Kontiomäki – Vartius – raja | Hyyinsalmi | K | | K |
| Dragsvik | | Dra | 171+180 | Karjaa – Hanko | Tammisaari | K | | K |
| Dynamiittivaihde | | Dmv | 199+185 | Karjaa – Hanko | Hanko | | K | K |
| Elijärvi | | Eli | 870+536 | Lautiosaari – Elijärvi | Keminmaa | | K | K |
| Eläinpuisto-Zoo | | Epz | 338+751 | Haapamäki – Seinäjoki | Ähtäri | | | |
| Eno | | Eno | 660+170 | Joensuu – Kontiomäki | Eno | K | | |
| Ervelä | | Erv | 118+777 | Karjaa – Turku | Perniö | K | | |
| Eskola | | Ela | 603+762 | Kokkola – Ylivieska | Kannus | K | | |
| Espoo | Esbo | Epo | 20+600 | Helsinki – Karjaa | Espoo | K | | |
| -(Esso) | | | 267+417 | Turku – Uusikaupunki | Uusikaupunki | | K | |
| (Finnish Chemicals) | Pappilankangas | | 308+638 | Luumäki – Parikkala | Joutseno | | K | |
| Haapajärvi | | Hpj | 649+205 | Iisalmi – Ylivieska | Haapajärvi | K | | K |
| Haapakoski | | Hps | 393+454 | Pieksämäki – Siilinjärvi | Pieksämäki | K | K | K |
| (Haapamäen kylästämö) | | | 304+940 | Haapamäki – Seinäjoki | Keuruu | | K | |
| Haapamäki | | Hpk | 300+235 | Orivesi – Haapamäki | Keuruu | K | K | K |
| Haarajoki | | Haa | 39+567 | Kerava – Hakosilta | Järvenpää | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-----------------|-----------------|-------------|----------|------------------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Hakosilta | | Hlt | 119+540 | Riihimäki – Lahti | Hollola | K | | |
| Haksi | Hax | Hsi | 56+737 | Olli – Porvoon keskusta | Porvoo | | | |
| Hamina | Fredrikshamn | Hma | 243+646 | Juurikorpi – Hamina | Hamina | M | K | K |
| Hammasslahti | | Hsl | 602+199 | Säkänieniemi – Joensuu | Pyhäselkä | K | | K |
| Hanala | Hanaböle | Hna | 21+394 | Helsinki – Riihimäki | Vantaa | K | | |
| Hangonsaari | | Hgs | 269+655 | Turku – Uusikaupunki – Hangonsaari | Uusikaupunki | | K | K |
| Hanhikoski | | Hnh | 1047+083 | Laurila – Kelloselkä | Kemijärvi | | | |
| Hankasalmi | | Hks | 418+089 | Jyväskylä – Pieksämäki | Hankasalmi | K | K | K |
| Hanko | Hangö | Hnk | 207+119 | Karjaa – Hanko | Hanko | M | K | |
| Hanko-Pohjoinen | Hangö Norra | Hkp | 205+935 | Karjaa – Hanko | Hanko | | | |
| Harjavalta | | Hva | 295+542 | Kokemäki – Pori | Harjavalta | K | K | K |
| Harju | | Hj | 201+643 | Kouvola – Pieksämäki | Valkeala | K | | K |
| Harviala | | Hrv | 99+456 | Riihimäki – Tampere | Janakkala | K | | |
| Haukipudas | | Hd | 775+159 | Oulu – Laurila | Haukipudas | K | | |
| Haukivuori | | Hau | 344+442 | Kouvola – Pieksämäki | Mikkeli | K | K | K |
| Hausjärvi | | Has | 86+210 | Riihimäki – Lahti | Hausjärvi | K | | K |
| Haviseva | | Hvs | 208+135 | Tampere – Orivesi | Kangasala | | | |
| Heikkilä | | Hek | 34+856 | Helsinki – Karjaa | Kirkkonummi | K | | |
| Heinola | | Ha | 167+607 | Lahti – Heinola | Heinola | M | K | |
| Heinoo | | Hno | 237+965 | Lielähti – Kokemäki | Vammala | K | | |
| Heinävaara | | Häv | 648+408 | Joensuu – Ilomantsi | Joensuu | | | K |
| Heinävesi | | Hnv | 468+135 | Huutokoski – Viinijärvi | Heinävesi | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|----------------------|-----------------|-------------|---------|-------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| HELSINKI | Helsingfors | Hel | | Helsinki – Riihimäki | Helsinki | M | | K |
| Helsinki asema | | Hki | 0+159 | | Helsinki | | | |
| Helsinki Kivihaka | Sterhagen | Khk | 4+701 | | Helsinki | | | K |
| Helsinki Länsisatama | | Län | 1+280 | | Helsinki | | | K |
| Helsinki Sörnäinen | | Sö | 12+194 | | Helsinki | | | |
| Ilmala asema | | Ila | 4+434 | | Helsinki | | | K |
| Ilmala ratapiha | | Ilr | 4+950 | | Helsinki | | K | |
| Käpylä | Kottby | Käp | 5+840 | | Helsinki | | | |
| Oulunkylä | Äggelby | Olk | 7+399 | | Helsinki | | K | |
| Pasila alapiha | | Psia | 3+193 | | Helsinki | | | K |
| Pasila asema | Böle | Psi | 3+230 | | Helsinki | | K | |
| Pasila tavara | | Psit | 4+748 | | Helsinki | | K | K |
| Herrala | | Hr | 115+790 | Riihimäki – Lahti | Hollola | | | |
| Hiekkaharju | Sandkulla | Hkh | 17+109 | Helsinki – Riihimäki | Vantaa | | | |
| Hirola | | Hir | 318+957 | Kouvola – Pieksämäki | Mikkeli | K | | |
| Hikiä | | Hk | 79+743 | Riihimäki – Lahti | Hausjärvi | | K | |
| Hiliosensalmi | | Hls | 233+344 | Kouvola – Pieksämäki | Valkeala | K | | |
| Hinthaara | Hindhår | Hh | 52+150 | Olli – Porvoon keskusta | Porvoo | | | |
| Hirvineva | | Hvn | 715+500 | Ylivieska – Oulu | Liminka | K | | K |
| Humpilla | | Hp | 188+778 | Toijala – Turku | Humpilla | K | K | K |
| Huopalahti | Hoplax | Hpl | 6+375 | Helsinki – Karjaa | Helsinki | K | | |
| Huutokoski | | Hko | 406+988 | Pieksämäki – Huutokoski | Joroinen | K | K | K |
| Hyrynsalmi | | Hys | 704+601 | Kontiomäki – Ämmänsaari | Hyrynsalmi | | | |
| Hyvinkää | Hyvinge | Hy | 58+792 | Helsinki – Riihimäki | Hyvinkää | K | K | K |
| Hämeenlinna | Tavastehus | Hi | 107+559 | Riihimäki – Tampere | Hämeenlinna | K | K | K |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|------------------------------|-----------------|-------------|----------|----------------------------------|---------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Härmä | | Hm | 472+940 | Seinäjäoki – Kokkola | Alahärmä | K | | |
| Höijäkkä | | Höl | 765+261 | Joensuu – Kontiomäki | Nurmes | | K | |
| li | | li | 789+165 | Oulu – Laurila | li | K | | |
| (lisalmen sahaj) | | | 546+495 | Siiinjärvi – lisalmi | lisalmi | | K | |
| (lisalmen teollisuuskylä) | | | 553+182 | lisalmi – Ylivieska | lisalmi | | K | |
| (lisalmen teollisuusraiteet) | Keveli | | 548+611 | Siiinjärvi – lisalmi | lisalmi | | K | |
| lisalmi | Idensalmi | Ilm | 550+360 | Siiinjärvi – lisalmi | lisalmi | M | | K |
| lisvesi | | lsv | 420+127 | Suonenjoki – lisvesi | Suonenjoki | | K | |
| littala | | lta | 129+286 | Riihimäki – Tampere | Kalvola | | | |
| Ilmajoki | | Ilj | 434+494 | Seinäjäoki – Kaskinen | Ilmajoki | | K | |
| Ilomantsi | Ilomants | Ilo | 695+203 | Joensuu – Ilomantsi | Ilomantsi | M | K | K |
| IMATRA | | Ima | | Luumäki – Parikkala | | M | | |
| Imatra asema | | Imr | 323+977 | | Imatra | | | |
| Imatra tavara | | Imt | 326+542 | | Imatra | | K | K |
| Imatrankoski | | Imk | 331+267 | | Imatra | | K | K |
| Pelkola | | Pa | 335+672 | | Imatra | | K | K |
| Imatrankoski-raja | | Imkr | 337+095 | Imatra tavara– Imatrankoski-raja | Imatra | K | | |
| (Imatran terästehdas) | Steel | | 332+602 | Imatra T – Imatrankoski-raja | Imatra | | K | K |
| Inha | | In | 341+367 | Haapamäki – Seinäjoki | Ähtäri | | | |
| Inkeroinen | | lkr | 212+781 | Kouvola – Kotka | Anjalankoski | K | K | |
| Inkoo | Ingå | Iko | 70+620 | Helsinki – Karjaa | Inkoo | K | | |
| Isokangas | | | 431+759 | Pori – Haapamäki | Parkano | | K | |
| Isokylä | | Ikä | 1062+829 | Laurila – Kelloseikä | Kemijärvi | | K | |
| Isokyrö | Storkyro | Iky | 447+488 | Seinäjäoki – Vaasa | Isokyrö | K | | |
| Jalasjärvi | | Jal | 309+871 | Tampere – Seinäjoki | Jalasjärvi | K | | |
| Jepua | Jepoo | Jpa | 495+784 | Seinäjäoki – Kokkola | Uusikaarlepyy | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|--------------------|-----------------|-------------|----------|--------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| JOENSUU | | Joe | | Säkäniemi – Joensuu | Joensuu | M | | |
| Joensuu asema | | Jns | 624+313 | | Joensuu | | K | K |
| Joensuu Peltola | | Plt | 623+540 | | Joensuu | | K | K |
| Joensuu Sulkulahti | | Sul | 622+650 | | Joensuu | | | K |
| Jokela | | Jlk | 47+937 | Helsinki – Riihimäki | Tuusula | | K | |
| Jokikylä | | Jkk | 688+344 | Kontiomäki – Ämmänsaari | Ristijärvi | | | |
| Joroinen | Jorois | Jor | 414+617 | Huutokoski – Savonlinna | Joroinen | | K | |
| Jorvas | | Jrs | 32+322 | Helsinki – Karjaa | Kirkkonummi | | | |
| Joutjärvi | | Jou | 133+460 | Lahti – Heinola | Lahti | K | K | |
| Joutseno | | Jts | 305+826 | Luumäki – Parikkala | Joutseno | K | K | K |
| Joutsijärvi | | Jsj | 1082+855 | Laurila – Kelloseikä | Kemijärvi | | K | |
| Juankoski | | Jki | 531+995 | Viinijärvi – Siilinjärvi | Juankoski | K | K | |
| Jukajärvi | | Jkj | 637+876 | Joensuu – Ilomantsi | Joensuu | | | |
| Jutla | | Jut | 94+620 | Riihimäki – Lahti | Kärkölä | K | | |
| Juupajoki | | Jj | 246+580 | Orivesi – Haapamäki | Juupajoki | | | |
| Juurikorpi | | Jri | 224+898 | Kouvola – Kotka | Kotka | K | | |
| Jyräkö | | Jyr | 165+774 | Lahti – Heinola | Heinola | | | |
| Jyväskylä | | Jy | 377+435 | Orivesi – Jyväskylä | Jyväskylä | K | K | K |
| Jämsä | | Jäs | 284+084 | Orivesi – Jyväskylä | Jämsä | K | | K |
| Jämsänkoski | | Jsk | 287+917 | Orivesi – Jyväskylä | Jämsänkoski | K | K | K |
| Järvelä | | Jr | 103+596 | Riihimäki – Lahti | Kärkölä | K | K | K |
| Järvenpää | Träskända | Jp | 36+786 | Helsinki – Riihimäki | Järvenpää | | | |
| Kaipainen | | Kpa | 214+451 | Kouvola – Luumäki | Anjalankoski | M | K | K |
| Kaipola | | Kla | 290+303 | Jämsä – Kaipola | Jämsä | | K | K |
| Kairokoski | | Kko | 423+184 | Niinisalo – Parkano | Parkano | | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|---------------|-----------------|-------------|---------|---------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Kaitjärvi | | Kjr | 226+912 | Kouvola – Luumäki | Luumäki | M | | |
| Kajaani | Kajana | Kaj | 633+491 | Isalmi – Kontiomäki | Kajaani | K | K | K |
| Kaleton | | Ktn | 320+875 | Haapamäki – Jyväskylä | Keuruu | | | |
| Kalkku | | Kau | 199+471 | Lielähti – Kokemäki | Tampere | | K | |
| Kalliovarasto | | Kao | 644+770 | Isalmi – Kontiomäki | Kajaani | | K | |
| Kalliolahti | | Kll | 465+822 | Huutokoski – Savonlinna | Savonlinna | | | |
| Kalvitsa | | Ksa | 330+634 | Kouvola – Pieksämäki | Mikkeli | K | | |
| Kangas | | Kgs | 642+466 | Ylivieska – Oulu | Ylivieska | K | | K |
| Kannelmäki | Gamlas | Kan | 9+300 | Huopalahti – Vantaankoski | Helsinki | K | | |
| Kannonkoski | | Ksi | 488+694 | Jyväskylä – Haapajärvi | Kannonkoski | | | |
| Kannus | | Kns | 591+582 | Kokkola – Ylivieska | Kannus | K | | K |
| Karhejärvi | | Krr | 224+902 | Tampere – Seinäjoki | Ylöjärvi | K | | |
| Karhukangas | | Khg | 621+508 | Kokkola – Ylivieska | Ylivieska | K | | |
| Karjaa | Karis | Kr | 157+817 | Hyvinkää – Karjaa | Karjaa | K | K | K |
| Karkku | | Kru | 230+733 | Lielähti – Kokemäki | Vammala | K | | |
| Karvainen | | Kar | 247+320 | Toijala – Turku | Aura | K | | |
| Kaskinen | Kaskö | Ksk | 530+522 | Seinäjoki – Kaskinen | Kaskinen | M | K | |
| Kauhajoki | | Kji | 472+720 | Seinäjoki – Kaskinen | Kauhajoki | | K | |
| Kauhava | | Kha | 455+728 | Seinäjoki – Kokkola | Kauhava | K | K | K |
| Kauklahti | Köklax | Klh | 24+277 | Helsinki – Karjaa | Espoo | K | | K |
| Kaulinranta | | Klr | 963+350 | Tornio – Kolari | Ylitornio | K | | |
| Kauniainen | Grankulla | Kni | 16+054 | Helsinki – Karjaa | Kauniainen | K | K | K |
| Kauppiänmäki | | Kpl | 568+751 | Isalmi – Kontiomäki | Isalmi | | | |
| Kausala | | Ka | 169+436 | Lahti – Kouvola | Iitti | | | |
| Kautua | | Ktu | 310+423 | Kiukainen – Säkylä | Eura | | | K |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|--------------|-----------------|-------------|----------|--------------------------|--------------|-------------------|---------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåraneläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Keitelepohja | | Ktp | 519+256 | Jyväskylä – Haapajärvi | Vittasaari | | | |
| Kekomäki | | Kek | 79+288 | Riihimäki – Lahti | Hausjärvi | K | | |
| Kello | | Kej | 336+703 | Orivesi – Jyväskylä | Jyväskylä | | | |
| Keikkamäki | | Klk | 399+992 | Jyväskylä – Pieksämäki | Laukaa | | K | |
| Kelloselkä | | Kls | 1135+115 | Laurila – Kelloselkä | Salla | | | |
| Kemi | | Kem | 858+300 | Oulu – Laurila | Kemi | K | K | K |
| Kemijärvi | | Kjä | 1056+399 | Laurila – Kelloselkä | Kemijärvi | K | K | |
| Kemira | | Ker | 495+600 | Viinijärvi – Siilinjärvi | Siilinjärvi | | K | |
| Kempele | | Kml | 741+075 | Ylivieska – Oulu | Kempele | K | | |
| Kera | | Kea | 14+536 | Helsinki – Karjaa | Espoo | K | | |
| KERAVA | | Kav | | Helsinki – Riihimäki | | | | |
| Kerava asema | Kervo | Ke | 28+869 | | Kerava | | K | K |
| Kytömaa | | Kyt | 31+203 | | Kerava | | | |
| Kerimäki | | Klä | 495+531 | Savonlinna – Parikkala | Kerimäki | K | K | K |
| Kesälahti | | Kti | 428+003 | Parikkala – Säkäniemi | Kesälahti | K | K | |
| Keuruu | | Kau | 316+041 | Haapamäki – Jyväskylä | Keuruu | K | | |
| Kihniö | | Kiö | 444+460 | Parkano – Kihniö | Kihniö | | | |
| Kiiala | Kiiala | Kia | 60+013 | Olli – Porvoon keskusta | Porvoo | | | |
| Kilo | | Kil | 13+035 | Helsinki – Karjaa | Espoo | | | |
| Kilpua | | Kua | 668+910 | Ylivieska – Oulu | Oulainen | K | | |
| Kinahmi | | Knh | 508+922 | Viinijärvi – Siilinjärvi | Nilsia | | K | |
| Kinni | | Kii | 247+982 | Kouvola – Pieksämäki | Mäntyharju | K | | |
| (Kirjola) | | | 384+483 | Luumäki – Parikkala | Parikkala | | K | |
| Kirkkonummi | Kyrkslätt | Kkn | 37+503 | Helsinki – Karjaa | Kirkkonummi | K | | K |
| Kirkniemi | Gernäs | Krn | 136+261 | Hyvinkää – Karjaa | Lohja | M | K | K |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------|-----------------|-------------|----------|-------------------------|--------------|-------------------|---------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåraneläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Kitee | | Kit | 460+016 | Parikkala – Säkäniemi | Kitee | K | K | K |
| Kiukainen | | Kn | 297+395 | Kokemäki – Rauma | Kiukainen | K | | |
| Kiuruvesi | | Kv | 583+985 | Iisalmi – Ylivieska | Kiuruvesi | K | K | K |
| Kivesjärvi | | Kvj | 878+146 | Oulu – Kontiomäki | Paltamo | K | | |
| Kotavaara | | Koh | 775+927 | Joensuu – Kontiomäki | Nurmes | | | |
| Koivu | | Kvu | 923+373 | Laurila – Kelloseleä | Tervola | K | | |
| Koivuhovi | Björkgård | Kvh | 17+861 | Helsinki – Karjaa | Espoo | | | |
| Koivukylä | Björkby | Kvy | 19+440 | Helsinki – Riihimäki | Vantaa | | | |
| Kokemäki | Kumo | Kki | 284+442 | Lielähti – Kokemäki | Kokemäki | K | | K |
| Kokkola | Karleby | Kok | 551+441 | Seinäjoeki – Kokkola | Kokkola | K | K | K |
| Kolari | | Kli | 1067+206 | Tornio – Kolari | Kolari | K | K | K |
| Kolho | | Klo | 286+265 | Orivesi – Haapamäki | Vilppula | | K | K |
| Kolppi | Källby | Kpi | 525+100 | Seinäjoeki – Kokkola | Pedersöre | K | K | K |
| Kommila | | Kmm | 429+700 | Huutokoski – Viinijärvi | Varkaus | | K | |
| Komu | | Kom | 607+174 | Iisalmi – Ylivieska | Pyhäjärvi | | K | |
| Kontiolahti | | Khi | 640+295 | Joensuu – Kontiomäki | Kontiolahti | K | | |
| Kontiomäki | | Kon | 658+786 | Iisalmi – Kontiomäki | Paltamo | K | K | K |
| Koppnäs | | Kop | 203+540 | Karjaa – Hanko | Hanko | | K | |
| Koria | | Kra | 185+440 | Lahti – Kouvola | Elimäki | | K | K |
| (Korjala) | | | 192+677 | Kouvola – Kuusankoski | Kouvola | | K | |
| Korkeakoski | | Kas | 247+910 | Orivesi – Haapamäki | Juupajoki | K | K | K |
| Korso | | Krs | 22+669 | Helsinki – Riihimäki | Vantaa | K | | |
| Korvensuo | | Ksu | 50+500 | Kerava – Hakosilta | Mäntsälä | K | | |
| Koskenkorva | | Kos | 442+447 | Seinäjoeki – Kaskinen | Ilmäki | | | |
| Kotavaara | | Ktv | 1064+700 | Laurila – Kelloseleä | Kemijärvi | K | K | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------------|-----------------|-------------|----------|--------------------------|---------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| KOTKA | | Kot | | Kouvola – Kotka | | M | | |
| Kotka asema | | Kta | 242+775 | | Kotka | | K | K |
| Kotka Hovinsaari | | Hos | 240+400 | | Kotka | | K | |
| Kotka satama | | Kts | 243+579 | | Kotka | | K | |
| Kotka tavarat | | | 240+870 | | Kotka | | K | |
| Kotka Mussalo | | Miss | 247+057 | | Kotka | | K | |
| Paimenportti | | Pti | 241+190 | | Kotka | | | |
| KOUVOLA | | Kvl | | Lahti – Kouvola | | M | | |
| Kouvola asema | | Kv | 191+540 | | Kouvola | | K | K |
| Kouvola lajittelu | | Kvla | 192+570 | | Kouvola | | K | K |
| Kouvola Oikoraide | | Oik | 194+460 | | Kouvola | | | |
| Kouvola tavarat | | Kvt | 194+050 | | Kouvola | | K | K |
| Kuusankoski | | Kuk | 199+290 | | Kuusankoski | | K | K |
| Kovjoki | | Koi | 508+925 | Seinäjoki – Kokkola | Uusikaarlepyy | K | | |
| Kruunupyyl | | Kpy | 537+585 | Seinäjoki – Kokkola | Kruunupyyl | K | K | K |
| Kuivasjärvi | | Kis | 276+327 | Tampere – Seinäjoki | Parkano | K | | |
| KUOPIO | Kronoby | Kpo | | Pieksämäki – Siilinjärvi | | M | | |
| Kuopio asema | | Kuo | 464+590 | | Kuopio | | | K |
| Kuopio tavarat | | Kuot | 465+500 | | Kuopio | | K | K |
| | | Krk | 452+013 | Seinäjoki – Kaskinen | Kurikka | | | |
| Kurkimäki | | Krm | 444+074 | Pieksämäki – Siilinjärvi | Kuopio | K | | K |
| Kursu | | Kuu | 1095+034 | Laurila – Kellosoelkä | Salla | | | |
| Kuurila | | Ku | 138+769 | Riihimäki – Tampere | Kalvola | K | | |
| Kuusanklampi | | Ksn | 194+000 | Kouvola – Kuusankoski | Kouvola | | K | |
| Kuusivaara | | Kvr | 1037+026 | Laurila – Kellosoelkä | Kemijärvi | | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|--------------|-----------------|-------------|---------|-------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Kyllälahti | | Kyn | 742+960 | Joensuu – Kontiomäki | Lieska | | | |
| Kymi | Kymmene | Ky | 233+450 | Kouvola – Kotka | Kotka | M | K | K |
| Kyminlinna | | Kln | 237+229 | Kouvola – Kotka | Kotka | | | |
| Kyrö | | Kö | 232+875 | Toijala – Turku | Karainen | K | K | K |
| Kyrölä | | Krö | 34+784 | Helsinki – Riihimäki | Järvenpää | | | |
| Kälviä | | Klv | 568+144 | Kokkola – Ylivieska | Kälviä | K | | |
| Köykkäri | Kelviä | Kök | 486+491 | Seinäjohti – Kokkola | Alahärmä | K | | |
| Laaja | | Lja | 722+271 | Kontiomäki – Pesiökyliä | Suomussalmi | K | | |
| Lahdenperä | | Lpr | 267+080 | Orivesi – Jyväskylä | Jämsä | K | | |
| Lahnaslampi | | Lhn | 881+053 | Vuokatti – Lahnaslampi | Sotkamo | | K | |
| Lahti | Lahtis | Lh | 130+170 | Riihimäki – Lahti | Lahti | K | K | K |
| Laihia | Laihela | Lai | 468+916 | Seinäjohti – Vaasa | Laihia | K | | |
| Lakiala | | Lak | 209+214 | Tampere – Seinäjohti | Ylöjärvi | K | | |
| Lamminkoski | | Lmk | 268+785 | Tampere – Seinäjohti | Parkano | K | | |
| Lapinjärvi | | Lpj | 185+432 | Lahti – Loviisan satama | Lapinjärvi | | | |
| Lapinlahti | Lapträsk | Lna | 525+604 | Silinjärvi – Iisalmi | Lapinlahti | K | | |
| Lapinneva | | Lpn | 415+618 | Niinisalo – Parkano | Parkano | | | |
| Lappeenranta | Villmanstrand | Lr | 287+726 | Luumäki – Parikkala | Lappeenranta | K | K | K |
| Lappila | | Laa | 97+693 | Riihimäki – Lahti | Kärkölä | | | |
| Lappohja | Lappvik | Lpo | 189+639 | Karjaa – Hanko | Hanko | K | K | K |
| Lapua | Lappo | Lpa | 441+094 | Seinäjohti – Kokkola | Lapua | K | K | K |
| Larvakytö | | Lyö | 333+057 | Tampere – Seinäjohti | Seinäjohti | K | | |
| Laukaa | | Lau | 401+193 | Jyväskylä – Haapajärvi | Laukaa | | | |
| Laurila | | Lla | 865+776 | Oulu – Laurila | Keminmaa | K | | K |
| Lauritsala | | Lrs | 291+936 | Luumäki – Parikkala | Lappeenranta | K | K | K |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|---------------------------|-----------------|-------------|---------|---------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Lautiosaari | | Li | 863+064 | Oulu – Laurila | Kemi | K | | K |
| Leikola | | Lkl | 276+011 | Kouvola – Pieksämäki | Hirvensalmi | K | | |
| Lempäälä | | Lpä | 165+928 | Riihimäki – Tampere | Lempäälä | K | | |
| Leppäkoski | | Lk | 87+830 | Riihimäki – Tampere | Janakkala | K | | |
| Leppävaara | Alberga | Lpv | 11+249 | Helsinki – Karjaa | Espoo | K | | K |
| Leteensuo | | Lts | 123+554 | Riihimäki – Tampere | Hattula | K | | |
| Liekka | | Lis | 728+121 | Joensuu – Kontiomäki | Liekka | K | K | K |
| (Liekkan teollisuuskyliä) | | | 728+847 | Joensuu – Kontiomäki | Liekka | | K | |
| Lielähti | | Llh | 193+393 | Tampere – Seinäjoki | Tampere | K | K | K |
| Lievestuore | | Lvt | 402+191 | Jyväskylä – Pieksämäki | Laukaa | K | K | K |
| Liminka | Limingo | Lka | 728+483 | Ylivieska – Oulu | Liminka | K | | K |
| Lohiluoma | | Luo | 463+619 | Seinäjoki – Kaskinen | Kurikka | | | |
| Lohja | Lojo | Lo | 122+965 | Hyvinkää – Karjaa | Lohja | | | |
| Lohjanjärvi | | Loj | 128+036 | Lohja – Lohjanjärvi | Lohja | | K | |
| (Lohja Oy) | | | 588+427 | Joensuu – Siilinjärvi | Outokumpu | | K | |
| Loimaa | | Lm | 208+870 | Toijala – Turku | Loimaa | K | K | K |
| Louhela | Klippsta | Loh | 13+190 | Huopalahti – Vantaankoski | Vantaa | | | |
| Loukolampi | | Lol | 360+013 | Kouvola – Pieksämäki | Pieksämäki | K | | |
| Loviisan satama | Lovisa hamn | Lvs | 207+209 | Lahti – Loviisan satama | Lovisa | M | K | K |
| Luikonlahti | | Lui | 557+061 | Viinjärvi – Siilinjärvi | Kaavi | K | K | |
| Luoma | Bobäck | Lma | 27+807 | Helsinki – Karjaa | Kirkkonummi | | | |
| Lustikulla | | Lul | 35+347 | Helsinki – Riihimäki | Järvenpää | K | | |
| Lusto | | Lus | 509+170 | Savonlinna – Parikkala | Punkaharju | | | |
| Luumäki | | Lä | 250+540 | Kouvola – Luumäki | Luumäki | K | K | K |
| Lähdemäki | | Läh | 79+373 | Kerava – Hakosilta | Orimattila | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-----------------|-----------------|-------------|----------|--------------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Länkipohja | | Läp | 256+024 | Orivesi – Jämsänkoski | Jämsä | K | | |
| Maanselkä | | Mlk | 836+049 | Joensuu – Kontiomäki | Sotkamo | | | |
| Maaria | St Marie | Mri | 262+070 | Toijala – Turku | Turku | K | | |
| Madesjärvi | | Md | 291+821 | Tampere – Seinäjoki | Jalasjärvi | K | | |
| Majajärvi | | Mij | 216+317 | Tampere – Seinäjoki | Ylöjärvi | K | | |
| Malmi | Malm | Ml | 10+900 | Helsinki – Riihimäki | Helsinki | K | | |
| Malminkartano | Malmgård | Mlo | 10+730 | Huopalahti – Vantaankoski | Helsinki | | | |
| Mankki | Mankby | Mnk | 25+401 | Helsinki – Karjaa | Kirkkonummi | | K | |
| Markkala | | Mrk | 403+737 | Pieksämäki – Siilinjärvi | Suonenjoki | K | | |
| Martinkaakso | Mårtensdal | Mrl | 14+010 | Huopalahti – Vantaankoski | Vantaa | K | | |
| Masala | Masaby | Mas | 29+561 | Helsinki – Karjaa | Kirkkonummi | | | |
| Matkaneva | | Mtv | 562+059 | Kokkola – Ylivieska | Kälviä | K | | |
| Mattila | | Mat | 159+906 | Riihimäki – Tampere | Lempäälä | K | | |
| Meltola | Mjöbolsta | Mel | 149+862 | Kirkniemi – Karjaa | Karjaa | | K | |
| (Metro) | | Metr | 7+515 | Helsinki – Riihimäki | Helsinki | | K | |
| Metsäkansa | | Msä | 155+811 | Toijala – Valkeakoski | Valkeakoski | | | |
| Mikkeli | St Michel | Mi | 305+165 | Kouvola – Pieksämäki | Mikkeli | K | | K |
| Misi | | Mis | 1021+255 | Laurila – Kelloseleä | Rovaniemi | | | |
| Mommila | | Mla | 91+430 | Riihimäki – Lahti | Hausjärvi | | | |
| Muhos | | Mh | 788+424 | Oulu – Kontiomäki | Muhos | K | | K |
| Mukkula | | Muk | 140+012 | Lahti – Mukkula | Lahti | | K | K |
| Murtomäki | | Mur | 613+165 | Iisalmi – Kontiomäki | Kajaani | K | | |
| Mustio | Svartå | Mso | 143+000 | Hyvinkää – Karjaa | Karjaa | | K | |
| Mustola | | Mst | 295+526 | Lappeenranta – Mustolan satama | Lappeenranta | | K | |
| Mustolan satama | | Mst | 296+720 | Lappeenranta – Mustolan satama | Lappeenranta | | K | |
| Muukko | | Mko | 297+112 | Luumäki – Parikkala | Lappeenranta | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|--------------|-----------------|-------------|---------|------------------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Muurame | | Muu | 324+768 | Orivesi – Jyväskylä | Muurame | K | | |
| Murola | | Mul | 948+494 | Laurila – Kelloseleä | Rovaniemi | K | | |
| Myllykangas | | Mys | 815+693 | Oulu – Laurila | li | K | | |
| Myllykoski | | Mki | 203+742 | Kouvola – Kotka | Anjalankoski | K | | |
| Myllymäki | | My | 333+721 | Haapamäki – Seinäjoki | Ähtäri | | | K |
| Myllyoja | | Myl | 161+727 | Lahti – Heinola | Heinola | K | | |
| Mynttilä | | Myt | 270+889 | Kouvola – Pieksämäki | Mäntyharju | K | | |
| Mynämäki | | Myn | 229+607 | Turku – Uusikaupunki – Hangonsaari | Mynämäki | M | | |
| Myrskylä | Mörskom | Myä | 169+771 | Lahti – Loviisan satama | Lapinjärvi | | | |
| Myrymäki | Myrbacka | Myr | 12+130 | Huopalahti – Vantaankoski | Vantaa | K | | |
| Mäkkylä | | Mäk | 9+511 | Helsinki – Karjaa | Espoo | | | |
| Mäntsälä | | Mlä | 59+210 | Kerava – Hakosilta | Mäntsälä | K | | |
| Mänttä | | Män | 282+740 | Vilppula – Mänttä | Mänttä | | K | K |
| Mäntyharju | | Mr | 262+680 | Kouvola – Pieksämäki | Mäntyharju | K | K | K |
| Mäntyluoto | | Mn | 342+020 | Pori – Mäntyluoto | Pori | M | K | K |
| Naantali | Nädendal | Nnl | 213+934 | Raisio – Naantali | Naantali | | K | K |
| Naarajärvi | | Nri | 449+862 | Jyväskylä – Pieksämäki | Pieksämäki | | K | |
| Nakkila | | Nal | 308+091 | Kokemäki – Pori | Nakkila | | | |
| Nastola | | Nsl | 146+169 | Lahti – Kouvola | Nastola | | | |
| Niemenpää | | Nmp | 923+605 | Tornio – Kolari | Tornio | K | | |
| Niinimaa | | Nii | 383+155 | Haapamäki – Seinäjoki | Alavus | | | |
| Niinisalo | | Nns | 386+215 | Niinisalo – Parkano | Kankaanpää | | K | |
| Niirala | | Nri | 555+846 | Niirala-raja – Säkäniemi | Tohmajärvi | K | K | K |
| Niirala-raja | | Nrir | 554+080 | Niirala-raja – Säkäniemi | Tohmajärvi | K | | |
| Niittylahti | | Nth | 613+475 | Säkäniemi – Joensuu | Pyhäselkä | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|---------------|-----------------|-------------|---------|----------------------------|--------------|-------------------|--------------------------|---------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växlarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Nikkilä | Nickby | Nlä | 39+176 | Kerava – Porvoo / Sköldvik | Sipoo | | | |
| Nivala | | Nvl | 676+878 | Isalmi – Ylivieska | Nivala | K | | |
| Nokia | | Noa | 204+004 | Lielahiti – Kokemäki | Nokia | K | K | K |
| Nummela | | Nm | 109+368 | Hyvinkää – Karjaa | Vihti | | | |
| Nuppulinnä | | Nup | 44+210 | Helsinki – Riihimäki | Tuusula | | | |
| Nurmes | | Nrm | 784+420 | Joensuu – Kontiomäki | Nurmes | K | | K |
| Närpiö | Närpes | När | 518+254 | Seinäjohti – Kaskinen | Närpiö | | | |
| Ohenmäki | | | 542+264 | Sillinjärvi – Isalmi | Isalmi | | | |
| Oitti | | Oi | 86+809 | Riihimäki – Lahti | Hausjärvi | | | |
| Olli | | Olli | 45+734 | Kerava – Porvoo / Sköldvik | Porvoo | K | K | |
| Onttola | | Ont | 631+177 | Joensuu – Viinijärvi | Joensuu | | K | |
| Orimattila | | Om | 150+407 | Lahti – Loviisan satama | Orimattila | | | |
| Orivesi | | Ov | 228+276 | Tampere – Orivesi | Orivesi | K | K | K |
| Otalampi | | Otp | 94+900 | Hyvinkää – Karjaa | Vihti | | | |
| Otanmäki | | Otm | 638+822 | Murtomäki – Otanmäki | Kajaani | | K | K |
| Otava | | Ot | 290+521 | Kouvola – Pieksämäki | Mikkeli | K | | K |
| Otavan satama | | Ots | 292+885 | Otava – Otavan satama | Mikkeli | | K | K |
| Oulainen | | Ou | 657+850 | Ylivieska – Oulu | Oulainen | K | K | K |
| OULU | Uleåborg | Oul | | Ylivieska – Oulu | Oulu | M | | |
| Oulu asema | | Oi | 752+778 | | Oulu | | | K |
| Oulu Nokela | | Nok | 750+030 | | Oulu | | K | K |
| Oulu Oritkari | | Ori | 751+180 | | Oulu | | K | K |
| Oulu tavara | | Olt | 751+360 | | Oulu | | K | K |
| Oulu Tuira | | Tua | 755+510 | | Oulu | | K | K |
| Paimio | Pemar | Po | 171+885 | Karjaa – Turku | Paimio | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Likenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|------------------------|-----------------|-------------|----------|-------------------------|--------------|------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Palopuro | | Plp | 54+535 | Helsinki – Riihimäki | Hyvinkää | K | | |
| Paltamo | | Pto | 901+579 | Oulu – Kontiomäki | Paltamo | K | K | K |
| (Palta Oy) | | | 905+050 | Oulu – Kontiomäki | Paltamo | | K | |
| Pankakoski | | Pas | 731+865 | Liekka – Pankakoski | Liekka | | | |
| Parikkala | | Par | 387+302 | Luumäki – Parikkala | Parikkala | K | | K |
| Parkano | | Pko | 262+483 | Tampere – Seinäjoki | Parkano | K | K | K |
| Parola | | Prl | 115+764 | Riihimäki – Tampere | Hattula | | K | |
| Pello | | Pel | 1002+632 | Tornio – Kolari | Pello | K | K | |
| Peltosalmi | | Pni | 545+355 | Siiinjärvi – Iisalmi | Iisalmi | | K | |
| (Perniön viljavarasto) | | Pö | 129+261 | Pasila – Turku satama | Perniö | | K | |
| Peräseinäjoki | | Psj | 318+481 | Tampere – Seinäjoki | Seinäjoki | K | K | |
| Pesökylä | | Psk | 732+752 | Kontiomäki – Ämmänsaari | Suomussalmi | M | | K |
| Petäjävesi | | Pvi | 343+357 | Haapamäki – Jyväskylä | Petäjävesi | K | | |
| PIEKSÄMÄKI | | Pie | | Kouvola – Pieksämäki | | K | | |
| Pieksämäki asema | | Pm | 376+000 | | Pieksämäki | | K | K |
| Pieksämäki lajittelu | | Pmla | 378+640 | | Pieksämäki | | K | K |
| Pieksämäki tavara | | Pmt | 379+960 | | Pieksämäki | | K | K |
| Pieksämäki Temu | | Tmu | 377+340 | | Pieksämäki | | K | K |
| Pietarsaari | Jakobstad | Pts | 528+780 | Pännänen – Pietarsaari | Pietarsaari | M | K | K |
| Pihlajavesi | | Ph | 312+500 | Haapamäki – Seinäjoki | Keuruu | K | | |
| Pihlava | | Piv | 337+091 | Pori – Mäntyluoto | Pori | | K | |
| Pilttipudas | | Pp | 540+605 | Jyväskylä – Haapajärvi | Pilttipudas | | | |
| Piikkiö | | Pik | 182+785 | Karjaa – Turku | Piikkiö | K | | |
| Pikkarala | Pikis | Pkl | 771+765 | Oulu – Kontiomäki | Oulu | K | K | |
| Pitäjänmäki | Sockenbacka | Pjm | 8+474 | Helsinki – Karjaa | Helsinki | | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------------|-----------------|-------------|---------|------------------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Pohjankuru | Skuru | Pku | 94+907 | Karjaa – Turku | Pohja | K | K | |
| Pohjois-Haaga | Norra Haga | Poh | 8+050 | Huopalahti – Vantaankoski | Helsinki | | | |
| Pohjois-Louko | | Plu | 329+329 | Tampere – Seinäjoki | Seinäjoki | K | | |
| Poikkeus | | Pkk | 254+744 | Tampere – Seinäjoki | Parkano | K | | |
| Poiksilta | | Poi | 416+728 | Parikkala – Säkänieniemi | Kesälahti | | | |
| Pori | Björneborg | Pri | 322+278 | Kokemäki – Pori | Pori | M | K | K |
| Porokylä | | Por | 787+046 | Joensuu – Kontiomäki | Nurmes | | K | |
| Porvoo | Borgå | Prv | 62+287 | Olli – Porvoon keskusta | Porvoo | | | K |
| Porvoon keskusta | Borgå Centrum | Pvk | 62+934 | Olli – Porvoon keskusta | Porvoo | | | |
| Puhos | | Pus | 452+808 | Parikkala – Säkänieniemi | Kitee | K | K | K |
| Puistola | Parkstad | Pla | 14+050 | Helsinki – Riihimäki | Helsinki | | | |
| Pukimäki | Bocksbacka | Pmk | 9+442 | Helsinki – Riihimäki | Helsinki | | | |
| Pulsa | | Pl | 262+491 | Luumäki – Vainikkala-raja | Lappeenranta | K | | |
| Punkaharju | | Pun | 515+111 | Savonlinna – Parikkala | Punkaharju | K | K | K |
| Purola | | Pur | 40+533 | Helsinki – Riihimäki | Järvenpää | K | | |
| Pyhäkumpu | | Pyk | 615+415 | Pyhäkumpu erk.vh – Pyhäkumpu | Pyhäjärvi | | K | |
| Pyhäkumpu erk.vh. | | | 613+511 | Isalmi – Ylivieska | Pyhäjärvi | K | | |
| Pyhäsalmi | | Phä | 615+934 | Isalmi – Ylivieska | Pyhäjärvi | K | K | |
| Pännänen | Bennäs | Pnä | 518+604 | Seinäjoki – Kokkola | Pedersöre | K | | K |
| Pääskylähti | | Pky | 484+913 | Savonlinna – Parikkala | Savonlinna | K | K | K |
| Raahе | Brahestad | Rhe | 726+726 | Tuomioja – Raahе | Raahе | M | K | |
| Raippo | | Rpo | 270+052 | Luumäki – Vainikkala-raja | Lappeenranta | K | K | |
| Raisio | Reso | Rai | 207+829 | Turku – Uusikaupunki – Hangonsaari | Raisio | M | K | |
| Rajamäki | | Rm | 72+267 | Hyvinkää – Karjaa | Nurmijärvi | | K | |
| Rajaperkiö | | Rjp | 448+396 | Seinäjoki – Kokkola | Lapua | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|---------------------|-----------------|-------------|---------|-------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Rantasalmi | | Rmi | 445+165 | Huutokoski – Savonlinna | Rantasalmi | | K | |
| Rasinsuo | | Ras | 258+510 | Luumäki – Parikkala | Luumäki | K | | |
| Ratikylä | | Rlä | 284+344 | Tampere – Seinäjoki | Kiinio | K | | |
| Rauha | | Rah | 318+490 | Luumäki – Parikkala | Joutseno | K | | K |
| Rauhalahti | | Rhl | 380+510 | Jyväskylä – Pieksämäki | Jyväskylä | | | |
| Rauma | | Rma | 331+659 | Kokemäki – Rauma | Rauma | M | K | K |
| Raunio | Raumo | Rio | 464+845 | Seinäjoki – Kokkola | Kauhava | K | | |
| Rautaruukki | | Rat | 730+050 | Tuomioja – Raahе | Raahе | | K | |
| Rautjärvi | | Rjä | 345+788 | Luumäki – Parikkala | Rautjärvi | K | | |
| (Rautpohja) | | | 372+841 | Haaparnäki – Jyväskylä | Jyväskylä | | K | |
| Rekola | Räckhals | Rkl | 20+615 | Helsinki – Riihimäki | Vantaa | K | | |
| Retretti | | Ree | 507+500 | Savonlinna – Parikkala | Punkaharju | | | |
| Riihimäki | | Rli | | Helsinki – Riihimäki | | K | | |
| Arolampi | | Arp | 66+600 | | Riihimäki | | | |
| Riihimäki asema | | Ri | 71+410 | | Riihimäki | | K | K |
| Riihimäki lajittelu | | Rila | 70+068 | | Riihimäki | | | K |
| Riihimäki tavara | | Rit | 68+773 | | Riihimäki | | | K |
| Riippa | | Rpa | 578+065 | Kokkola – Ylivieska | Kälviä | K | | |
| Ristina | | Rst | 291+162 | Mynttilä – Ristina | Ristina | | K | K |
| Ristijärvi | | Rjv | 676+804 | Kontiomäki – Ämmänsaari | Ristijärvi | | | |
| Rovaniemi | | Roі | 971+775 | Laurila – Kelloseleä | Rovaniemi | M | K | K |
| Ruha | | Rha | 433+128 | Seinäjoki – Kokkola | Lapua | K | | |
| Runni | | Rnn | 568+518 | Iisalmi – Ylivieska | Iisalmi | | | |
| Ruosniemi | | Rsn | 330+936 | Pori – Ruosniemi | Pori | | K | |
| Ruukki | | Rki | 705+228 | Ylivieska – Oulu | Sillakajoki | K | K | K |
| Ruusutorppa | | Rus | 11+927 | Helsinki – Karjaa | Espoo | K | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-----------------------|-----------------|-------------|----------|--------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Ryttylä | | Ry | 80+770 | Riihimäki – Tampere | Hausjärvi | | K | |
| Röykkä | | Rö | 80+657 | Hyvinkää – Karjaa | Nurmijärvi | | K | |
| Röyttä | | Röy | 893+917 | Tornio – Röyttä | Tornio | | K | |
| Saakoski | | Saa | 305+373 | Orivesi – Jyväskylä | Korpilahti | K | | |
| Saari | | Sr | 405+246 | Parikkala – Säkäniemi | Parikkala | K | | |
| Saarijärvi | | Srj | 452+723 | Jyväskylä – Haapajärvi | Saarijärvi | M | K | |
| Salla | | Sll | 1121+403 | Laurila – Kellosele | Salla | | | |
| Salminen | | Sln | 426+718 | Pieksämäki – Siilinjärvi | Suonenjoki | K | | |
| Salmivaara | | Smv | 1111+444 | Laurila – Kellosele | Salla | | | |
| Salo | | Slo | 143+981 | Karjaa – Turku | Salo | K | | K |
| Salpausselkä | | Sss | 129+372 | Lahti – Salpausselkä | Lahti | | | |
| Sammalisto | | Sam | 74+487 | Riihimäki – Tampere | Riihimäki | K | | |
| Santala | Sandö | Sta | 196+908 | Karjaa – Hanko | Hanko | | | |
| Santanäki | | | 838+314 | Oulu – Kontiomäki | Vaala | | | |
| Saunakallio | | Sau | 38+846 | Helsinki – Riihimäki | Järvenpää | K | K | K |
| Savio | | Sav | 26+265 | Helsinki – Riihimäki | Kerava | | K | |
| Savonlinna | Nyslott | Sl | 481+772 | Savonlinna – Parikkala | Savonlinna | K | K | K |
| Savonlinna-Kauppatori | | Slk | 482+748 | Savonlinna – Parikkala | Savonlinna | | | |
| (Savontalo) | | Nip | 194+017 | Kouvola – Kuusankoski | Kouvola | M | K | |
| SEINÄJOKI | | Sei | | Tampere – Seinäjoki | | | | |
| Seinäjoki asema | | Sk | 418+001 | | Seinäjoki | | K | K |
| Seinäjoki tavara | | Skt | 416+580 | | Seinäjoki | | K | K |
| Selänpää | | Spä | 209+869 | Kouvola – Pieksämäki | Valkeala | K | | |
| Sieppiärvä | | Spj | 1045+904 | Tornio – Kolari | Kolari | | | |
| Sievi | | Svi | 613+592 | Kokkola – Ylivieska | Sievi | K | | K |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------|-----------------|-------------|---------|----------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Siikämäki | | Skä | 389+745 | Pieksämäki – Huutokoski | Pieksämäki | K | | |
| Siilinjärvi | | Sij | 489+718 | Pieksämäki – Siilinjärvi | Siilinjärvi | K | K | K |
| Simo | | Sim | 833+715 | Oulu – Laurila | Simo | K | | |
| Simpelä | | Spl | 368+317 | Luumäki – Parikkala | Rautjärvi | K | K | K |
| Sipilä | | Sip | 68+697 | Kerava – Hakosilta | Mäntsälä | K | | |
| Sisätö | | Stö | 235+602 | Tampere – Seinäjoki | Ikaalinen | K | | |
| Siuntio | | Sti | 51+285 | Helsinki – Karjaa | Siuntio | K | | |
| Siuro | Sjundeå | Siu | 213+355 | Lielähti – Kokemäki | Nokia | K | | |
| Skogby | | Sgy | 184+790 | Karjaa – Hanko | Tammisaari | | | |
| Sköldvik | Kilpilähti | Sld | 56+360 | Kerava – Porvoo / Sköldvik | Porvoo | M | K | K |
| Soinlahti | | Soa | 559+651 | Iisalmi – Kontiomäki | Iisalmi | | K | K |
| Sorsasalo | | Sor | 473+775 | Pieksämäki – Siilinjärvi | Kuopio | | | |
| Sukeva | | Skv | 589+222 | Iisalmi – Kontiomäki | Sonkajärvi | | | |
| Suolahti | | Suo | 417+796 | Jyväskylä – Haapajärvi | Äänekoski | K | K | K |
| Suonenjoki | | Snj | 413+842 | Pieksämäki – Siilinjärvi | Suonenjoki | K | | K |
| Suoniemi | | Snm | 220+655 | Lielähti – Kokemäki | Nokia | K | | |
| Syrjä | | Syr | 452+865 | Huutokoski – Viinijärvi | Heinävesi | | | |
| Syrjämäki | | Ski | 341+621 | Tampere – Seinäjoki | Nurmo | K | | |
| Sysmäjärvi | | Snj | 669+601 | Viinijärvi – Siilinjärvi | Outokumpu | | K | K |
| Säkylä | | Säk | 315+928 | Kiukainen – Säkylä | Säkylä | | K | K |
| Säkänemi | | Sä | 586+873 | Säkänemi – Joensuu | Tohmajärvi | K | | |
| Sänkimäki | | Skm | 504+505 | Viinijärvi – Siilinjärvi | Nilsiä | | | |
| Särkisalmi | | Smi | 536+082 | Savonlinna – Parikkala | Parikkala | | | |
| Sääksjärvi | | Sj | 177+734 | Riihimäki – Tampere | Tampere | K | | |
| Taavetti | | Ta | 238+589 | Kouvola – Luumäki | Luumäki | | K | K |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|--------------------|-----------------|-------------|---------|--------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Tahkoluoto | | Tko | 350+750 | Pori – Mäntyluoto | Pori | | K | K |
| Taipale | | Te | 537+605 | Siilinjärvi – Iisalmi | Iisalmi | K | | |
| Taivaiainen | | Tv | 247+245 | Orivesi – Jyväskylä | Orivesi | K | | |
| Tammisaari | Ekenäs | Tms | 174+056 | Karjaa – Hanko | Tammisaari | | | |
| TAMPERE | Tammerfors | Tre | | Riihimäki – Tampere | | M | K | K |
| Tampere asema | | Tpe | 187+389 | | Tampere | | | |
| Tampere Järvensivu | | Jvs | 187+814 | | Tampere | | | |
| Tampere tavara | | Tpet | 184+100 | | Tampere | | | |
| Tampere Viinikka | | Vka | 185+400 | | Tampere | | | |
| Tapanila | Mosabacka | Tna | 12+610 | Helsinki – Riihimäki | Helsinki | | | |
| Tapavainola | | Tap | 270+405 | Luumäki – Parikkala | Lappeenranta | K | | |
| Tavastila | | Tsl | 228+854 | Kouvola – Kotka | Kotka | | | |
| Tervajoki | | Tk | 460+156 | Seinäjohti – Vaasa | Isokyrö | | | |
| Tervasuo | | | 645+040 | Joensuu – Ilomantsi | Joensuu | | | |
| Tervola | | Trv | 900+521 | Laurila – Kelloseikä | Tervola | K | | |
| Teuva | Östermark | Tuv | 497+474 | Seinäjohti – Kaskinen | Teuva | | K | |
| Tikkala | | Tkk | 592+461 | Säkänemi – Joensuu | Tohmajärvi | K | | |
| Tikkurila | Dickursby | Tkl | 15+861 | Helsinki – Riihimäki | Vantaa | K | K | K |
| Tohmajärvi | | Toh | 571+752 | Niirala-raja – Säkänemi | Tohmajärvi | M | | |
| Toijala | | Ti | 147+339 | Riihimäki – Tampere | Akaa | K | K | K |
| Toivala | | Toi | 479+162 | Pieksämäki – Siilinjärvi | Siilinjärvi | K | | |
| Tolsa | Tolls | Tol | 35+634 | Helsinki – Karjaa | Kirkkonummi | | | |
| Tommola | | Tom | 117+197 | Riihimäki – Lahti | Hollola | K | | |
| Torkkeli | | Trk | 240+154 | Orivesi – Jämsänkoski | Orivesi | K | | |
| Tornio | Torneå | Tor | 884+646 | Laurila – Tornio-raja | Tornio | K | K | K |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|------------------|-----------------|-------------|---------|------------------------------------|---------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Tornio-raja | Torneå gränsen | Trr | 887+236 | Laurila – Tornio-raja | Tornio | K | | |
| Tuomarila | Domsby | Trl | 19+022 | Helsinki – Karjaa | Espoo | | | |
| Tuomioja | | Tja | 698+504 | Ylivieska – Oulu | Siikajoki | K | | K |
| Turenki | | Tu | 93+771 | Riihimäki – Tampere | Janakkala | K | K | K |
| TURKU | Åbo | Tur | | Karjaa – Turku | Turku | M | | |
| Kupittaa | Kuppis | Kut | 196+372 | | Turku | | | |
| Turku asena | | Tku | 199+673 | | Turku | | K | K |
| Turku satama | Åbo hamn | Tus | 277+696 | | Turku | | K | |
| Turku tavara | | Tkut | 200+460 | | Turku | | K | K |
| Turku Viheräinen | | Vie | 209+305 | | Naantali | | K | |
| Tuupovaara | | Tpv | 668+672 | Joensuu – Ilomantsi | Joensuu | | | K |
| Tuuri | | Tuu | 366+962 | Haapamäki – Seinäjoki | Alavus | | | K |
| Törmä | | Tör | 878+075 | Laurila – Kelloseleä | Keminmaa | K | | |
| Törolä | | Trä | 264+972 | Luumäki – Parikkala | Lappeenranta | K | | |
| Töysä | | Tö | 356+397 | Haapamäki – Seinäjoki | Alavus | | | |
| Uimaharju | | Uim | 674+451 | Joensuu – Kontiomäki | Eno | K | K | K |
| Ulasoori | | Uso | 328+188 | Pori – Mäntyluoto | Pori | | | |
| Urijala | | Ur | 165+588 | Toijala – Turku | Urijala | K | | |
| Utajärvi | | Uti | 810+502 | Oulu – Kontiomäki | Utajärvi | K | | K |
| Utti | | Uti | 204+085 | Kouvola – Luumäki | Anjalankoski | | | |
| Uusikaupunki | Nystad | Ukp | 264+795 | Turku – Uusikaupunki – Hangonsaari | Uusikaupunki | M | K | |
| Uusikyliä | | Ukä | 150+722 | Lahti – Kouvola | Nastola | M | | K |
| Vaajakoski | | Vko | 384+866 | Jyväskylä – Pieksämäki | Jyväskylä mik | K | | |
| Vaala | | Vaa | 844+671 | Oulu – Kontiomäki | Vaala | K | | K |
| Vaarala | | Vra | 981+481 | Laurila – Kelloseleä | Rovaniemi | | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------------|-----------------|-------------|---------|---------------------------|----------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Vaasa | Vasa | Vs | 492+588 | Seinäjoki – Vaasa | Vaasa | M | K | K |
| Vahojärvi | | Vjr | 244+926 | Tampere – Seinäjoki | Parkano | K | | |
| VAINIKKALA | | Vai | | Luumäki – Vainikkala-raja | | M | | |
| Vainikkala asema | | Vna | 282+784 | | Lappeenranta | | K | K |
| Vainikkala tavara | | Vnat | 281+700 | | Lappeenranta | | K | K |
| Vainikkala-raja | | Vnar | 284+862 | Luumäki – Vainikkala-raja | Lappeenranta | K | | |
| Valimo | Gjuteriet | Vmo | 7+480 | Helsinki – Karjaa | Helsinki | | | |
| Valkeakoski | | Vi | 164+952 | Toijala – Valkeakoski | Valkeakoski | | K | K |
| Valkeasuo | | Vso | 583+976 | Niirala-raja – Säkänemi | Tohmajärvi | | | |
| Valtimo | | Vlm | 808+636 | Joensuu – Kontiomäki | Valtimo | | | |
| Vammala | | Vma | 245+885 | Lielähti – Kokemäki | Vammala | K | K | K |
| Vanattara | | Vtr | 172+340 | Riihimäki – Tampere | Lempäälä | K | | |
| Vantaankoski | Vandaforsen | Vks | 14+907 | Huopalahti – Vantaankoski | Vantaa | K | | |
| Varkaus | | Var | 424+685 | Huutokoski – Viinijärvi | Varkaus | K | K | K |
| Vartius | | Vus | 753+755 | Kontiomäki – Vartius-raja | Kuhmo | M | | K |
| Vartius-Raja | | Vur | 755+856 | Kontiomäki – Vartius-raja | Kuhmo | K | | |
| Vasikkahaka | | Vkh | 31+175 | Helsinki – Karjaa | Kirkkonummi | K | | |
| Vaskiluoto | Vasklot | Vsk | 496+463 | Seinäjoki – Vaasa | Vaasa | | K | |
| Venetmäki | | Vki | 433+164 | Jyväskylän – Pieksämäki | Pieksämäki | K | | |
| Vesanka | | Vn | 364+469 | Haapamäki–Jyväskylän | Jyväskylän mlk | | | |
| Vieikki | | Vk | 753+979 | Joensuu – Kontiomäki | Liekka | | | |
| Vierumäki | | Vrm | 153+801 | Lahti – Heinola | Heinola | M | | |
| Vihanti | | Vti | 684+573 | Ylivieska – Oulu | Vihanti | K | K | K |
| Vihtari | | Vih | 489+889 | Huutokoski – Viinijärvi | Heinävesi | K | | |
| Viala | | Via | 154+288 | Riihimäki – Tampere | Akaa | | K | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Liikenteen-ohjaus | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-----------------|-----------------|-------------|----------|---------------------------|--------------|-------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Viinijärvi | | Vnj | 656+569 | Joensuu – Viinijärvi | Liperi | K | | K |
| Vika | | Vlk | 1010+478 | Laurila – Kelloseleä | Rovaniemi | | | |
| Vilppula | | Vlp | 274+760 | Orivesi – Haapamäki | Vilppula | K | | K |
| Vinnilä | | Vln | 131+243 | Riihimäki – Tampere | Kalvola | K | | |
| Virtakallio | | Vrk | 89+900 | Kerava – Hakosilta | Orimattila | K | | |
| Voltti | | Vt | 479+402 | Seinäjoki – Kokkola | Alahärmä | K | | |
| Vuohijärvi | | Vhj | 221+308 | Kouvola – Pieksämäki | Valkeala | K | | |
| Vuojoki | | Vjo | 318+501 | Kokemäki – Rauma | Eurajoki | K | | |
| Vuokatti | | Vkt | 868+838 | Joensuu – Kontiomäki | Sotkamo | | K | K |
| Vuonilahti | | Vsl | 705+240 | Joensuu – Kontiomäki | Liekka | M | | |
| Vuonos | | Vns | 588+808 | Sysmäjärvi – Vuonos | Outokumpu | | K | |
| (Vuorten-Vuori) | | | 576+687 | Jyväskylä – Haapajärvi | Haapajärvi | | K | |
| Ykspihlaja | Yxpila | Yks | 555+428 | Kokkola – Ykspihlaja | Kokkola | | K | |
| Ylistaro | | Yst | 439+558 | Seinäjoki – Vaasa | Ylistaro | | | |
| Ylitornio | | Ytr | 946+139 | Tornio – Kolari | Ylitornio | | | |
| Ylivalli | | Ylv | 302+016 | Tampere – Seinäjoki | Jalasjärvi | K | K | |
| Ylivieska | | Yv | 630+343 | Kokkola – Ylivieska | Ylivieska | M | K | K |
| Yläkoski | | Ylk | 416+984 | Suonenjoki – Iisvesi | Suonenjoki | | K | |
| Ylämylly | | Yly | 639+019 | Joensuu – Viinijärvi | Liperi | | | |
| Ylöjärvi | | Ylö | 200+753 | Tampere – Seinäjoki | Ylöjärvi | K | | |
| Ypykkävaara | | Ypy | 729+780 | Kontiomäki – Vartius-raja | Kuhmo | | | |
| Äetsä | | Äs | 258+280 | Lielähti – Kokemäki | Äetsä | K | K | K |
| Äntäri | Etseri | Änt | 346+067 | Haapamäki – Seinäjoki | Äntäri | K | | |
| Ämmänsaari | | Äm | 750+448 | Kontiomäki – Ämmänsaari | Suomussalmi | M | | K |
| Äänekoski | | Äki | 424+515 | Jyväskylä – Haapajärvi | Äänekoski | K | K | K |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laiturin korkeus | Laitureiden lukumäärä | Mitoitettava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|--------------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|----------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perrong-längd | Längsta perrong-längd | Perrong-höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido-perrong | End loading platform | Lastning på samma plan | Crane [t] | Fuel | Passenger traffic | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | | Loading site | | | | Freight traffic |
| Ahvenus | | | | 0 | 769 | — | — | — | — | — | — | — | — |
| Airaksela | | | | 0 | 876 | — | — | — | — | — | — | — | K |
| Aittaluoto | | | | 0 | 485 | — | — | — | Y | — | — | — | K |
| Ajos | | | | 0 | 806 | 25 A | Y | — | Y | — | — | — | K |
| Alapitkä | | | | 0 | 672 | 25 A | — | — | K | — | — | — | K |
| Alavus | 80 | 203 | 265 | 2 | 781 | 25 A | — | — | K | — | — | K | K |
| Alholma | | | | 0 | 777 | — | — | — | K, Y | — | — | — | K |
| Alvajärvi | | | | 0 | 608 | — | — | — | K | — | — | — | K |
| Arola | | | | 0 | 793 | 25A | 24 | — | K | — | — | — | K |
| Dragsvik | | 70 | 550 | 1 | 966 | — | — | — | — | — | — | — | — |
| Dynamittivaihe | | | | 0 | 151 | — | — | — | K | — | — | — | K |
| Elijärvi | | | | 0 | 205 | — | — | — | — | — | — | — | K |
| Eläinpuisto-Zoo | | 99 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Eno | | 80 | 550 | 1 | 646 | 16 A | — | — | K | — | — | K | K |
| Ervelä | | | | 0 | 632 | — | — | — | — | — | — | — | — |
| Eskola | | (120) | (265) | (1) | 818 | — | 11 | — | K | — | — | — | K |
| Espoo | 240 | 322 | 550 | 4 | 281 | — | — | — | — | — | — | K | — |
| (Esso) | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| (Finnish Chemicals) | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Haapajärvi | | 160 | 265 | 1 | 767 | 25 A | 12 | — | K, Y | — | — | K | K |
| Haapakoski | | | | 0 | 789 | — | — | — | K | — | — | — | — |
| (Haapamäen kyläliikenne) | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Haapamäki | 188 | 325 | 265 | 4 | 711 | 63 A | 60 | — | K | — | — | K | K |
| Haarajoki | 220 | 220 | 550 | 2 | 263 | — | — | — | — | — | — | — | — |
| Hakosilta | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Haksi | | 20 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|----------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|---------------------|
| Namn | Kortaste perrong- längd | Längsta perrong- längd | Perrong- höjd | Antal spår med perrong | Dimensionerande spårängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Hamina | | | | 0 | 881 | 25 A | 15 | K | K | Y | K | — | K |
| Hammaslahti | | 146 | 265 | 1 | 710 | — | 13 | — | K | — | — | K | K |
| Hanala | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Hangonsaari | | | | 0 | 442 | — | — | — | — | — | — | — | K |
| Hanhikoski | | | | 0 | 160 | — | 20 | — | K | — | — | — | — |
| Hankasalmi | 233 | 289 | 265 | 2 | 774 | 25 A | 20 | K | K, Y | — | — | K | K |
| Hanko | 108 | 108 | 265 | 2 | 772 | 63 A | 167 | K | K | Y | — | K | K |
| Hanko-Pohjoinen | | 68 | 550 | 1 | 0 | — | — | — | — | — | — | K | — |
| Harjavalta | 250 | 250 | 550 | 2 | 789 | 25 A | — | — | K | — | — | K | K |
| Harju | | | | 0 | 820 | — | — | — | K | — | — | — | — |
| Harjala | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Haukipudas | | | | 0 | 865 | — | 12 | — | K | — | — | — | — |
| Haukivuori | 199 | 200 | 265 | 2 | 927 | — | 5 | — | K | — | — | K | K |
| Hausjärvi | | | | 0 | 687 | — | — | — | — | Y | — | — | — |
| Haviseva | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Heikkilä | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Heinola | | 106 | 265 | 1 | 608 | 25 A | 45 | — | K | — | — | — | K |
| Heinoo | | | | 0 | 769 | — | — | — | — | — | — | — | — |
| Heinävaara | | | | 0 | 690 | — | — | — | K | — | — | — | K |
| Heinävesi | 100 | 206 | 265 | 2 | 613 | — | 9 | — | K | — | — | K | K |
| HELSINKI | | | | | | | | | | | | | |
| Helsinki asema | 265 | 477 | 550 | 19 | 493 | 63 A | — | K | — | — | — | K | — |
| Helsinki Kivihaka | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Helsinki Länsisatama | | | | 0 | 600 | — | — | — | K | Y | — | — | K |
| Helsinki Sörnäinen | | | | 0 | 0 | — | — | — | K | Y | — | — | — |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavarailikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Pääty- laiturin | Kuormaus- kenttä | Nosturi | Poltto- aine | Henkilö- liikennettä | Tavara- liikennettä |
|---------------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|----------------------|------------------------|-----------|--------------|----------------------|---------------------|
| Namn | Kortaste perrong- längd | Längsta perrong- längd | Perrong- höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | End loading platform | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Ilmala asema | 275 | 275 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Ilmala ratapiha | | | | 0 | 0 | 63 A, 1500 V | — | — | — | — | K | — | — |
| Käpylä | 244 | 334 | 550 | 2 | — | — | — | — | — | — | — | K | — |
| Oulunkylä | 270 | 274 | 550 | 2 | — | — | — | — | — | — | — | K | — |
| Pasila alapiha | | | | 0 | 933 | 25 A | — | — | — | — | — | — | K |
| Pasila asema | 322 | 425 | 550 | 10 | — | — | — | — | — | — | — | K | — |
| Pasila tavara | | | | 0 | 742 | — | 230, Y | K | K | 50 | — | — | K |
| Herrala | 110 | 110 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Hiekkaharju | 257 | 526 | 550 | 3 | 0 | — | — | — | — | — | — | K | — |
| Hiirola | | | | 0 | 784 | — | — | — | — | — | — | — | — |
| Hikiä | 120 | 120 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Hillosensalmi | | (178) | (550) | (1) | 833 | — | — | — | — | — | — | — | — |
| Hinthaara | 55 | 65 | 265 | 2 | 108 | — | — | — | — | — | — | K | — |
| Hirvineva | | | | 0 | 862 | 25 A | 12 | — | K | — | — | — | — |
| Humpplila | 249 | 430 | 550 | 2 | 800 | 25 A | 29 | — | Y | — | — | K | K |
| Huopalahti | 270 | 270 | 550 | 4 | 0 | — | — | — | — | — | — | K | — |
| Huutokoski | | | | 0 | 672 | 25 A | — | — | — | — | — | — | — |
| Hyrynsalmi | | (100) | (265) | (1) | 768 | 25 A | 12 | — | K | — | — | — | K |
| Hyvinkää | 315 | 332 | 550 | 3 | 770 | 25 A | 20 | — | K | — | — | K | K |
| Hämeenlinna | 257 | 450 | 550 | 3 | 1033 | 25 A | 34 | K | K | — | — | K | K |
| Härmä | (51) | 188 | 265 | 1 (1) | 855 | — | 18 | — | K | — | — | K | K |
| Höjljääkä | | 92 | 265 | 1 | 618 | 25 A | — | — | K | — | — | K | K |
| li | | 92 | 265 | 1 | 724 | — | — | — | K | — | — | K | — |
| (Iisalmen sahat) | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| (Iisalmen teollisuuskylä) | | | | 0 | 464 | — | Y | — | — | — | — | — | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laiturikorkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|------------------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårängd (godstrafik) | Tillgång till elström | Sidoperrong | Perrong i ändan av banan | Lastning på samma plan | Liftkran | Bränsle | Persontrafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| (lisälmen teollisuusraiteet) | | | | | | | | | | | | | |
| Isalmi | 162 | 396 | 265 | 0 | 0 | — | — | — | — | — | — | — | — |
| Isvesi | | | | 3 | 763 | 63 A, 1500 V | 83 | Y | K, Y | — | K | K | K |
| Isittala | 170 | 170 | 550 | 0 | 310 | — | — | — | K | — | — | — | — |
| Ilmajoki | | | | 2 | 0 | — | — | — | — | — | — | K | — |
| Ilomantsi | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| IMATRA | | | | 0 | 787 | 25 A | — | — | K | — | — | — | K |
| Imatra asema | | 450 | 265 | 1 | 0 | | — | — | — | — | — | K | — |
| Imatra tavara | | | | 0 | 935 | 63 A, 1500 V | — | — | — | — | K | — | K |
| Imatrankoski | | | | 0 | 1269 | — | 14 | — | — | — | — | — | K |
| Pelkola | | | | 0 | 1410 | — | — | — | — | — | — | — | K |
| Imatrankoski-raja | | | | 0 | 0 | — | — | — | — | — | — | — | K |
| (Imatran terästehdas) | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Immola | | | | 0 | 513 | — | — | — | K | — | — | — | K |
| Inha | | (99) | (265) | (1) | 249 | — | 42 | — | K | — | — | — | K |
| Inkeroinen | 120 | 172 | 265 | 3 | 831 | — | 21 | — | K | — | — | K | K |
| Inkoo | 100 | 170 | 550 | 2 | 237 | — | — | — | K | — | — | K | — |
| Isokangas | | | | 0 | 0 | — | — | — | K | — | — | — | — |
| Isokylä | | | | 0 | 623 | — | Y | — | K | — | — | — | K |
| Isokyrö | 110 | 150 | 550/265 | 2 | 550 | — | — | — | — | — | — | K | K |
| Jalasjärvi | | 51 | 550 | 1 | 794 | — | 27 | — | K | — | — | K | — |
| Jepua | | (133) | (265) | (1) | 797 | 25 A | 15 | — | K | — | — | — | — |
| JOENSUU | | | | | | | | | | | | | |
| Joensuu asema | 226 | 377 | 265 | 3 | 591 | 63 A, 1500 V | 44 | K | — | — | K | K | K |
| Joensuu Peltola | | | | 0 | 696 | — | — | — | K | — | — | — | K |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laiturikorkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|--------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perrong-längd | Längsta perrong-längd | Perrong-höjd | Antal spår med perrong | Dimensionerande spår-längd (godstrafik) | Tillgång till elström | Sido-perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Joensuu Sulkulahti | | | | 0 | 732 | — | — | — | — | — | — | — | K |
| Jokela | 320 | 338 | 550 | 3 | 851 | — | — | — | K | — | — | K | — |
| Jokikylä | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Joroinen | | (80) | (265) | (1) | 467 | — | 13 | K | K | — | — | — | K |
| Jonas | 97 | 124 | 265 | 2 | 0 | — | — | — | — | — | — | K | — |
| Joutjärvi | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Joutseno | 460 | 460 | 550 | 2 | 845 | — | — | — | — | — | — | K | — |
| Joutsijärvi | | | | 0 | 611 | 25 A | — | — | Y | — | — | — | K |
| Juankoski | | | | 0 | 610 | 25 A | Y | — | K, Y | — | — | — | K |
| Jukajärvi | | | | 0 | 285 | — | — | — | K | — | — | — | — |
| Jutla | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Juupajoki | 80 | | 550 | 1 | 0 | — | — | — | — | — | — | K | — |
| Juurikorpi | | | | 0 | 825 | — | — | — | — | — | — | — | — |
| Jyränkö | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Jyväskylä | 57 | 449 | 550 | 4 | 842 | 63 A, 1500 V | 88 | K | K | 30 | K | K | K |
| Jämsä | 194 | 313 | 265 | 2 | 801 | 25 A | 12 | K | K, Y | — | — | K | K |
| Jämsänkoski | | | | 0 | 638 | 25 A | — | — | K | — | — | — | K |
| Järvelä | 122 | 122 | 550 | 2 | 637 | — | 12 | — | K | — | — | K | K |
| Järvenpää | 345 | 393 | 550 | 3 | 0 | — | 29 | K | — | — | — | K | K |
| Kaipainen | | | | 0 | 804 | — | — | — | K | — | — | — | K |
| Kaipola | | | | 0 | 538 | — | — | — | K | — | — | — | K |
| Kairokoski | | | | 0 | 552 | — | 15 | — | K | — | — | — | K |
| Kaijärvi | | | | 0 | 756 | — | — | — | K | — | — | — | — |
| Kajaani | 350 | 350 | 265 | 2 | 777 | 63 A, 1500 V | 122 | K | K | — | — | K | K |
| Kaleton | | | | 0 | 374 | — | K | — | K | — | — | — | K |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Poltto- aine | Henkilö- liikennettä | Tavara- liikennettä |
|---------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|--------------|----------------------|---------------------|
| Namn | Kortaste perrong- längd | Längsta perrong- längd | Perrong- höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Kalkku | | | | 0 | 0 | — | Y | — | Y | — | — | — | K |
| Kalliovarasto | | | | 0 | 0 | — | — | — | Y | — | — | — | — |
| Kallislaitti | | (86) | (265) | (1) | 575 | — | 65 | — | K | — | — | — | K |
| Kalvitsa | | | | 0 | 897 | — | — | — | K | — | — | — | K |
| Kängas | | (47) | (265) | (1) | 811 | 25 A | — | — | K | — | — | — | — |
| Kannelmäki | 226 | 226 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Kannonkoski | | | | 0 | 645 | — | 13 | — | K | — | — | — | K |
| Kannus | 339 | 420 | 265 | 2 | 849 | 25 A | 19 | — | K | — | — | K | — |
| Karhejärvi | | | | 0 | 810 | 25 A | 4 | — | K | — | — | — | — |
| Karhukangas | | | | 0 | 879 | — | — | — | — | — | — | — | — |
| Karjaa | 248 | 352 | 550 | 4 | 785 | 63 A | 115 | K | K | — | K | K | K |
| Karkku | | 143 | 265 | 1 | 885 | — | — | — | K | — | — | K | — |
| Karvainen | | | | 0 | 770 | — | — | — | — | — | — | — | — |
| Kaskinen | | | | 0 | 1222 | — | 70 | — | Y | — | — | — | K |
| Kauhajoki | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Kauhava | | | | 1 | 871 | 25 A | — | — | K | — | — | K | K |
| Kauklahti | 270 | 270 | 550 | 3 | 466 | — | — | — | K | — | — | K | — |
| Kaulinranta | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Kauniainen | 194 | 204 | 265 | 3 | 299 | — | — | — | — | — | — | K | K |
| Kauppiänmäki | | | | 0 | 666 | — | — | — | K | — | — | — | K |
| Kausala | 84 | 160 | 265 | 3 | 678 | — | — | — | K | — | — | K | — |
| Kauttua | | (42) | (265) | (1) | 508 | — | 14 | — | K | — | — | — | K |
| Keitelepoijia | | | | 0 | 676 | — | 8 | — | K | — | — | — | K |
| Kekomäki | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Keljo | | | | 0 | 0 | — | — | — | — | — | — | — | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaiturin suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|--------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|------------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Keljonlahti | | | | 0 | 506 | — | — | — | — | — | — | — | — |
| Kelkkämäki | | | | 0 | 0 | — | Y | — | Y | — | — | — | — |
| Kelloselkä | | | | 0 | 635 | — | — | — | Y | — | — | — | K |
| Kemi | 450 | 450 | 550/265 | 3 | 1018 | 63 A | 147 | Y | K | — | K | K | K |
| Kemijärvi | | 235 | 265 | 1 | 656 | 63 A | 94 | — | K, Y | — | — | K | K |
| Kemira | | (119) | (265) | 0 | 453 | — | — | — | Y | — | — | — | K |
| Kempele | | | | (1) | 787 | — | 9 | — | K | — | — | — | — |
| Kera | 216 | 224 | 265 | 2 | 0 | — | — | — | — | — | — | K | — |
| KERAVA | | | | | | | | | | | | | |
| Kerava asema | 270 | 350 | 550 | 4 | 537 | 25 A | — | — | — | — | — | K | — |
| Kytömaa | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Kerimäki | | 108 | 265 | 1 | 455 | — | — | — | K | — | — | K | K |
| Kesälahti | 63 | 322 | 265 | 1 | 695 | 25 A | — | — | K | — | — | K | K |
| Keuruu | | 111 | 550 | 1 | 702 | — | — | — | K | — | — | K | K |
| Kihniö | | | | 0 | 577 | — | 10 | — | K | — | — | — | K |
| Kiiala | | 49 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Kilo | 270 | 270 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Kilpua | | (70) | (265) | (1) | 784 | 25 A | — | — | — | — | — | — | — |
| Kinahmi | | | | 0 | 312 | — | — | — | — | — | — | — | — |
| Kinni | | | | 0 | 819 | — | — | — | — | — | — | — | — |
| (Kirjola) | | | | 0 | | — | — | — | Y | — | — | — | — |
| Kirkkonummi | 316 | 322 | 660 | 3 | 627 | — | — | — | K | — | — | K | — |
| Kirkniemi | | | | 0 | 620 | 25 A | — | — | K | — | — | — | K |
| Kitee | | 355 | 265 | 1 | 686 | 25 A | 17 | — | Y | — | — | K | K |
| Kiukainen | | | | 0 | 798 | — | 14 | — | K | — | — | — | — |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Pääty- laiturin | Kuormaus- kenttä | Nosturi | Poltto- aine | Henkilö- liikennettä | Tavara- liikennettä |
|-------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|----------|--------------|----------------------|---------------------|
| Namn | Kortaste perrong- längd | Längsta perrong- längd | Perrong- höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Liftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic |
| Kiuruvesi | | 126 | 265 | 1 | 592 | 25 A | Y | — | K, Y | — | — | K | K |
| Kivesjärvi | | (53) | (265) | (1) | 1143 | — | — | — | — | — | — | — | — |
| Kohtavaara | | 55 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Koivu | | (40) | (265) | (1) | 637 | — | 29 | — | K | — | — | — | K |
| Koivuhovi | 278 | 278 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Koivukylä | 270 | 270 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Kokemäki | 249 | 249 | 550 | 3 | 795 | — | 29 | — | K | — | — | K | K |
| Kokkola | 308 | 482 | 265 | 2 | 871 | 63 A, 1500 V | 8 | Y | K | — | K | K | K |
| Kolari | (370) | 675 | 550/265 | 1 | 1204 | 63 A | 21 | K | K | — | — | K | K |
| Kolho | | (127) | (265) | (1) | 651 | — | — | — | K | — | — | — | K |
| Kolppi | | | | 0 | 801 | — | — | — | — | — | — | — | — |
| Kommila | | | | 0 | 788 | 25 A | — | — | Y | — | — | — | K |
| Komu | | | | 0 | 575 | — | — | — | Y | — | — | — | — |
| Kontiolahti | | (95) | (265) | (1) | 634 | — | — | K | K | — | — | K | K |
| Kontiomäki | 226 | 544 | 265 | 5 | 823 | 63 A | — | K | K | — | K | K | K |
| Kopnäs | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Koria | 61 | 61 | 265 | 2 | 693 | — | 39 | — | K | — | — | K | — |
| (Korjala) | | | | 0 | 0 | — | — | — | Y | — | — | — | — |
| Korkeakoski | | (72) | (265) | (1) | 768 | — | 11 | K | K | — | — | — | K |
| Korso | 270 | 270 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Korvensuo | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Koskenkorva | | | | 0 | 251 | — | — | — | — | — | — | — | K |
| Kotavaara | | | | 0 | 0 | — | — | — | K | — | — | — | — |
| KOTKA | | | | | 0 | — | — | — | — | — | — | — | — |
| Kotka asema | | 193 | 265 | 1 | 279 | 63 A | — | — | — | — | — | K | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|-------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|------------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Kotka Hovinsaari | | | | 0 | 896 | 25 A | — | — | — | — | — | — | K |
| Kotka Mussalo | | | | 0 | 1055 | — | — | — | — | Y | — | — | K |
| Kotka satama | 110 | | 265 | 1 | 0 | — | — | — | — | Y | — | K | K |
| Kotka tavara | | | | 0 | 581 | — | Y | — | — | — | K | — | K |
| Paimenportti | 53 | | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| KOUVOLA | | | | | | | | | | | | | |
| Kouvola asema | 300 | 400 | 265 | 7 | 695 | 63 A | — | — | K | — | K | K | — |
| Kouvola lajittelu | | | | 0 | 906 | — | 175 | K | — | — | — | — | K |
| Kouvola Oikoraide | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Kouvola tavara | | | | 0 | 945 | — | — | — | — | — | — | — | K |
| Kuusankoski | | | | 0 | 860 | — | — | — | — | — | — | — | K |
| Kovjoki | (102) | | (265) | (1) | 887 | — | — | — | — | — | — | — | — |
| Kruunupyö | (70) | | (265) | (1) | 806 | 25 A | 43 | — | K | — | — | — | K |
| Kuivasjärvi | | | | 0 | 812 | — | — | — | K | — | — | — | — |
| KUOPIO | | | | | | | | | | | | | |
| Kuopio asema | 180 | 387 | 265 | 3 | 389 | 63 A | — | K | — | — | — | K | — |
| Kuopio tavara | | | | 0 | 797 | 63 A | Y | — | Y | — | K | — | K |
| Kurikka | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Kurkimäki | | | | 0 | 811 | — | — | — | K | — | — | — | K |
| Kursu | | | | 0 | 653 | — | — | — | K | — | — | — | — |
| Kuurila | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Kuusanlampi | | | | 0 | 0 | — | — | — | K | — | — | — | — |
| Kuusivaara | 28 | | 265 | 1 | 0 | — | — | — | K | — | — | K | — |
| Kylälahti | 57 | | 265 | 1 | 0 | — | — | — | K | — | — | K | — |
| Kymi | 32 | 66 | 265 | 2 | 790 | — | — | — | K | — | — | K | — |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|--------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|---------------------|
| Namn | Kortaste perrong- längd | Längsta perrong- längd | Perrong- höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Liftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Kyminlinna | | 55 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Kyrö | | | | 0 | 764 | — | — | — | K | — | — | — | K |
| Kyrölä | 270 | 270 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Kälviä | | | | 0 | 1075 | 25 A | 17 | — | K | — | — | — | — |
| Köykkäri | | | | 0 | 877 | — | — | — | — | — | — | — | — |
| Laaja | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Lahdenperä | | | | 0 | 819 | 25 A | — | — | — | — | — | — | — |
| Lahnaslampi | | | | 0 | 605 | — | Y | — | — | — | — | — | K |
| Lahti | 270 | 450 | 550 | 4 | 742 | 63 A | Y | Y | K | — | K | K | K |
| Laihia | | 201 | 265 | 1 | 508 | 25 A | — | — | K | — | — | K | K |
| Lakiala | | | | 0 | 750 | — | 11 | — | K | — | — | — | — |
| Lamminkoski | | | | 0 | 764 | — | — | — | — | — | — | — | — |
| Lapinjärvi | | | | 0 | 427 | — | 12 | — | K | — | — | — | K |
| Lapinlahti | 301 | 355 | 265 | 2 | 766 | 25 A | — | — | Y | — | — | K | K |
| Lapinneva | | | | 0 | 446 | — | — | — | K | — | — | — | — |
| Lappeenranta | 430 | 450 | 550 | 3 | 773 | 25 A | 14, Y | — | K | — | K | K | K |
| Lappila | 60 | 60 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Lappohja | | 70 | 550 | 1 | 773 | — | — | — | — | — | — | K | K |
| Lapua | | 438 | 265 | 1 | 798 | — | — | — | K | — | — | K | K |
| Larvakyttö | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Laukaa | | 90 | 265 | 1 | 250 | — | — | — | K | — | — | — | — |
| Laurila | | | | 0 | 641 | 25 A | — | — | K | — | — | — | — |
| Lauritsala | | | | 0 | 680 | — | — | — | K | — | — | — | K |
| Lautiosaari | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Leikola | | | | 0 | 836 | — | — | — | — | — | — | — | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoitettava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|--------------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|------------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Lempäälä | 170 | 170 | 550 | 2 | 811 | — | — | — | — | — | — | K | — |
| Leppäkoski | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Leppävaara | 266 | 292 | 550 | 4 | 0 | — | — | — | — | — | — | K | — |
| Leteensuo | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Liekka | | 151 | 265 | 1 | 750 | — | 25 | K | K | — | K | K | K |
| (Liekсан teollisuuskylä) | | | | 0 | 690 | — | — | — | — | — | — | — | — |
| Lielähti | | | | 0 | 759 | — | 8 | — | K | — | — | — | K |
| Lievestuore | | 259 | 265 | 1 | 909 | 25 A | 23 | — | K | — | — | K | K |
| Liminka | | (147) | (265) | (1) | 775 | 25 A | 23 | — | K | — | — | — | — |
| Lohiluoma | | | | 0 | 243 | — | — | — | K | — | — | — | — |
| Lohja | | | | 0 | 493 | 25 A | 86 | — | K | — | — | — | K |
| Lohjanjärvi | | | | 0 | 422 | — | — | — | — | — | — | — | K |
| (Lohja Oy) | | | | 0 | 0 | — | — | — | Y | — | — | — | — |
| Loimaa | 252 | 450 | 550 | 3 | 817 | — | — | — | K | — | — | K | K |
| Louhela | 238 | 238 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Loukolampi | | | | 0 | 917 | — | — | — | — | — | — | — | — |
| Loviisan satama | | | | 0 | 721 | 25 A | Y | — | K | Y | — | — | K |
| Luikonlahti | | | | 0 | 920 | 25 A | — | — | Y | — | — | — | K |
| Luoma | 216 | 216 | 265 | 2 | 0 | — | — | — | — | — | — | K | — |
| Lustikulla | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Lusto | | 124 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Luumäki | | | | 0 | 780 | — | 13 | — | K | — | — | — | K |
| Lähdemäki | | | | 0 | 1028 | — | — | — | — | — | — | — | — |
| Länkipohja | | | | 0 | 834 | — | — | — | — | — | — | — | — |
| Maanselkä | | | | 0 | 647 | — | — | — | K | — | — | — | — |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaiturin suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|-----------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|---------------------|
| Namn | Kortaste perrong-längd | Längsta perrong-längd | Perrong-höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido-perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Maaria | | | | 0 | 776 | - | - | - | - | - | - | - | - |
| Madesjärvi | | | | 0 | 809 | 25 A | 7 | - | K | - | - | - | K |
| Majajärvi | | | | 0 | 740 | - | - | - | - | - | - | - | - |
| Malmi | 300 | 348 | 550 | 2 | 0 | - | - | - | - | - | - | K | - |
| Malminkartano | 284 | 284 | 550 | 2 | 0 | - | - | - | - | - | - | K | - |
| Mankki | 126 | 136 | 265 | 2 | 0 | - | - | - | - | - | - | K | - |
| Markkala | | | | 0 | 776 | - | - | - | - | - | - | - | - |
| Martinlaakso | 236 | 236 | 550 | 2 | 0 | - | - | - | - | - | - | K | - |
| Masala | 216 | 235 | 550 | 2 | 0 | - | - | - | - | - | - | K | - |
| Matkaneva | | | | 0 | 878 | - | - | - | - | - | - | - | - |
| Mattila | | | | 0 | 0 | - | - | - | - | - | - | - | - |
| Meltola | | | | 0 | 287 | - | - | - | - | - | - | - | - |
| (Metro) | | | | 0 | 0 | - | - | - | Y | - | - | - | - |
| Metsäkansa | | | | 0 | 300 | - | 9 | - | - | - | - | - | K |
| Mikkeli | 350 | 452 | 550 | 3 | 709 | 25 A | 44, Y | - | Y | - | - | K | K |
| Misi | | 83 | 265 | 1 | 771 | 63 A | 51 | K | K | - | - | K | K |
| Mommila | 60 | 60 | 550 | 2 | 0 | - | - | - | - | - | - | K | - |
| Muhos | 151 | 212 | 265 | 2 | 1051 | 25 A | 25 | - | K | - | - | K | - |
| Mukkula | | | | 0 | 472 | - | - | - | K | - | - | - | K |
| Murtomäki | | | | 0 | 609 | - | - | - | K | - | - | - | - |
| Mustio | | | | 0 | 808 | - | - | - | K | - | - | - | K |
| Mustola | | | | 0 | 0 | - | Y | - | Y | - | - | - | - |
| Mustolan satama | | | | 0 | 500 | - | Y | - | Y | - | - | - | K |
| Muukko | | | | 0 | 817 | - | - | - | - | - | - | - | - |
| Muurame | | | | 0 | 871 | - | - | - | K | - | - | - | - |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|--------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|----------------------|------------------------|----------|------------|--------------------|------------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | End loading platform | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic |
| Murola | 316 | 317 | 265 | 2 | 760 | — | — | — | K | — | — | K | — |
| Myllykangas | | | | 0 | 867 | — | — | — | — | — | — | — | — |
| Myllykoski | 110 | 110 | 265 | 2 | 753 | — | — | — | — | — | — | K | — |
| Myllymäki | 185 | 219 | 265 | 2 | 859 | — | — | — | K | — | — | K | K |
| Myllyoja | | | | 0 | 415 | — | — | — | Y | — | — | — | K |
| Mynttilä | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Mynämäki | | (124) | (265) | (1) | 568 | — | — | — | K | — | — | — | — |
| Myrskylä | | | | 0 | 625 | — | — | — | K | — | — | — | — |
| Myrymäki | 232 | 232 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Mäkkylä | 270 | 288 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Mäntsälä | 220 | 220 | 550 | 2 | 1032 | — | — | — | — | — | — | — | — |
| Mänttä | | | | 0 | 680 | — | — | — | K | — | — | — | K |
| Mäntyharju | 457 | 457 | 550 | 2 | 1023 | — | 159 | — | K | — | — | K | K |
| Mäntyluoto | | | | 0 | 840 | — | Y | — | Y | — | — | — | K |
| Naantali | | | | 0 | 485 | — | 20 | — | Y | Y | — | — | K |
| Naarajärvi | | | | 0 | 839 | — | — | — | K | — | — | — | K |
| Nakkila | | | | 0 | 766 | — | — | — | — | — | — | — | — |
| Nastola | 120 | 120 | 550 | 2 | 0 | — | — | — | — | — | — | — | — |
| Niemenpää | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Niinimaa | | (85) | (265) | (1) | 704 | — | — | — | K | — | — | — | — |
| Niinisalo | | | | 0 | 547 | — | 21 | Y | Y | — | — | — | K |
| Niirala | | (42) | (265) | (1) | 991 | 25 A | Y | — | K | — | — | — | K |
| Niirala-raja | | | | 0 | 0 | — | — | — | — | — | — | — | K |
| Niittylahti | | | | 0 | 725 | — | 10 | — | K | — | — | — | — |
| Nikkilä | | 30 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Pääty- laiturin | Kuormaus- kenttä | Nosturi | Poltto- aine | Henkilö- liikennettä | Tavara- liikennettä |
|---------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|----------|--------------|----------------------|---------------------|
| Namn | Kortaste perrong- längd | Längsta perrong- längd | Perrong- höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Liftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane | Fuel | Passenger traffic | Freight traffic |
| Nivala | | 97 | 265 | 1 | 725 | 25 A | — | — | K | — | — | K | K |
| Nokia | | 282 | 265 | 1 | 899 | — | — | — | — | — | — | K | K |
| Nummela | | | | 0 | 446 | — | — | — | K | — | — | — | K |
| Nuppulinna | 210 | 240 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Nurmes | 73 | 205 | 265 | 2 | 908 | 63 A | 53 | K | K | — | — | K | K |
| Närpiö | | | | 0 | 122 | — | — | — | K | — | — | — | — |
| Ohermäki | | | | 0 | 372 | — | — | — | — | — | — | — | — |
| Oitti | 102 | 102 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Olli | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Onttola | | | | 0 | 645 | — | — | — | — | — | — | — | K |
| Orimattila | | | | 0 | 702 | — | 12 | — | K | — | — | — | — |
| Orivesi | 263 | 304 | 265 | 3 | 796 | 25 A | 46 | — | K | — | K | K | K |
| Otalampi | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Otanmäki | | | | 0 | 449 | — | — | — | Y | — | — | — | K |
| Otava | | (152) | (265) | (1) | 737 | — | — | — | K | — | — | — | K |
| Otavan satama | | | | 0 | 582 | — | — | — | — | — | — | — | — |
| Oulainen | 427 | 428 | 265 | 3 | 969 | 25 A | 78 | — | Y | — | — | K | K |
| OULU | | | | | | | | | | | | | |
| Oulu asema | 344 | 458 | 550/265 | 3 | 511 | 63 A, 1500 V | — | — | — | — | — | K | — |
| Oulu Nokela | | | | 0 | 920 | — | — | — | — | — | — | — | K |
| Oulu Öritkari | | | | 0 | 603 | 63 A | 200 | — | — | — | — | — | K |
| Oulu tavara | | | | 0 | 818 | 25 A | — | — | — | — | K | — | K |
| Oulu Tuira | | | | 0 | 761 | — | Y | — | — | — | — | — | K |
| Paimio | | | | 0 | 793 | — | — | — | — | — | — | — | — |
| Palopuro | | | | 0 | 0 | — | — | — | — | — | — | — | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laiturikorkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|------------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|----------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sidoperrong | End loading platform | Lastning på samma plan | Lyftkran | Bränsle | Persontrafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Paltamo (Paltia Oy) | | 230 | 265 | 1 | 686 | — | — | — | K | — | — | K | K |
| Pankakoski | | | | 0 | 0 | — | — | — | Y | — | — | — | — |
| Parikkala | 210 | 379 | 265 | 3 | 729 | — | — | — | K | — | — | — | — |
| Parkano | 600 | 600 | 550 | 3 | 974 | 25 A | 29 | — | K | — | — | K | K |
| Parola | 191 | 196 | 550 | 2 | 730 | 25 A | 9, Y | — | K | — | — | K | K |
| Pello | 454 | 454 | 265 | 1 | 715 | — | 31 | — | K | — | — | K | K |
| Peltosalmi | | | | 0 | 504 | 25 A | 30 | — | Y | — | — | K | K |
| (Perniön viljavarasto) | | | | 0 | 0 | — | — | — | K | Y | — | — | — |
| Peräseinäjoki | | | | 0 | 801 | — | — | — | K | — | — | — | — |
| Pesio kylä | (80) | | (265) | (1) | 783 | — | Y | — | K | — | — | — | K |
| Petäjävesi | 142 | 142 | 265 | 1 | 793 | — | — | — | K | — | — | K | K |
| PIEKSÄMÄKI | | | | | | | | | K | — | — | — | — |
| Pieksämäki asema | 332 | 611 | 265 | 4 | 529 | 63 A | Y | — | — | — | — | K | — |
| Pieksämäki lajittelu | | | | 0 | 994 | — | — | — | — | — | — | — | K |
| Pieksämäki tavaras | | | | 0 | 786 | — | — | — | — | — | K | — | K |
| Pieksämäki Temu | | | | 0 | 985 | 25 A | — | — | K | — | — | — | — |
| Pietarsaari | | (70) | (265) | (1) | 759 | — | — | — | K | — | — | — | K |
| Pihlajavesi | 99 | 120 | 550/265 | 2 | 600 | — | — | — | K | — | — | K | — |
| Pihlaja | | | | 0 | 435 | — | — | — | — | — | — | — | — |
| Pihltpudas | | (125) | (265) | (1) | 787 | 25 A | Y | Y | K | — | — | — | K |
| Piikkiö | | (31) | (265) | (1) | 321 | — | — | — | K | — | — | — | K |
| Pikkarala | | | | 0 | 779 | — | — | — | — | — | — | — | — |
| Pitäjänmäki | | | | 2 | 0 | — | — | — | — | — | — | K | — |
| Pohjankuru | 270 | 306 | 550 | 0 | 324 | — | — | — | K | Y | — | — | K |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laiturikorkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|-------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sidoperrong | Perrong i ändan av banan | Lastning på samma plan | Liftkran | Bränsle | Persontrafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Pohjois-Haaga | 240 | 240 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Pohjois-Louko | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Poikkeus | | | | 0 | 735 | — | — | — | — | — | — | — | — |
| Poiksilta | | | | 0 | 268 | — | — | — | K | — | — | — | K |
| Pori | 251 | 251 | 550 | 2 | 776 | 63 A, 1500 V | 112 | — | Y | 30 | K | K | K |
| Porokylä | 0 | 0 | 0 | 0 | 482 | — | — | — | K | — | — | — | K |
| Porvoo | | 218 | 265 | 1 | 446 | — | 145 | — | K | — | — | K | — |
| Porvoon keskusta | | 68 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Puhos | | | | 0 | 670 | 25 A | 13 | — | K | — | — | — | K |
| Puistola | 274 | 274 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Pukinmäki | 273 | 279 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Pulsa | | (68) | (265) | (1) | 1872 | — | — | — | K | — | — | — | — |
| Punkaharju | | 201 | 265 | 1 | 506 | 25A | — | — | K | — | — | K | K |
| Purola | 270 | 270 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Pyhäkumpu | | | | 0 | 378 | — | 9 | — | K | — | — | — | K |
| Pyhäkumpu erk.vh. | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Pyhäsalmi | | 126 | 265 | 1 | 687 | 25 A | — | — | K | — | — | K | K |
| Pännäinen | | 440 | 265 | 2 | 799 | 25 A | 18 | — | K | — | — | K | K |
| Pääskylähti | | | | 0 | 714 | — | 12 | — | K | — | — | — | K |
| Raahe | | | | 0 | 747 | 63 A | 53 | — | K | — | — | — | K |
| Raippo | | | | 0 | 1890 | — | — | — | — | — | — | — | K |
| Raisio | (120) | (168) | (265) | (3) | 563 | — | — | — | — | — | — | — | K |
| Rajamäki | | | | 0 | 290 | — | — | — | K | — | — | — | K |
| Rajaperkiö | | | | 0 | 876 | — | — | — | — | — | — | — | — |
| Rantasalmi | | (95) | (265) | (1) | 565 | 25 A | 98 | — | K | — | — | — | K |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laiturikorkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaiturin suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|---------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido-perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Rasinsuo | | | | 0 | 765 | — | — | — | — | — | — | — | — |
| Ratikylä | | | | 0 | 771 | — | — | — | K | — | — | — | K |
| Rauha | | | | 0 | 823 | — | — | — | K | — | — | — | K |
| Rauhalampi | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Rauma | | | | 0 | 957 | 25 A | 80 | K | Y | Y | K | — | K |
| Raunio | | | | 0 | 872 | — | — | — | — | — | — | — | — |
| Rautaruukki | | | | 0 | 884 | — | — | — | Y | — | — | — | K |
| Rautjärvi | | | | 0 | 664 | — | — | — | — | — | — | — | — |
| (Rautpohja) | | | | 0 | 0 | — | — | — | Y | — | — | — | — |
| Rekola | 270 | 270 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Retretti | | 121 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| RIIHIMÄKI | | | | | | | | | | | | | |
| Riihimäki Arolampi | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Riihimäki asema | 425 | 430 | 265 | 5 | 668 | 63 A, 1500 V | Y | — | Y | — | K | K | — |
| Riihimäki lajittelu | | | | 0 | 839 | — | — | — | — | — | — | — | K |
| Riihimäki tavara | | | | 0 | 737 | — | Y | Y | K | — | — | — | K |
| Riippa | | | | 0 | 876 | — | — | — | — | — | — | — | — |
| Ristiina | | | | 0 | 885 | — | — | — | K | — | — | — | K |
| Ristijärvi | | (80) | (265) | (1) | 0 | — | — | — | — | — | — | — | — |
| Rovaniemi | 485 | 548 | 550/265 | 3 | 802 | 63 A, 1500 V | 33 | Y | Y | — | — | K | K |
| Ruha | | | | 0 | 886 | — | — | — | — | — | — | — | — |
| Runni | | 36 | 550 | 1 | 0 | — | — | — | — | — | — | K | — |
| Ruosniemi | | (100) | (265) | (1) | 655 | — | — | — | Y | — | — | — | K |
| Ruukki | 430 | 448 | 265 | 2 | 786 | 25 A | 7, Y | — | K | — | — | K | K |
| Ruusutorppa | | | | 0 | 0 | — | — | — | — | — | — | — | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laiturikorkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|-----------------------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido-perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Rytylä | 171 | 173 | 550 | 2 | 500 | — | 7 | — | K | — | — | K | K |
| Röykkä | | | | 0 | 181 | — | — | — | — | — | — | — | — |
| Röyttä | | | | 0 | 733 | 25 A | — | — | K | — | — | — | K |
| Saakoski | | | | 0 | 852 | — | — | — | K | — | — | — | — |
| Saari | | 201 | 265 | 1 | 694 | — | — | — | K | — | — | K | K |
| Saarijärvi | | (75) | (265) | (1) | 594 | 25 A | 40 | K | K | — | — | — | K |
| Salla | | | | 0 | 531 | — | 12 | — | K | — | — | — | K |
| Salmiinen | | | | 0 | 788 | — | — | — | K | — | — | — | — |
| Salmivaara | | | | 0 | 630 | — | — | — | K | — | — | — | — |
| Salo | 306 | 310 | 550 | 3 | 426 | — | — | K | K | — | — | K | K |
| Salpausselkä | | 194 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Sammalisto | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Santala | | 70 | 550 | 1 | 0 | — | — | — | — | — | — | K | — |
| Santamäki | | | | 0 | 0 | — | — | — | K | — | — | — | — |
| Saunakallio | 180 | 275 | 550 | 4 | 650 | — | — | — | Y | — | — | K | K |
| Savio | 270 | 270 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Savonlinna | 165 | 165 | 265 | 2 | 618 | 63 A | Y | — | K | — | K | K | — |
| Savonlinna-Kauppatori (Savontalo) | 165 | 149 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| SEINÄJOKI | | | | 0 | 0 | — | — | — | Y | — | — | — | — |
| Seinäjoki asema | 335 | 514 | 265 | 4 | 491 | 63 A, 1500 V | — | — | — | — | — | K | — |
| Seinäjoki tavara | | | | 0 | 914 | — | Y | — | K | 30 | K | — | K |
| Selänpää | | | | 0 | 802 | — | — | — | — | — | — | — | — |
| Siepijärvi | | | | 0 | 756 | — | Y | — | Y | — | — | — | K |
| Sievi | | (77) | (265) | (1) | 780 | — | — | — | K | — | — | — | — |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Pääty- laituri | Kuormaus- kenttä | Nosturi | Poltto- aine | Henkilö- liikennettä | Tavara- liikennettä |
|------------|-----------------------------------|-----------------------------------|----------------------------|---------------------------------------|--|-------------------------------|------------------------------------|--------------------------------|---------------------------|--------------|-----------------|-------------------------|------------------------|
| Namn | Kortaste perrong- längd | Längsta perrong- längd | Perrong- höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Siikamäki | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Silinjärvi | 156 | 360 | 265 | 2 | 728 | 25 A | — | — | K | — | — | K | K |
| Simo | | 88 | 265 | 1 | 1021 | — | 46 | — | K | — | — | — | — |
| Simpelä | 271 | 301 | 265 | 3 | 844 | 25 A | 17 | K | K | — | — | K | K |
| Sipilä | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Sisättö | | | | 0 | 779 | — | — | — | — | — | — | — | — |
| Siuntio | 112 | 178 | 550 | 2 | 507 | — | — | — | — | — | — | K | — |
| Siuro | | (113) | (265) | (1) | 746 | — | — | — | — | — | — | — | — |
| Skogby | | 68 | 550 | 1 | 0 | — | — | — | — | — | — | K | — |
| Sköldvik | | | | 0 | 971 | 25 A | — | — | — | — | — | — | K |
| Soinlahti | | | | 0 | 888 | 25 A | — | — | Y | — | — | — | K |
| Sorsasalo | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Sukeva | 100 | 239 | 265 | 2 | 663 | — | — | — | K | — | — | K | K |
| Suolahti | | (150) | (265) | (1) | 723 | 25 A | — | — | K | — | — | — | K |
| Suonenjoki | 250 | 341 | 265 | 3 | 857 | 16 A | Y | K | K | — | — | K | K |
| Suoniemi | | | | 0 | 767 | — | — | — | — | — | — | — | — |
| Syrjä | | | | 0 | 245 | — | 6 | — | K | — | — | — | — |
| Syrjämäki | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Sysmäjärvi | | | | 0 | 636 | — | — | — | K, Y | — | — | — | K |
| Säkylä | | | | 0 | 587 | — | — | — | — | — | — | — | — |
| Säkäniemi | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Sänkimäki | | | | 0 | 700 | — | — | — | — | — | — | — | K |
| Särkisalmi | | (60) | (265) | (1) | 555 | — | — | — | K | — | — | — | K |
| Sääksjärvi | | | | 0 | 0 | — | — | — | K | — | — | — | — |
| Taavetti | 188 | 196 | 265 | 2 | 812 | — | Y | — | K | — | — | K | K |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laiturikorkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|--------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sidoperrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Persontrafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Tahkoluoto | | | | 0 | 500 | — | — | — | Y | — | — | — | K |
| Taipale | | | | 0 | 847 | — | — | — | — | — | — | — | — |
| Talvainen | | | | 0 | 765 | 25 A | — | — | K | — | — | — | — |
| Tammisaari | | 80 | 550 | 1 | 0 | — | — | — | — | — | — | K | — |
| TAMPERE | | | | | | | | | | | | | |
| Tampere asema | 500 | 500 | 550 | 5 | 536 | 63 A, 1500 V | — | — | — | — | — | K | — |
| Tampere Järvensivu | | | | 0 | 0 | — | — | — | — | — | — | — | K |
| Tampere tavara | | | | 0 | 808 | 63 A | 15 | — | — | 12,5 | K | — | K |
| Tampere Viinikka | | | | 0 | 859 | — | 179 | — | — | 50 | — | — | K |
| Tapanila | 272 | 272 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Tapavainola | | | | 0 | 774 | — | — | — | — | — | — | — | — |
| Tavastila | | 47 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Tervajoki | | 171 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Tervasuo | | | | 0 | 722 | — | — | — | — | — | — | K | — |
| Tervola | 231 | 301 | 265 | 2 | 821 | — | 11 | — | K | — | — | K | — |
| Teuva | | | | 0 | 477 | 25 A | — | — | K | — | — | — | K |
| Tikkala | | | | 0 | 775 | — | — | — | K | — | — | — | — |
| Tikkurila | 320 | 444 | 550 | 6 | 450 | — | Y | — | K | — | — | K | K |
| Tohmajärvi | | | | 0 | 745 | — | — | — | K | — | — | — | K |
| Toijala | 450 | 450 | 550 | 4 | 770 | 25 A | — | — | K | Y | — | K | K |
| Toivala | | | | 0 | 786 | — | — | — | K | — | — | — | K |
| Tolsa | 109 | 109 | 265 | 2 | 0 | — | — | — | — | — | — | K | — |
| Tomnola | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Torkkeli | | | | 0 | 831 | — | — | — | — | — | — | — | — |
| Tornio | (86) | 101 | 265 | 1 | 718 | 63 A | 215, Y | K, Y | K | 70 | — | — | K |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoitettava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|-------------------|--------------------------|--------------------------|----------------------|--------------------------------|---|-------------------------|----------------------------|----------------------|--------------------|-----------|------------|--------------------|---------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | End loading platform | Loading site Crane | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform lenght [m] | Max. platform lenght [m] | Platform height [mm] | Number of tracks with platform | Design train lenght (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site Crane | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Tornio-raja | | | | 0 | 0 | — | — | — | — | — | — | — | K |
| Tuomarila | 220 | 222 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Tuomioja | | (198) | (265) | (1) | 829 | 25 A | 11 | — | K | — | — | — | — |
| Turenki | 170 | 170 | 550 | 2 | 1287 | — | — | — | K | — | — | K | K |
| TURKU | | | | | | | | | | | | | |
| Kupittaa | 420 | 420 | 550 | 2 | 657 | — | — | — | — | — | — | K | — |
| Turku asema | 315 | 466 | 550 | 6 | 788 | 63 A, 1500 V | Y | Y | — | — | K | K | K |
| Turku satama | 300 | 304 | 550/265 | 2 | 431 | 63 A | — | — | — | — | — | K | — |
| Turku tavara | | | | 0 | 416 | 25 A | 8 | — | — | — | — | — | K |
| Turku Viheriäinen | | | | 0 | 469 | — | — | — | — | — | — | — | K |
| Tuupovaara | | | | 0 | 599 | — | 13 | — | K | — | — | — | K |
| Tuuri | | 66 | 550 | 1 | 335 | — | — | — | K | — | — | K | — |
| Törmä | | | | 0 | 887 | — | — | — | — | — | — | — | — |
| Törölä | | | | 0 | 782 | — | — | — | — | — | — | — | — |
| Töysä | | (91) | (265) | (1) | 364 | — | — | — | K | — | — | — | — |
| Uimaharju | | 174 | 265 | 1 | 897 | 25 A | — | — | K | — | — | K | K |
| Ulasoori | | | | 0 | 0 | — | Y | — | — | — | — | — | — |
| Urjala | | | | 0 | 755 | — | — | — | K | — | — | K | — |
| Utajärvi | 163 | 174 | 265 | 2 | 736 | — | 25 | — | K | — | — | K | K |
| Utti | | | | 0 | 1025 | — | 100 | — | K | — | — | — | K |
| Uusikaupunki | | (66) | (265) | (1) | 545 | — | 24 | — | — | — | — | — | K |
| Uusikylä | (114) | (116) | (550) | (3) | 527 | — | 57 | — | K | — | — | — | K |
| Vaajakoski | | (127) | (265) | (1) | 626 | 25 A | 13 | — | K | — | — | — | K |
| Vaala | 183 | 236 | 265 | 2 | 1050 | 25 A | 25 | — | K | — | — | K | — |
| Vaarala | | | | 0 | 327 | — | — | — | K | — | — | — | K |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|-------------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|---------------------|
| Namn | Kortaste perrong-längd | Längsta perrong-längd | Perrong-höjd | Antal spår med perrong | Dimensionerande spårängd (godstrafik) | Tillgång till elström | Sido-perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Vaasa | 287 | 287 | 550 | 2 | 695 | 63 A, 1500 V | 192, Y | Y | Y | — | — | K | K |
| Vahojärvi | | | | 0 | 740 | — | — | — | — | — | — | — | — |
| VAINIKKALA | | | | | | | | | | | | | |
| Vainikkala asema | 482 | 484 | 550 | 3 | 997 | — | — | — | — | — | — | K | — |
| Vainikkala tavara | | | | 0 | 1138 | 25 A | Y | K | K | 30.5 | — | — | K |
| Vainikkala-raja | | | | 0 | 0 | — | — | — | — | — | — | K | K |
| Valimo | 270 | 270 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Valkeakoski | | (42) | (265) | (1) | 903 | — | 54 | — | K | — | — | — | K |
| Valkeasuo | | | | 0 | 628 | — | — | — | — | — | — | — | — |
| Valtimo | | | | 0 | 819 | — | — | — | K | — | — | — | K |
| Vammala | 251 | 251 | 550 | | 875 | — | 128 | — | Y | — | — | K | K |
| Vanattara | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Vantaankoski | 276 | 276 | 550 | 2 | 0 | — | — | — | — | — | — | K | — |
| Varkaus | 180 | 213 | 265 | 2 | 763 | 25 A | 20, Y | Y | K | — | — | K | K |
| Vartius | | | | 0 | 1127 | — | — | — | Y | — | — | — | K |
| Vartius-raja | | | | 0 | 0 | — | — | — | — | — | — | — | K |
| Vasikkahaka | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Vaskiluoto | | | | 0 | 497 | — | Y | — | K | — | — | — | K |
| Venetmäki | | | | 0 | 919 | — | — | — | K | — | — | — | — |
| Vesanka | | | | 0 | 394 | — | 10 | — | K | — | — | — | — |
| Vieikki | | | | 0 | 750 | — | — | — | K | — | — | — | — |
| Vierumäki | | | | 0 | 620 | — | 92 | — | K | — | — | — | K |
| Vihanti | 395 | 455 | 265 | 2 | 722 | 25 A | — | — | Y | — | — | K | K |
| Vihuri | 58 | 103 | 265 | 2 | 603 | 25 A | 29 | — | K | — | — | K | K |
| Viala | 170 | 170 | 550 | 2 | 305 | — | — | — | K | — | — | K | K |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara- liikennettä |
|-----------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|------------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido- perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Vinijärvi | 136 | 211 | 265 | 2 | 663 | 25A | — | — | K | — | — | K | — |
| Vika | | | | 0 | 0 | — | — | — | — | — | — | K | — |
| Vilppula | | 110 | 550 | 1 | 732 | 25 A | — | — | K | — | — | K | K |
| Vinnilä | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Virtakallio | | | | 0 | 0 | — | — | — | — | — | — | — | — |
| Voltti | | (149) | (265) | (1) | 884 | — | — | — | K | — | — | — | — |
| Vuohijärvi | | | | 0 | 733 | — | 15 | K | — | — | — | — | K |
| Vuojoki | | | | 0 | 782 | — | — | — | — | — | — | — | — |
| Vuokatti | (111) | (116) | (265) | (2) | 674 | 25 A | — | — | Y | — | — | — | K |
| Vuonilahti | | 94 | 265 | 1 | 701 | — | — | — | — | — | — | K | — |
| Vuonos | | | | 0 | 501 | — | — | — | Y | — | — | — | K |
| (Vuorten-Vuori) | | | | 0 | — | — | Y | — | Y | — | — | — | — |
| Yksipihlaja | | | | 0 | 859 | — | 57 | — | K | — | — | — | K |
| Ylistaro | | 176 | 265 | 1 | 0 | — | — | — | — | — | — | K | — |
| Ylitornio | | 167 | 265 | 1 | 138 | 25 A | — | — | — | — | — | K | — |
| Ylivalli | | | | 0 | 1048 | — | — | — | K | — | — | — | — |
| Ylivieska | 315 | 482 | 265 | 3 | 812 | 63 A | Y | — | Y | Y | K | K | K |
| Yläkoski | | | | 0 | 472 | — | — | — | K | — | — | — | K |
| Ylämylly | | | | 0 | 674 | — | 77 | — | K | — | — | — | K |
| Ylöjärvi | | | | 0 | 735 | — | 60 | — | K | — | — | — | K |
| Ypykkävaara | | | | 0 | 786 | — | — | — | K | — | — | — | K |
| Äetsä | | (157) | (265) | (1) | 951 | — | — | — | K | — | — | — | K |
| Ähtäri | 85 | 225 | 265 | 2 | 667 | — | — | — | — | — | — | K | — |
| Ämmänsaari | 0 | 0 | 0 | | 721 | 25 A | — | — | — | — | — | — | K |
| Äänekoski | | (73) | (265) | (1) | 683 | 25 A | 19 | K | K, Y | — | — | — | K |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Kaukoohjaus manuaalinen | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|---------------|-----------------|-------------|---------|--------------------------|--------------|-------------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Ahonpää | | Aho | | Seinäjoki – Oulu | | | | |
| Aviapolis | | Avp | | Tikkurila – Vantaankoski | Vantaa | K | | |
| Jäniskorpi | | Jnk | | Seinäjoki – Oulu | | | | |
| Kivistö | | Ktö | | Tikkurila – Vantaankoski | Vantaa | K | | |
| Kullasvaara | | Kuv | | Kouvola – Luumäki | | | | |
| Kuninkaanmäki | | Knm | 38+500 | Kerava – Vuosaari | Vantaa | K | | |
| Leinelä | | Lniä | | Tikkurila – Vantaankoski | Vantaa | K | | |
| Lentoasema | | Len | | Tikkurila – Vantaankoski | Vantaa | K | | |
| Liminpuro | Flygplatsen | Lmp | 864+750 | Oulu – Kontiomäki | Vaala | K | | |
| Niinimäki | | Nmä | | Lahti – Kouvola | | | | |
| Niska | | Nsk | 826+880 | Oulu – Kontiomäki | Utajärvi | K | | |
| Petas | | Pet | | Tikkurila – Vantaankoski | Vantaa | K | | |
| Puikkokoski | | Pui | 665+680 | Kontiomäki – Vartius | Paltamo | K | | |
| Riijärvi | | Rjr | | Seinäjoki – Oulu | | | | |
| Ruonneva | | Rnv | | Seinäjoki – Oulu | | | | |
| Ruskeasanta | | Rs | | Tikkurila – Vantaankoski | Vantaa | K | | |
| Saarela | Rödsand | Srl | | Seinäjoki – Oulu | | | | |
| Salmennäki | | Sal | | Seinäjoki – Oulu | | | | |
| Saunamäki | | Smä | | Lahti – Kouvola | | | | |
| Tikkaperä | | Tkp | | Seinäjoki – Oulu | | | | |
| Temmesjoki | | Tmj | | Seinäjoki – Oulu | | | | |
| Tuomaanvaara | | Tva | 682+300 | Kontiomäki – Vartius | Ristijärvi | K | | |
| Vehkala | Veckal | Veh | | Tikkurila – Vantaankoski | Vantaa | K | | |
| Viinikkala | Vinikby | Vkl | | Tikkurila – Vantaankoski | Vantaa | K | | |
| Villähde | | Vlh | | Lahti – Kouvola | | | | |
| Vuosaari | Nordsjö | Vsa | 48+750 | Kerava – Vuosaari | Helsinki | K | | |

| Nimi | Lyhin laituripituus | Pisin laituripituus | Laiturikorkeus | Laitureiden lukumäärä | Mitoitettava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Päätylaituri | Kuormauskenttä | Nosturi | Polttoaine | Henkilöliikennettä | Tavara-liikennettä |
|---------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|------------|--------------------|--------------------|
| Namn | Kortaste perronglängd | Längsta perronglängd | Perronghöjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido-perrong | Perrong i ändan av banan | Lastning på samma plan | Lyftkran | Bränsle | Persontrafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Ahonpää | | | | | | | | | | | | | |
| Aviapolis | | | | | | | | | | | | | |
| Jäniskorpi | | | | | | | | | | | | | |
| Kivistö | | | | | | | | | | | | | |
| Kullasvaara | | | | | | | | | | | | | |
| Kuninkaanmäki | | | | | | | | | | | | | |
| Leinelä | | | | | | | | | | | | | |
| Lentoasema | | | | | | | | | | | | | |
| Limnypuro | | | | | | | | | | | | | |
| Niinimäki | | | | | | | | | | | | | |
| Niska | | | | | | | | | | | | | |
| Petas | | | | | | | | | | | | | |
| Puikkokoski | | | | | | | | | | | | | |
| Riijärvi | | | | | | | | | | | | | |
| Ruonneva | | | | | | | | | | | | | |
| Ruskeasanta | | | | | | | | | | | | | |
| Saarela | | | | | | | | | | | | | |
| Salmennmäki | | | | | | | | | | | | | |
| Tikkaperä | | | | | | | | | | | | | |
| Temmesjoki | | | | | | | | | | | | | |
| Tuomaanvaara | | | | | | | | | | | | | |
| Vehkala | | | | | | | | | | | | | |
| Viinikkala | | | | | | | | | | | | | |
| Villähde | | | | | | | | | | | | | |
| Vuosaari | | | | | | | | | | | | | |

| Nimi | Toinen nimi | Lyhenne | Km Hki | Rataosuus | Kunta | Kauko-ohjaus manuaalinen | Yksityisraiteita | Vaihtotyö-mahdollisuus |
|-------------|-----------------|-------------|---------|---|--------------|--------------------------|--------------------------|----------------------------|
| Namn | Namn på svenska | Förkortning | | Banavsnitt | Kommun | Trafikledning | Privata spåranläggningar | Möjlighet till växelarbete |
| Name | Another name | Abbr. | | Section | Municipality | Traffic control | Private sidings | Shunting |
| Buslovskaja | | | 288+000 | Vainikkala raja – Viipuri | | K | | |
| Haaparanta | Haparanda | Hpa | 888+130 | Tornio-raja – Boden | Haparanda | K | | |
| Kivijärvi | | Kiv | 759+800 | Vartius-raja – Kostamus | | K | | |
| Svetogorsk | | | 338+200 | Imatrankoski-raja – Kamennogorsk (Antrea) | | K | | |
| Värtsilä | | Vär | 553+300 | Niirala-raja – Matkaselkä | | K | | |

| Nimi | Lyhin laiturin pituus | Pisin laiturin pituus | Laituri- korkeus | Laitureiden lukumäärä | Mitoittava raidepituus (tavaraliikenne) | Sähkövirran saanti | Sivulaituri, suurin pituus | Pääty-laituri | Kuorma-us-kenntä | Nosturi | Poltto-aine | Henkilö-liikennettä | Tavara-liikennettä |
|-------------|--------------------------|--------------------------|----------------------|---------------------------------|---|-------------------------|----------------------------|--------------------------|------------------------|-----------|-------------|---------------------|--------------------|
| Namn | Kortaste perrong-längd | Längsta perrong-längd | Perrong-höjd | Antal spår med perrong | Dimensionerande spårlängd (godstrafik) | Tillgång till elström | Sido-perrong | Perrong i ändan av banan | Lastning på samma plan | Liftkran | Bränsle | Person- trafik | Godstrafik |
| Name | Min. platform length [m] | Max. platform length [m] | Platform height [mm] | Number of tracks with platforms | Design train length (freight traffic) [m] | Power supply [400 V, A] | Side loading platform [m] | End loading platform | Loading site | Crane [t] | Fuel | Passenger traffic | Freight traffic |
| Buslovskaja | | | | | | | | | | | | | |
| Haaparanta | | | | | | | | | | | | | |
| Kivijärvi | | | | | | | | | | | | | |
| Svetogorsk | | | | | | | | | | | | | |
| Värtsilä | | | | | | | | | | | | | |

Appendix 3

Transport Operation Regulations for Cross-border Movements in Tornio-Haaparanta Area

Introduction

The previous regulations have been redefined, because the signals have been changed in this area and the new Train Safety Regulation was introduced in Finland on 5 June 2005.

At the national border the area between signals HP 6/3 and T 832 is called "Common zone", which is jointly reserved by the Swedish and Finnish traffic control operators.

In principle, only one train movement is allowed at a time within the common zone, with the exception of irregular situations, such as engine failure or accident.

These regulations have been made in co-operation between Banverket's North Swedish area and the Finnish Rail Administration.

Scope

The Regulations are applicable to cross-border movements between Tornio and Haaparanta, and within the common zone.

Reference Documents

- **TRI (BVF 900.3)** (Safety Regulation / Traffic Safety Instructions)
- **Jt** (Train Safety Regulation)

Definitions

- **Common zone**
The area to be jointly reserved by the Swedish and Finnish traffic control operators and limited on the Swedish side by the 6/3 intermediate signal and on the Finnish side by the T 832 ground signal.
- **Cross-border movement**
Movements entirely or partly operated within the common zone.
- **Movement**
Refers to railway work and shunting.
- **Permission**
Refers to permission to allow movement to begin.
- **Swedish movement**
Shunting or railway work started in Sweden.
- **Finnish movement**
Shunting or railway work started in Finland.

General

The regulations are drafted in Swedish and Finnish with an identical content.

No movement is allowed within the common zone without the Swedish and Finnish traffic control operators having reserved the relevant section of line.

More than one movement is allowed in the common zones only in irregular situations, such as engine failure or accident. In such cases, the work of several movements shall be agreed at the time.

Tornio-Haaparanta Cross-border Movements

General

Movements are operated as specified in the Finnish Jt, as “shunting” operations, and as specified in the Swedish TRI (BVF 900.3), as “shunting” or “small-wagon shunting” operations.

Messages and Message Transmission

The Finnish staff shall be in contact with the Finnish traffic control operators, who will deliver the message to the Swedish traffic control operators.

The Swedish staff shall be in contact with the Swedish traffic control operators, who will deliver the message to the Finnish traffic control operators.

Haaparanta-Tornio

Prior to the commencement of a Swedish cross-border shunting operation in the Haaparanta-Tornio direction, permission by the traffic control operators in Haaparanta is required.

Prior to the commencement of a Finnish cross-border shunting operation in the Haaparanta-Tornio direction, permission by the traffic control operators in Tornio is required.

The traffic control unit that granted permission shall be notified of the completion of the movement.

Tornio-Haaparanta

Prior to the commencement of a Finnish cross-border shunting operation in the Tornio-Haaparanta direction, permission by the traffic control operators in Tornio is required.

Prior to the commencement of a Swedish cross-border shunting operation in the Tornio-Haaparanta direction, permission by the traffic control operators in Haaparanta is required.

The traffic control unit that granted permission shall be notified of the completion of the movement.

Railway Work within the Common Zone

General

The Finnish staff shall be in contact with the Finnish traffic control operators transmitting possible messages to and from the Swedish traffic control operators.

The Swedish staff shall be in contact with the Swedish traffic control operators transmitting possible messages to and from the Finnish traffic control operators.

Swedish Staff

The permission of the Haaparanta traffic control operators is required for work carried out by the Swedish staff within the common zone.

Prior to granting permission, the Haaparanta and Tornio traffic control operators shall reserve the common zone.

The Haaparanta traffic control operators shall be notified of the completion of the work.

Finnish Staff

The permission of the Tornio traffic control operators is required for work carried out by the Finnish staff within the common zone.

Prior to granting permission, the Tornio and Haaparanta traffic control operators shall reserve the common zone.

The Tornio traffic control operators shall be notified of the completion of the work.

Safety Calls and Documentation

Safety Calls

The safety calls between the Swedish and Finnish traffic control operators shall be conducted either in Swedish or Finnish.

There is a word list with translations in Appendix 5, while Appendix 6 includes examples of phrases to be used.

The safety calls shall be repeated.

Train Log

A train log shall be used according to the instructions and regulations of the traffic control.

Reservation of Common Zone

The reservation of the common zone shall be operated jointly by the Swedish and Finnish traffic control operators.

The clearance of the occupancy of the common zone shall be operated jointly by the Swedish and Finnish traffic control operators.

Maximum Permitted Speed

The maximum permitted speeds are specified in the speed signs, which are described in Appendix 2.

Accidents

Any accident or risk of an accident shall be reported to the traffic control operators.

Manual Signalling

The Swedish shunting staff shall implement manual signalling as specified in BVF 900.3, irrespective of whether the activity takes place on the Swedish or Finnish side of the border.

The Finnish shunting staff shall implement signalling as specified in Jt, irrespective of whether the activity takes place on the Finnish or Swedish side or the border.

A “stop” signal shall always be followed, irrespective of whether it is operated in conformity with the Swedish or Finnish regulations.

Appendix 1

Signals and Signal Aspects

The signals are applicable in conformity with the regulations of the country concerned.

Haaparanta–Tornio Direction

From Finnish tracks, intermediate signal (main ground signal) 1/6 km 1310.845.



“Stop”



“Proceed”



“Proceed – check clearance”



“Proceed – check turnouts and clearance”

From Swedish tracks, intermediate signal 5/6 km 1310.697



“Stop”



“Proceed – check turnouts and clearance”

Swedish and Finnish tracks, intermediate signal 6/8 km 1311.006



“Stop”



“Proceed”

Common track, Tornio T 832, km 886.8



“Stop”



“Proceed with caution”

Tornio-Haaparanta Direction

No optical signals are used in Tornio for movements towards Sweden.
Intermediate signal 6/3, km 1311.012



"Stop"




"Proceed – check
turnouts and clearance"

Appendix 2

Speed Signs

In conformity with Jt



Maximum permitted speed
(the example displaying max. 30 km/h)

In conformity with BVF 900.3



Maximum permitted speed
(the example displaying max. 30 km/h)

Appendix 3
“Stop” Signalling

In conformity with BVF 900.3




Read: Stop

In conformity with Jt




Read: Stop



Read: Danger (emergency stop)

Appendix 4

Drawing of Haaparanta–Tornio Area



Appendix 5

Translation Table

| Svenska | Suomi | English |
|----------------------|-----------------------|------------------------|
| Växling | Vaihtotyö | Shunting work |
| Arbete | Ratatyö | Work |
| Reserverad zon | Varaus | Reserved/Occupied |
| Upphävande | Peruuttaminen | Clearance of occupancy |
| Tågklarerare | Junasuorittaja | Dispatcher |
| Trafikledning | Liikenteenohjaus | Traffic control |
| Station | Asema | Station |
| Fara | Vaara | Danger |
| Stoppsignal | Seis-opaste | Stop aspect |
| Passage av en signal | Opastimen ohittaminen | Passing of signal |
| Signal | Opastin/Opaste | Signal/Signal aspect |
| Repetera | Toistaa | Repeat |
| Rätt uppfattat | Oikein ymmärretty | Correctly read |

Appendix 6

Example Phrases

Zone reservation request for shunting work

Swe: Tågklareraren _____, reserverad zon Haparanda–Torneå, växling.

Fin: Liikenteenohjaus _____, varaus Haaparanta–Tornio välille, vaihtotyö.

Eng: Traffic control _____, reservation Haaparanta–Tornio, shunting.

Zone reservation request for railway work

Swe: Tågklareraren _____, reserverad zon Haparanda–Torneå, arbete.

Fin: Liikenteenohjaus _____, varaus välille Haaparanta–Tornio, työ.

Eng: Traffic control _____, reservation Haaparanta–Tornio, work.

Clearance of occupied zone

Swe: Tågklareraren _____, upphävande reserverad zon _____ - _____

Fin: Liikenteenohjaus _____, varauksen peruuttaminen välille _____ - _____

Eng: Traffic control _____, clearance of occupied zone _____ - _____

Request for reservation in dangerous situation

Swe: Tågklareraren _____, Fara Haparanda–Torneå.

Fin: Liikenteenohjaus _____, vaara Haaparanta–Tornio,

Eng: Traffic control _____, danger Haaparanta–Tornio.

Permission to pass stop signal aspect, Haaparanta

Swe: Tågklareraren Haparanta, medgivande att passera signal (ett-sex) och/eller (åtta-tre) och/eller (sex-åtta)

Fin: Liikenteenohjaus Haaparanta, lupa ohittaa opastin (yksi-kuusi) ja/tai (kahdeksan-kolme) ja/tai (kuusi-kahdeksan)

Eng: Traffic control Haaparanta, permission to pass signal (one-six) and/or (eight-three) and/or (six-eight)

Permission to pass stop signal aspect, Tornio

Swe: Tågklareraren Torneå, växling, medgivande att passera signal (T åtta-tre-två)

Fin: Liikenteenohjaus Tornio, vaihtotyö, lupa ohittaa opastin (T kahdeksan-kolme-kaksi)

Eng: Traffic control Tornio, shunting, permission to pass signal (T eight-three-two)

Correctly read

Swe: Rätt uppfattat

Fin: Oikein ymmärretty

Eng: Correctly read

Repeat

Swe: Repetera

Fin: Toista

Eng: Repeat

Appendix 4

Loading Gauge

The loading gauge (KU) refers to the space inside which the load on an open wagon shall remain, when the wagon is in the centre position on a straight, even track.




Figure 1. Principal dimensions of the loading gauge.

Use of the Loading Gauge

The loading gauge is valid on the whole rail network with the exceptions mentioned below.

The loading gauge may be used for wagons in which the wheelbase or the distance between bogie centres is max. 17.5m, and the length of the loading area of the wagon outside the wheelbase or the distance between bogie centres is max. 0.2 times the length of the wheelbase or the distance between bogie centres. In other cases, loading shall be examined separately.

If there is a risk that the load may be displaced laterally outside the loading gauge during transportation, the width of the load shall be reduced correspondingly. If the displacement of the load may increase the height of some parts of the load so that they extend outside the loading gauge, the height of the load shall be reduced correspondingly.

If the load extends below the floor level of the wagon, the regulations concerning the vehicle gauge (LKU) are applied or the load is carried as special transport.

Loading Gauge Restrictions

The bridges on the line section Helsinki (passenger railway yard) – Pasila (passenger railway yard) - Ilmala (depot) restrict the loading gauge. The loading gauge valid on these bridges is marked with a dashed line (-----) on the loading gauge drawing (Figure 1).

On several industrial and other sidings, there are loading gauge restrictions, which shall be taken into account in local traffic operating.

Transports Exceeding the Loading Gauge

Lorries, lorry trailers and containers exceeding the loading gauge may be transported on separately specified line sections on the conditions laid down in the transport permit.

Other transports exceeding the loading gauge are transported as special transports.

Appendix 5

Structure Gauge

The form and dimensions of the structure gauge (ATU) on a straight track, on an open line and in the railway yard are shown in Figure 1. The space required for the mounting of the catenary structure and for the passage of the pantograph on electrified lines is marked by the broken line D-E-F-G-H-L. The widths of the structure gauge in curves, restrictions and more detailed instructions are presented in the RAMO publication, part 2 "Radan geometria" (Track geometry).

Effective Passing Clearance

The structure gauge described on the previous page shall be followed when building and mounting new structures and equipment in the vicinity of the track. The structure gauge or the deviations from it constitute the effective available structure gauge, that is the passing clearance, for special transports. Information about the passing clearance are collected for each line section and continuously updated by the maintainers.




Figure 1. Principal dimensions of the structure gauge.

Appendix 6

Line Categories and Permitted Speeds for Different Axle Loads

Lines other than those listed in Table 2 are secondary lines. The secondary lines belong to different line categories as indicated in Table 3.

Division of Lines into Line Categories

The lines are divided into line categories according to the superstructure as follows:

Table 1. Division of lines into line categories.

| Line category | | Superstructure | | |
|----------------|--------|------------------------|------------------------------|----------------------|
| RHK | UIC | Rails | Sleepers | Ballast |
| A | C4 | K30, K33 | wooden | gravel or equivalent |
| B ₁ | D4 | K43, 54 E1, K60, 60 E1 | wooden | gravel or equivalent |
| B ₂ | D4 | K43, K60 | wooden, concrete | railway ballast |
| C ₁ | D4 /E4 | 54 E1 | wooden, concrete before 1987 | railway ballast |
| C ₂ | D4/E4 | 54 E1 | concrete 1987 and after | railway ballast |
| D | D4/E4 | 60 E1 | concrete | railway ballast |

The border of the line category is marked in the middle of the station building in the traffic operating point, unless another point is indicated by the kilometre marking.

The line categories for sections of lines are also presented in Figure 1.

Responsibility of the Track Maintainer

The track maintainer has the right to issue, at his discretion, regulations restricting the permitted axle load and speed depending on the condition of the track superstructure.

Table 2. Categories of the main lines and permitted speeds for different axle loads.

| Section of line | Line category | | Passenger trains | | Freight trains | | | |
|---|----------------|-----|-------------------|------------|----------------|-----|-------|-----|
| | RHK | UIC | locomotive hauled | motor cars | 16t | 20t | 22.5t | 25t |
| Helsinki – Tampere | | | | | | | | |
| Helsinki – Pasila | C ₁ | D4 | 80 | 80 | 80 | 80 | 80 | — |
| Pasila – Tikkurila westernmost track | D | E4 | 160 | 160 | 120 | 120 | 100 | 100 |
| Pasila – Tikkurila western middle track | D | E4 | 160 | 160 | 120 | 120 | 100 | 100 |
| Tikkurila – Kerava westernmost track | D | E4 | 160 | 200 | 120 | 120 | 100 | 100 |
| Tikkurila – Kerava western middle track | D | E4 | 160 | 200 | 120 | 120 | 100 | 100 |
| Pasila – Kerava easternmost middle track | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Pasila – Kerava easternmost track | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| Kerava – Tampere | D | E4 | 200 | 200 | 120 | 120 | 100 | 100 |
| Toijala – Valkeakoski | C ₁ | D4 | 50 | 50 | 50 | 50 | 50 | — |
| Kerava – Sköldvik | | | | | | | | |
| Kerava – shunting track switch | C ₂ | D4 | 30 | 30 | 30 | 30 | 30 | — |
| Kytömaa switch – Sköldvik | D | D4 | 80 | 80 | 80 | 80 | 80 | — |
| Kerava – Lahti | | | | | | | | |
| Kerava – Hakosilta | D | E4 | 200 | 220 | 120 | 120 | 100 | 100 |
| Hakosilta – Lahti | D | E4 | 160 | 160 | 120 | 120 | 100 | 80 |
| Helsinki – Port of Turku | | | | | | | | |
| Helsinki – Leppävaara | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Leppävaara – Kirkkonummi | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Kirkkonummi – Karjaa | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | — |
| Karjaa – Pohjankuru | D | D4 | 160 | 200 | 120 | 120 | 100 | — |
| Pohjankuru – km 103,6 | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | — |
| km 103,6 – km 158,0 | C ₂ | D4 | 160 | 200 | 120 | 120 | 100 | — |
| km 158,0 – Turku | C ₁ | D4 | 160 | 180 | 120 | 120 | 100 | — |
| Turku – Port of Turku | C ₁ | D4 | 40 | 40 | 40 | 40 | 40 | — |
| Huopalahti – Vantaankoski | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Turku – Uusikaupunki/Naantali | | | | | | | | |
| Turku – Raisio (km 207,4) | C ₁ | D4 | 60 | 60 | 60 | 60 | 60 | — |
| Raisio (km 207,4) – Uusikaupunki (km 265,1) | B ₁ | D4 | 60 | 60 | 60 | 60 | 50 | — |
| Uusikaupunki (km 265,1) – km 266,4 | C ₁ | D4 | 30 | 30 | 30 | 30 | 30 | — |
| Raisio – Naantali | B ₁ | D4 | 60 | 60 | 60 | 60 | 50 | — |
| Hyvinkää – Hanko | | | | | | | | |
| Hyvinkää – km 133,1 | C ₁ | D4 | 80 | 80 | 80 | 80 | 80 | — |
| km 133,1 – Kirkniemi | D | D4 | 80 | 80 | 80 | 80 | 80 | — |
| Kirkniemi – km 152,2 | D | E4 | 80 | 80 | 80 | 80 | 80 | 80 |
| km 152,2 – Karjaa | C ₁ | E4 | 80 | 80 | 80 | 80 | 80 | 60 |
| Karjaa – km 205,7 | D | E4 | 120 | 120 | 120 | 120 | 100 | 100 |
| km 205,7 – Hanko | C ₁ | E4 | 60 | 60 | 60 | 60 | 60 | 60 |
| Toijala – Turku | | | | | | | | |
| Toijala – km 256,7 | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| km 256,7 – Turku | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Lielähti – Mäntyluoto/Rauma | | | | | | | | |
| Lielähti – Kokemäki | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Kokemäki – Harjavalta | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Harjavalta – Pori | D | E4 | 140 | 140 | 120 | 120 | 100 | 100 |
| Pori – Mäntyluoto | C ₁ | E4 | 70 | 70 | 70 | 70 | 70 | 50 |
| Kokemäki – Rauma | D | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Tampere – Seinäjoki | | | | | | | | |
| Tampere – Lielähti | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Lielähti – Seinäjoki | D | D4 | 160 | 160 | 120 | 120 | 100 | — |
| Parkano – Niinisalo | A | C4 | 30 | 30 | 30 | 30 | — | — |
| Parkano – Kihniö | A | C4 | 30 | 30 | 30 | 30 | — | — |
| Tampere – Pieksämäki | | | | | | | | |
| Tampere – Orivesi | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Orivesi – Jämsänkoski | D | D4 | 120 | 140 | 120 | 120 | 100 | — |
| Jämsänkoski–Saakoski | D | D4 | 160 | 160 | 120 | 120 | 100 | — |
| Saakoski – Jyväskylä | C ₁ | D4 | 160 | 160 | 120 | 120 | 100 | — |
| Jyväskylä – Pieksämäki | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |

| Section of line | Line category | | Passenger trains | | Freight trains | | | |
|----------------------------------|-------------------|-----|-------------------|------------|----------------|-----|-------|-----|
| | RHK | UIC | locomotive hauled | motor cars | 16t | 20t | 22.5t | 25t |
| Orivesi – Seinäjoki | | | | | | | | |
| Orivesi – Haapamäki | B ₁ | D4 | 100 | 100 | 100 | 70 | 50 | — |
| Haapamäki – km 301,4 | B ₁ | D4 | 100 | 100 | 100 | 60 | 50 | — |
| km 301,4 – Pihlajavesi | B ₂ | D4 | 100 | 100 | 100 | 90 | 80 | — |
| Pihlajavesi – Seinäjoki | B ₁ | D4 | 100 | 100 | 100 | 60 | 50 | — |
| Seinäjoki – Kaskinen | B ₁ 1) | D4 | 80 | 80 | 80 | 60 | 50 | — |
| Seinäjoki – Vaasa | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Seinäjoki – Tornio border | | | | | | | | |
| Seinäjoki – km 481,6 | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| km 481,6 – Karhukangas | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Karhukangas – Oulu | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Oulu – Kemi | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Kemi – Tornio | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Tornio – Tornio border | C ₁ | D4 | 40 | 40 | 40 | 40 | 40 | — |
| Pännäinen – Pietarsaari | C ₁ | D4 | 60 | 60 | 60 | 60 | 50 | — |
| Tuomioja – Raahе | C ₂ | D4 | 80 | 80 | 80 | 80 | 80 | — |
| Tornio – Röyttä | B ₁ | D4 | 50 | 50 | 50 | 50 | 50 | — |
| Tornio – Kolari | | | | | | | | |
| Tornio – km 914 | C ₂ | D4 | 100 | 100 | 100 | 100 | 100 | — |
| km 914 – km 1011,6 | B ₂ | D4 | 100 | 100 | 100 | 90 | 80 | — |
| km 1011,6 – Kolari | C ₁ | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Laurila – Kelloseleä | | | | | | | | |
| Laurila – Koivu | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Koivu – Rovaniemi | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Rovaniemi – Misi | C ₂ | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Misi – Kemijärvi | C ₁ | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Kemijärvi – Isokylä | C ₁ | D4 | 50 | 50 | 50 | 50 | 50 | — |
| Isokylä – Kelloseleä | A | C4 | 50 | 50 | 50 | 40 | — | — |
| Riihimäki – Kouvola | | | | | | | | |
| Riihimäki – Hakosilta | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Lahti – Kouvola | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Lahti – Heinola | B ₁ | D4 | 60 | 60 | 60 | 60 | 50 | — |
| Lahti – Port of Loviisa | B ₁ | D4 | 60 | 60 | 60 | 60 | 50 | — |
| Kouvola – Kontiomäki | | | | | | | | |
| Kouvola – Pieksämäki | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Pieksämäki – Iisalmi | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Iisalmi – Murtoäki | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Murtoäki – Kontiomäki | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Kouvola – Kuusankoski | C ₁ | D4 | 50 | 50 | 50 | 50 | 50 | — |
| Murtoäki – Otanmäki | A | C4 | 50 | 50 | 50 | 40 | — | — |
| Iisalmi – Ylivieska | | | | | | | | |
| Iisalmi – km 555,8 | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| km 555,8 – km 613,1 | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| km 613,1 – Ylivieska | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Kontiomäki – Vartius | | | | | | | | |
| Kontiomäki – Vartius | C ₁ | D4 | 80 | 80 | 80 | 80 | 80 | — |
| Kontiomäki – Pesiökyä | A | C4 | 50 | 50 | 50 | 40 | — | — |
| Pesiökyä – Ämmänsaari | A | C4 | 50 | 50 | 50 | 40 | — | — |
| Siilinjärvi – Viinijärvi | C ₂ | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Haapamäki – Jyväskylä | | | | | | | | |
| Haapamäki – Jyväskylä | B ₁ | D4 | 100 | 100 | 100 | 70 | 50 | — |
| Jyväskylä – Haapajärvi | | | | | | | | |
| Jyväskylä – Äänekoski | C ₁ | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Äänekoski – Haapajärvi | A | C4 | 60 | 60 | 50 | 40 | — | — |

| Section of line | Line category | | Passenger trains | | Freight trains | | | |
|---------------------------------------|-------------------|-----|-------------------|------------|----------------|-----|-------|-----|
| | RHK | UIC | locomotive hauled | motor cars | 16t | 20t | 22.5t | 25t |
| Kouvola – Kotka/Hamina | | | | | | | | |
| Kouvola – Juurikorpi western track | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Kouvola – Inkeroinen eastern track | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Inkeroinen – Juurikorpi eastern track | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Juurikorpi – Kotka | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Juurikorpi – Hamina | C ₁ | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Kouvola – Imatra / Vainikkala | | | | | | | | |
| Kouvola – Luumäki southern track | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Kouvola – Kaipiainen northern track | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Kaipiainen – Luumäki northern track | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Luumäki – Imatra | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Luumäki – Vainikkala | D | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Joensuu – Ilomantsi | | | | | | | | |
| | A | C4 | 50 | 50 | 50 | 40 | — | — |
| Pieksämäki – Joensuu | | | | | | | | |
| Pieksämäki – Varkaus | C ₁ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Varkaus – Joensuu | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Parikkala – Huutokoski | | | | | | | | |
| Parikkala – Savonlinna | B ₂ 1) | D4 | 110 | 110 | 110 | 90 | 80 | — |
| Savonlinna – Huutokoski | A | C4 | 50 | 50 | 50 | 40 | — | — |
| Imatra – Joensuu | | | | | | | | |
| Imatra – km 395,5 | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| km 395,5 – Säkäniemi | C ₂ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Säkäniemi – Tikkala | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Tikkala – Hammaslahti | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Hammaslahti – Joensuu | D | D4 | 140 | 140 | 120 | 120 | 100 | — |
| Imatra – Imatrankoski border | D | D4 | 60 | 60 | 60 | 60 | 60 | — |
| Säkäniemi – Niirala border | D | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Joensuu – Kontiomäki | | | | | | | | |
| Joensuu – Uimaharju | C ₂ | D4 | 120 | 120 | 120 | 120 | 100 | — |
| Uimaharju – Lieksa | C ₂ | D4 | 100 | 100 | 100 | 100 | 100 | — |
| Lieksa – Porokylä | B ₂ | D4 | 110 | 110 | 110 | 90 | 80 | — |
| Porokylä – Vuokatti | A | C4 | 50 | 50 | 50 | 40 | — | — |
| Vuokatti – Kontiomäki | B ₁ | D4 | 100 | 100 | 100 | 60 | 50 | — |
| Vuokatti – Lahnaslampi | B ₂ | D4 | 50 | 50 | 50 | 50 | 50 | — |
| Oulu – Kontiomäki | | | | | | | | |
| | C ₁ | D4 | 140 | 140 | 120 | 120 | 100 | — |

1) Bridge restrictions, see appendix 10

Secondary Lines and Sidings

- The maximum permitted speed on secondary lines and sidings is 35 km/h, unless otherwise ordered.
- On the sidings belonging to line category A, the maximum permitted speed is 20 km/h.
- On the secondary lines, the speeds indicated in Table 3 are permitted for different axle loads:

Table 3. Permitted speeds on sidings for the different axle loads.

| Section of line | Line category | | Passenger trains | Freight trains | | | |
|--|----------------|-----|------------------|----------------|-----|-------|-----|
| | RHK | UIC | | 16t | 20t | 22.5t | 25t |
| Mäntyluoto – Tahkoluoto | B ₂ | D4 | 50 | 50 | 50 | 50 | — |
| Vilppula – Mänttä | B ₁ | D4 | 50 | 50 | 50 | 50 | — |
| Lappeenranta – Port of Mustola | C ₁ | D4 | 50 | 50 | 50 | 50 | — |
| Sysmäjärvi – Vuonos | B ₂ | D4 | 35 | 35 | 35 | 35 | — |
| Mynttilä – Ristiina | A | C4 | 50 | 50 | 35 | 20 | — |
| Kiukainen – Säskylä | A | C4 | 30 | 30 | 20 | — | — |
| Jämsä – Kaipola | B ₁ | D4 | 50 | 50 | 50 | 50 | — |
| Paimenportti – Kotka Mussalo | C ₁ | D4 | 50 | 50 | 50 | 50 | — |
| Kirkniemi factory railway | B ₁ | E4 | 30 | 30 | 30 | 30 | 30 |
| Helsinki asema – West Harbour | B ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Olli – Porvoo | A | A | 50 | 35 | — | — | — |
| Lohja – Lohjanjärvi | B ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Lower railway yard of Pasila – Sörnäinen | B ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Uusikaupunki (km 266,4) – Hangonsaari | B ₁ | D4 | 30 | 30 | 30 | 30 | — |
| Pori – Ruosniemi | B ₁ | D4 | 20 | 20 | 20 | 20 | — |
| Lahti – Salpausselkä | A | C4 | 20 | 20 | 20 | 20 | — |
| Joutjärvi – Mukkula | B ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Kotka station – Port of Kotka | B ₁ | D4 | 30 | 30 | 30 | 30 | — |
| Otava – Port of Otava | B ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Varkaus – Kommila | B ₂ | D4 | 50 | 50 | 50 | 50 | — |
| Liekka – Pankakoski | A | C4 | 30 | 30 | 30 | 20 | — |
| Suonenjoki – Iisvesi | B ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Vaasa – Vaskiluoto | A | C4 | 30 | 30 | 30 | 20 | — |
| Pyhäkumpu erk.vh – Pyhäkumpu | B ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Pietarsaari – Alholma | B ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Kokkola – Ykspihlaja | C ₁ | D4 | 35 | 35 | 35 | 35 | — |
| Raahe – Rautaruukki | C ₂ | D4 | 35 | 35 | 35 | 35 | — |
| Kemi – Ajos | B ₁ | D4 | 50 | 50 | 50 | 50 | — |
| Turku freight – Turku Viheriäinen | B ₁ | D4 | 35 | 35 | 35 | 35 | — |

Wagons with Axle Loads
above the Accepted Limit

- 1) A wagon, the axle load of which exceeds the maximum axle load permitted for different axle loads, is too heavy for the line category in question.
- 2) Wagons shall not be intentionally overloaded. When an overload is discovered, the speed of train shall be reduced in accordance with Point 3. If the weight of the load exceeds the permitted load by more than 5% (by more than 2% for 25t axle load), the excess load shall be unloaded at the first possible station.
- 3) If the maximum permitted axle load of the wagon is 22.5t, overloaded wagons may be transported only with the following maximum speeds:

| Line category | Max. axle load [t] | Speed [km/h] |
|-------------------------------------|--------------------|--------------|
| A | — | — |
| B ₁ | 23.5 | 35 |
| B ₂ | 23.5 | 50 |
| C ₁ , C ₂ , D | 23.5 | 80 |

Moreover, transportation shall be carried out in accordance with the regulations for special transports. The condition of the wagons shall be inspected before transportation, especially in regard to the wheel and axle sets.

- 4) On certain lines belonging to line category A, overloaded wagons may be transported in regular traffic. The axle loads mentioned below shall not be exceeded, and the excess load shall be unloaded at the station where it is discovered. The maximum permitted speed is 40 km/h on the track and 20 km/h on K30 switches. The sections of line and the axle loads permitted on them are as follows:

| Section of line | Max. permitted axle load [t] |
|-------------------------|------------------------------|
| Parkano – Niinisalo | 20 |
| Parkano – Kihniö | 20 |
| Isokylä – Kelloseleä | 20 |
| Äänekoski – Haapajärvi | 20 |
| Murtomäki – Otanmäki | 20 |
| Kontiomäki – Ämmänsaari | 20 |
| Savonlinna – Huutokoski | 20 |
| Joensuu – Ilomantsi | 20 |
| Porokylä – Vuokatti | 20 |

- 5) On the secondary lines belonging to line category A, overloaded wagons may be transported as follows:
 - maximum axle load 20t, speed 35 km/h
 - axle load more than 20t but not more than 22.5t, speed 20 km/h
 Traffic with over 22.5t axle loads on the secondary lines belonging to line category A is forbidden.
- 6) On the sidings belonging to line category A, overloaded wagons may be transported as follows:
 - maximum axle load 22.5t, speed 20 km/h
 Traffic with over 22.5t axle loads on the sidings belonging to line category A is forbidden.

- 7) On the main lines belonging to line category A, overloaded wagons may temporarily be transported as follows:
 - maximum axle load 22.5t, speed 20 km/h
 Temporary transportation of overloaded wagons is allowed if occasional need arises. The track maintainer shall be informed of temporary transportation of overloaded wagons to check the condition of the line superstructure.
- 8) Wagons with 24.5t axle load built according to the Russian standard may be carried as special transport on the sections of line laid down separately on the conditions specified in the transport permit. Traffic on the secondary lines and sidings belonging to line category A is forbidden.
- 9) Bridge restrictions, see Appendix 10 of the Network Statement.
- 10) Wagons with axle loads above the accepted limit, other than those mentioned under (3), (4) and (5), which do not have a permanent traffic permit, are handled as special transport.


Maximum Permitted Speed on Points and Track Crossings

Table 4. Maximum permitted speed on points and track crossings.

| | Line category | | | | | |
|------------------------------------|------------------|------------------|------------------|------------------|------------------|------------------|
| | A | B1 | B2 | C1 | C2 | D |
| Straight track | | | | | | |
| Single points, 60 E 1, short | 70 | 100 | 110 | 180 | 200 | 200 |
| Single points, 60 E 1, long | — | 100 | 110 | 180 | 200 | 220 |
| Single points, 54 E 1, long | 70 | 100 | 110 | 140 | 140 | 140 |
| Single points, other | 70 | 100 | 110 | 160 | 160 | 160 |
| Three-throw points | 70 | 100 | 110 | 120 | 120 | 120 |
| Diamond crossings | 35 | 90 | 90 | 90 | 90 | 90 |
| Track crossings | 35 ¹⁾ | 90 ¹⁾ | 90 ¹⁾ | 90 ¹⁾ | 90 ¹⁾ | 90 ¹⁾ |
| Deflection track | | | | | | |
| Short points R = 165m | 20 ¹⁾ | 20 ¹⁾ | 20 ¹⁾ | 20 ¹⁾ | 20 ¹⁾ | 20 ¹⁾ |
| Short points | 35 | 35 | 35 | 35 | 35 | 35 |
| Short points when axle load is 25t | — | 10 | 20 | 20 | 20 | 35 |
| Long points | | | | | | |
| R = 530 m | 70 | 70 | 70 | — | — | — |
| R = 900 m | — | 80 | 80 | 80 | 80 | 80 |
| R = 1600 m | — | — | — | 110 | 110 | 110 |
| R = 2500 m | — | — | — | 140 | 140 | 140 |
| R = 3000 m | — | — | — | 160 | 160 | 160 |
| Non-interlocked points | | | | | | |
| Straight track | 50 | 50 | 50 | 50 | 50 | 50 |
| Deflection track | 35 | 35 | 35 | 35 | 35 | 35 |
| Trailable points | | | | | | |
| | 30 ¹⁾ | 30 ¹⁾ | 30 ¹⁾ | 30 ¹⁾ | 30 ¹⁾ | 30 ¹⁾ |

¹⁾ Indicated with speed signs

Figure 1. Line categories and electrification. Legend on the next page.



| Line category | Superstructure | | | | |
|----------------|-----------------|-------------|-------------------------|------------------------------|----------------------|
| | Non-electrified | Electrified | Rails | Sleepers | Ballast |
| A | --- | ---- | K30, K33 | wooden | gravel or equivalent |
| B ₁ | ----- | ===== | K43, 54 E 1, K60, 60 E1 | wooden | gravel or equivalent |
| B ₂ | ===== | ===== | K43, K60 | wooden, concrete | railway ballast |
| C ₁ | ===== | ===== | 54 E1 | wooden, concrete before 1987 | railway ballast |
| C ₂ | ===== | ===== | 54 E1 | concrete 1987 and after | railway ballast |
| D | ===== | ===== | 60 E1 | concrete | railway ballast |

The border of the line category is marked in the middle of the station building in the traffic operating point, unless another point is indicated by the kilometre marking.

Appendix 7

Signalling Systems

The signalling systems used on the lines are represented in the figures in this appendix. The lines on which none of the signalling systems mentioned in the figures are used, are controlled manually by the dispatchers.



Figure 1. Lines with a section blocking system.



Figure 2. Lines with a centralised traffic control systems.



Figure 3. Lines with ATP.

- Junan kokonaisuuden seurannalla
 varustettu rataosa
 Linjen med automatisk
 registrering av tågrörelsen
 Line with train detection and
 train integrity monitoring
- Radio-ohjattu rataosa
 Linjen med radioblocksystemet
 Line with a radio-controlled
 traffic system



Figure 4. Lines with train detection and train integrity monitoring or with a radio-controlled traffic system.

Appendix 8

Vibration-related Speed Restrictions

Table 1. Vibration-related speed restrictions.

| Site | km-stretch | Valid since | Speed restriction |
|------------|-------------------|-------------|---------------------------|
| Liminka | 726+900 – 729+200 | 1998 | ≥ 3000-ton trains 50 km/h |
| Koria | 182+900 – 186+400 | 2001 | ≥ 3000-ton trains 30 km/h |
| Kempele | 740+600 – 741+700 | 7.1.2002 | ≥ 3000-ton trains 50 km/h |
| Hollola | 116+200 – 118+500 | 2001 | ≥ 3000-ton trains 40 km/h |
| Lahti | 125+000 – 125+400 | 7.1.2002 | ≥ 3000-ton trains 40 km/h |
| Jokela | 47+950 – 49+950 | 1999 | ≥ 3000-ton trains 40 km/h |
| Nikkilä | 38+850 – 40+160 | 1997 | all trains 40 km/h |
| Myllykoski | 201+500 – 203+100 | 2000 | ≥ 3000-ton trains 40 km/h |
| Kurikka | 450+500 – 452+000 | 1999 | all trains 40 km/h |
| Muhos | 786+000 – 790+000 | 5.11.2002 | ≥ 3000-ton trains 60 km/h |
| Oulu | 762+800 – 763+800 | 2004 | ≥ 3000-ton trains 40 km/h |
| Turku | 271+900 – 273+700 | 1.10.2006 | ≥ 3000-ton trains 40 km/h |

Appendix 9

Maximum Permitted Train Speeds in Tunnels

| Tunnel | Maximum speed [km/h] | | |
|--------------|----------------------|-------------|-----|
| Hki - Karjaa | Single-deck | Double-deck | Sm3 |
| Espoo | | | |
| Lillgård | 160 | 120 | 180 |
| Riddarbacken | 160 | 120 | 180 |
| Karjaa-Salo | | | |
| Bäljens | 160 | 140 | 200 |
| Köpskog | 160 | 140 | 200 |
| Åminne | 160 | 140 | 200 |
| Högbacka | 160 | 140 | 200 |
| Kaivosmäki | 160 | 140 | 200 |
| Haukkamäki | 160 | 140 | 200 |
| Harmaamäki | 160 | 140 | 200 |
| Lemunmäki | 160 | 160 | 180 |
| Märjänmäki | 160 | 160 | 180 |
| Lavianmäki | 160 | 160 | 180 |
| Tottola | 160 | 120 | 180 |
| Salo-Turku | | | |
| Halikko | 160 | 140 | 200 |
| Pepallonmäki | 160 | 140 | 200 |

Appendix 10

Bridge-related Restrictions

On the bridges mentioned below, axle loads, speed or both impose restrictions on the running of rail vehicles. The speed restrictions are indicated by speed signs.

Bridges with Weight Restrictions

- 1) Kyrönsalmi bridge on the Parikkala–Savonlinna section of line:
 - Axle load restriction 22.5 t
 - Maximum permitted speed on the bridge is 20 km/h.
- 2) Seinäjoki, Kyrönjoki, Nenätönjoki, Kainastonjoki, Teuvan-joki, Närpiönjoki and Kaskistensalmi bridges on the Seinä-joki–Kaskinen section of line.
 - Axle load restriction 22.5 t
 - Maximum permitted speed on the bridge is 60 km/h.

These regulations do not apply to 6- or 8-axle wagons built to the Russian standard, which can be carried over the above-mentioned bridges only as special transport on the conditions laid down in the transport permit.

Movable Bridges

On movable bridges, the maximum permitted speed is 40 km/h, unless reduced for other reasons. If the movable bridge is locked and the rail joints are equipped with fishplates or other corresponding locking or control, the maximum speed is 60 km/h.

Table 1. Restrictions related to movable bridges.

| Bridge | Railway section | Permitted speed [km/h] |
|---------------|---------------------------|------------------------|
| Pohja | Tammisaari–Hanko | 50 |
| Kyrönsalmi | Savonlinna–Parikkala | 20 ¹ |
| Pirttiniemi | Varkaus–Viinijärvi | 40 ² |
| Taipale canal | Varkaus–Viinijärvi | 40 ² |
| Pielisjoki | Joensuu–Lieksa/Viinijärvi | 50 |
| Päiväranta | Kuopio–Iisalmi | 60 |
| Uimasalmi | Joensuu–Lieksa | 60 |
| Tahkoluoto | Pori–Tahkoluoto | 50 |

¹ See Bridges with weight restrictions

² The bridge and the rail joints can be locked, in which case the permitted speed is 60 km/h.

Appendix 11

Significant and Other Track Works Affecting Traffic in 2008

| Location | Affects traffic | Break description |
|---|-----------------|---|
| SOUTHERN FINLAND | | |
| Espoo–Turku, fundamental improvement and screening of ballast in Turku, and bridge work in Aurajoki and Paimionjoki rivers) | X | total break 1 week |
| Leppävaara–Kirkkonummi, track work at the station | X | – |
| Turku–Toijala, straightening at Kiimasuo and mainline points | X | Straightening at Kiimasuo: 8 h breaks in jointing phase |
| JKV3 track work, Hyvinkää–Karjaa | – | – |
| Ilmala railway yard | X | – |
| Central Pasila | – | – |
| EASTERN FINLAND | | |
| Lahti–Vainikkala, raising the standard between Kouvola and Luumäki | X | In May–November about 300 reservations of one or two rails, about 300 3–10 h total breaks |
| Luumäki–Joensuu, fundamental improvement, jointing in Tikkala and rail yard work | X | Jointing in Tikkala (at least a total break of 1 day) |
| Kuopio rail yard | X | – |
| Kotolahti rail yard | X | – |
| Pieksämäki–Kuopio, Suonenjoki, track work at the station | – | – |
| Kuopio–Iisalmi, rail replacement, foundation structure and mainline points | X | changes in freight traffic and replacements in passenger traffic |
| Kouvola–Kuusankoski, ballast work | X | changes in freight traffic |
| Uimaharju–Lieksa, ballast work | X | – |
| Kouvola–Kotka/Hamina, work required for 25t axle load | – | – |
| Luumäki–Imatra, work required for 25t axle load | – | – |
| Northern Savo, raising the speed limit on some parts of the track | – | – |
| WESTERN FINLAND | | |
| Jämsänkoski–Jyväskylä, tunnels, rock cuttings, ballast work, culverts and GSM-R | X | a total break 5–15 May, in April and June 20 4 h breaks, changing speed limit between Jämsänkoski and Jyväskylä in part 50/80 1–30 June |
| Weak soil at Oriselkä | X | 48 h break, preceded by 30 8 h breaks |
| Tampere passenger rail yard | X | – |
| JKV3 track work, Seinäjoki–Kaskinen | – | – |
| Seinäjoki–Oulu, raising the standard, phase I work mainly between Seinäjoki and Kokkola | X | 8 h break daily from 1 June to 30 September + 6 12 h breaks once a month, possibly also in June–November |
| Rauma signal box + remote control, Pori–Mäntyluoto signal box + remote control and Tampere remote control | – | – |
| Vilppula–Mänttä, track work | X | |

| Location | Affects traffic | Break description |
|---|-----------------|---|
| NORTHERN FINLAND | | |
| Points between Kokkola and Oulu, smart screening of ballast | X | – |
| Tornio–Kolari, ballast renewal | X | 3 week total break in summer 2008 |
| Kontiomäki–Vartius, sleeper replacement | X | 8 h breaks, duration 2 weeks |
| Building of Alholma rail yard | X | |
| OTHER BREAKS | | |
| Rail checking on sections of line Sn>140 | X | 1 h breaks in those sections of line |
| Maintenance supports and investments (points, rails, bridges, sleepers) and maintenance work separately ordered | X | Locations will be specified later. Some will require separate breaks. |

Map of Traffic Planning Areas

Coordination of track work and traffic according to the traffic planning areas shown on the map below.

Traffic Planning Areas, 22.2.2006

CONTACTS

VR Ltd., Traffic Planners

Traffic Control Centre Helsinki

liikennesuunnittelu.helsinki@vr.fi
Kovanen Timo +358 40 866 3839
Miikkola Reijo +358 40 866 3840
Pirttimäki Jouko +358 40 862 0972
Burman Raimo (4 h/weekday) +358 40 866 3846

Traffic Control Centre Tampere

liikennesuunnittelu.tampere@vr.fi
Jalanto Esko +358 40 863 0570
Kunelius Juha +358 40 863 1118

Traffic Control Centre Oulu

liikennesuunnittelu.oulu@vr.fi
Meripaasi Sakari +358 40 864 5450
Järvinen Olavi +358 40 864 5446

Traffic Control Centre Kouvola

liikennesuunnittelu.kouvola@vr.fi
Korpi Vesa +358 40 863 4197
Lahtinen Juha +358 40 863 4271

Pieksämäki (Traffic Control Centre Kouvola)

liikennesuunnittelu.pieksamaki@vr.fi
Kröger Juha +358 40 863 7002

Joensuu (Traffic Control Centre Kouvola)

liikennesuunnittelu.joensuu@vr.fi
Papunen Arto +358 40 864 0379

Traffic Control Centres

- Helsinki
- Oulu
- Tampere
- Kouvola
- Pieksämäki
- Joensuu



Appendix 12

Passenger Information at the stations of the State-owned Rail Network

RHK has acquired a new passenger information system (MIKU), which will replace the present information systems. MIKU helps the information staff to control the monitors and make announcements. In 2007 MIKU will be installed at 96 stations.

Table 1. Passenger information at the stations.

| Railway section | Information |
|--|---|
| Helsinki–Turku, Helsinki–Hyvinkää | HELMi system at the busiest stations. The system is an automatic electronic information system, giving timetable-based passenger information and information on the delays. Some of the stations are provided with only remote announcement equipment. |
| Vantaankoski line Riihimäki–Tampere | Remote announcement equipment between Pohjois-Haaga and Vantaankoski Stations are equipped with an electronic information system, giving timetable-based information and warning of passing trains and with remote announcement equipment. Riihimäki, Hämeenlinna, Toijala and Tampere have electronic timetable-based information equipment and automatic announcement equipment. |
| Toijala–Turku, Tampere–Pori, Oulu–Kontiomäki, Kouvola–Pieksämäki | Remote announcement equipment |
| Other major stations | Automatic announcement equipment |
| Other passenger stations | Mainly remote announcement equipment |
| Travel centres Seinäjoki, Jyväskylä, Kouvola, Lappeenranta, Pieksämäki, Oulu, Rovaniemi | Electronic, timetable-based information equipment, automatic announcement equipment. The system will also be used in new travel centres. |

Appendix 13

Network Statements of Other Countries

Table 1 shows the Internet addresses of the network statements published by the infrastructure managers of other countries, and the names used for the network statement. The information in the table is subject to change.

Table 1. Network statements of other countries

| Infrastructure manager | Country | Name used | Internet address |
|--|-----------------|------------------------------------|---|
| Administrador de Infraestructuras Ferroviarias (ADIF) | Spain | Declaración sobre la Red | http://www.infraestructuras-ferroviarias.com/ |
| Banedanmark | Denmark | Netredegørelse | http://www.bane.dk/visArtikel.asp?artikelID=129 |
| Banverket, Swedish National Rail Administration (BV) | Sweden | Järnvägsnåtsbeskrivning | http://www.banverket.se/templates/StandardTtH_11568.asp |
| BLS Lötschbergbahn AG (BLS) | Switzerland | Network Statement | http://www.bls.ch/unternehmen/trassen_d.html |
| Ceské Dráhy (CD) / SZCD | Czech | Network Statement | http://www.szdc.cz/english/prohlaseni_en.php |
| Chemins de fer Hélieniques / Hellenic Railways (CH-OSE) | Greece | | www.ose.gr |
| Compania Nationala De Cai Ferate S.A. (CFR) | Rumania | Documentul de referinta al retelei | http://www.cfr.ro/ |
| DB Netz AG | Germany | Schienenetz-Nutzungsbedingungen | www.db.de/track-infrastructure |
| Eurotunnel | France/England | Eurotunnel Network Statement | http://www.eurotunnel.com/ukcP3Main/ukcCorporate/ukcAboutUs/ukcDevelopment/ukpETNetworkStatement.htm |
| Gyor-Sopron-Ebenfurti Vasút Rt. / Raab-Oedenburg-Ebenfurter Eisenbahn AG | Austria/Hungary | A GySEV Zrt. Üzletszabályzata | https://www.gysev.hu/portal/page?_pageid=74,55447&_dad=portal&_schema=PORTAL&p_h_menu=5 |
| Jernbaneverket | Norway | Network Statement | www.jernbaneverket.no/marked/ |
| Infrabel | Belgium | | http://www.infrabel.be/ |
| National Railway Infrastructure Company (NRIC) | Bulgaria | Network Statement | http://rail-infra.bg/page.php?n=13 |
| Network Rail | UK | Network Statement | http://www.networkrail.co.uk/browseDirectory.aspx?dir=Network%20Statement&pageid=2891&root= |
| ÖBB Infrastruktur Betrieb AG | Austria | Schienenetz-Nutzungsbedingungen | http://www.railnet.austria.at/vip8/betrieb/de/OneStopShop/Schienenetz_nutzungsbedingungen_2006/index.jsp |
| PKP Polskie Linie Kolejowe S.A. (PKP-PLK) | Poland | Network Statement | http://www1.plk-sa.pl/en/02oferta/11.php |
| ProRail | Netherlands | Netverklaring | http://www.prorail.nl/ProRail/English/Network+Statement.htm |

| Infrastructure manager | Country | Name used | Internet address |
|--|-------------|--|---|
| Public Agency for Rail Transport of RS (ÂZP) | Slovenia | Informacij javnega znacaja | http://www.azp.si/informacije.php?jezik=ENG |
| Rede Ferroviária Nacional, | Portugal | Directorio da Rede | www.refer.pt |
| Réseau Ferré de France (RFF) | France | Document de référence du réseau ferré national | www.rff.fr |
| Rete Ferroviaria Italiana SpA (RFI) | Italy | Prospetto Informativo della Rete | www.rfi.it |
| Swiss Federal Railways SBB-Infrastructure (SBB CFF FFS) | Switzerland | Network Statement | http://mct.sbb.ch/mct/en/infrastruktur/infrastruktur_dienstleistungen/onestopshop/onestopshop-ns/onestopshop-ns1.htm |
| Société Nationale des Chemins de Fer Luxembourgeois (CFL) | Luxembourg | Document de Reference du Reseau | www.railinfra.lu |
| Železnice Slovenskej Republiky | Slovakia | Sietové vyhlá senie | http://www.zsr.sk/generate_page.php?page_id=231 |

PUBLICATION OF FINNISH
RAIL ADMINISTRATION ON F SERIES

| | |
|--------|---|
| 1/2003 | Verkkoselostus 2004 |
| 2/2003 | Luettelo rautatieliikennepaikoista 1.6.2003 |
| 3/2003 | Finnish Network Statement 2004 |
| 4/2003 | Beskrivning av Finlands bannät 2004 |
| 5/2003 | Verkkoselostus 2005 |
| 6/2003 | Finnish Network Statement 2005 |
| 7/2003 | Beskrivning av Finlands bannät 2005 |
| 1/2004 | Verkkoselostus 2006 |
| 2/2004 | Finnish Network Statement 2006 |
| 3/2004 | Beskrivning av Finlands bannät 2006 |
| 1/2005 | Luettelo rautatieliikennepaikoista 5.6.2005 |
| 2/2005 | Verkkoselostus 2007 |
| 3/2005 | Finnish Network Statement 2007 |
| 4/2005 | Beskrivning av Finlands bannät 2007 |
| 1/2006 | Verkkoselostus 2008 |
| 2/2006 | Finnish Network Statement 2008 |



**FINNISH RAIL
ADMINISTRATION**

Publisher:

Finnish Rail Administration (RHK)
PO Box 185, Keskuskatu 8, FI-00101 Helsinki
tel. +358 (0)20751 5111, fax +358 (0)20751 5108
www.rhk.fi/english

ISBN 952-445-169-7 (stapled)
ISBN 952-445-170-0 (PDF)
ISSN 1459-3831